

02-8811-13-SI
REV. NO. 0

**FINAL DRAFT
SITE INSPECTION REPORT
NTU CIRCUITS, INC.
BABYLON, NEW YORK 11704**


**PREPARED UNDER
TECHNICAL DIRECTIVE DOCUMENT NO. 02-8811-13
CONTRACT NO. 68-01-7346**

**FOR THE
ENVIRONMENTAL SERVICES DIVISION
U.S. ENVIRONMENTAL PROTECTION AGENCY**


MARCH 30, 1989

**NUS CORPORATION
SUPERFUND DIVISION**

SUBMITTED BY



**DONALD P. HESSEMER
PROJECT MANAGER**

REVIEWED/APPROVED BY


**DAVID HEIM
SITE MANAGER**


**RONALD M. NAMAN
FACILITY MANAGER**

338794



SITE NAME: NTU Circuits, Inc.
ADDRESS: 60 Dale Street
Babylon, New York 11704

EPA ID NO: NYD981562614
LATITUDE: 40° 42' 55" N
LONGITUDE: 73° 23' 28" W

1.0 SITE SUMMARY

The NTU Circuits, Inc. Site is located in a 400-acre industrial park in the northwestern portion of Babylon, Suffolk County, New York. Printed circuit boards were manufactured at the facility between 1978 and September 1983, when the company moved to another location. NTU Circuits Inc. leased the eastern portion of a building from Spectrum Finishing Corporation. The current tenant is Midmer, Inc., an assembler of pipe organs. The western portion of the building was and is leased by a welding shop, Welding Metallurgy, Inc. NTU used seven leach pools to dispose of its wastewater. The Suffolk County Department of Health Services (SCDHS) repeatedly notified NTU that its discharge was in violation of NTU's State Pollution Discharge Elimination System (SPDES) permit. Elevated levels of cadmium, copper, fluoride, iron, lead, silver and total solids were detected. The pH of the discharge was also found to be excess of New York groundwater standards.

In 1982, the Attorney General of the State of New York filed a complaint against NTU Circuits in regard to these violations of NTU's SPDES permit. The case was settled through a negotiated Stipulation of Discontinuance, which specified conditions for NTU to clean up its leach pools. The cleanup was supervised by SCDHS and Fanning, Phillips and Molnar (NTU's consultant) and was conducted by Patterson Chemical Co., a certified waste hauler.

From November 29 through December 3, 1983, liquids were drained from the leach pools and transported to NTU's new building (in North Bay Shore, New York), where they were treated in NTU's wastewater treatment system. Approximately 1 foot of sandy bottom material was removed from each leach pool. The leach pool for which NTU had its SPDES permit was treated with a lime slurry to precipitate any remaining metals. All leach pools were then lined with 1 to 2 feet of clean sand. The piping leading to the SPDES pool (SD-3) was cemented closed.

A site inspection was conducted by NUS Corporation Region 2 FIT personnel on November 30, 1988. Sediment samples were collected from four leach pools. Analytical data from these samples indicate the presence of the phthalate esters butylbenzylphthalate, bis(2-ethylhexyl)phthalate, and di-n-octylphthalate, and an estimated concentration of cadmium above that normally found in natural soils. These substances all were present in the discharge pool into which rinse water from NTU's photo darkroom was discharged. For a time, this pool had been connected to the pool designated to receive industrial discharge (pool SD-3). No organics were detected in any other samples, and inorganic substances detected were within normal ranges for natural soils. There are 4,744 residents within 1 mile of the site, and 30,236 people live within 3 miles of the site.

2.0 SITE INSPECTION NARRATIVE

2.1 EXISTING ANALYTICAL DATA

From 1979 through 1981, SCDHS collected samples of wastewater being discharged to NTU's various leach pools. SCDHS issued 18 Notifications of Unsatisfactory Industrial Waste Sampling. The highest concentrations of compounds detected, and the applicable New York State Groundwater Standards, are presented in Table 1.

Ref. No. 7

2.2 WASTE SOURCE DESCRIPTION

NTU Circuits, Inc. operated at the facility at 60 Dale St. in Babylon, New York from 1978 to September 1983. NTU's operation involved the manufacture of printed circuit boards following designs submitted by clients. The process consisted of drilling, plating, photo developing, and cleaning operations. All plating solutions were reportedly drummed and removed for disposal by a licensed waste hauler. NTU produced an average of 6,205 gallons of waste per day.

There were seven leach pools to which water was discharged from the NTU facility. These were sand-lined pits through which water infiltrated to the water table. Three of these, SD-N1, SD-2, and SD-8, reportedly only received storm runoff and roof drainage. SD-A was an older sanitary pool which received sanitary wastes from both NTU and its neighbor, Welding Metallurgy, Inc. SD-3 was the permitted (SPDES) discharge pool to which NTU released rinse water from plating processes. SD-7 received rinsewater from the photo printing operation, and was connected to SD-3 by a pipe.

A number of site inspections by the SCDHS noted the presence of foamy, bluish liquids in both SD-3 and SD-7. These findings prompted the sampling discussed in Section 2.1 above. NUS Corporation Region 2 FIT collected samples from four leach pools to characterize any residual contamination.

Ref. Nos. 2, 4, 5

2.3 GROUNDWATER ROUTE

The NTU Circuits site is entirely paved, except for the drainage pools. These drain into Pleistocene Age glacial outwash deposits of sand and gravel, with a permeability of approximately 10^{-3} cm/sec.. This formation is approximately 75 ft thick and houses the Upper Glacial Aquifer, which is under water-table conditions. Groundwater is found at approximately 15 ft below the ground surface, and, in the absence of influences from pumping, moves to the south-southeast at approximately 0.5 ft/day.

TABLE 1

**Highest Concentrations Detected in
Wastewater at NTU Circuits, Inc.**

<u>Analyte</u>	<u>Concentration(mg/L)</u>	<u>New York State Groundwater Standards (mg/L)</u>
pH (range)	3-11 (pH units)	6.5 - 8.5 (pH units)
Copper	440	1.0
Chromium	0.15	0.10
Iron	28	0.6
Cadmium	0.07	0.02
Lead	4.6	0.02
Fluoride	3.2	3.0
Silver	1.1	0.1
Total Dissolved Solids	3,983	1,000

Ref. No. 7

Beneath the glacial deposits lie the sand and silt of the Matawan Group of the Magothy Formation. The Gardiners Clay may lie between the Magothy Formation and the glacial deposits, but the Gardiners Clay is not continuous in this area of Long Island. Therefore, the Magothy Formation is hydraulically connected to the glacial outwash deposits. The Magothy is estimated to be 800 ft thick. It is recharged from percolation through the glacial deposits, and recharge generally occurs in the center of Long Island, with discharge into Long Island Sound and the Atlantic Ocean. The average annual net precipitation is 15 inches.

The aquifers underlying Long Island are the sole source of water for public supply, irrigation and industry. The Upper Glacial and Magothy aquifers act as a single hydrogeologic unit, although only the Magothy is tapped for water within 3 miles of the site. Purity of water in the Upper Glacial Aquifer may be affected by the nearby Babylon Landfill, approximately 0.25 mile east of the NTU site. There are six public water systems which draw groundwater from the Magothy within 3 miles of the site:

- Suffolk County Water Authority
- South Huntington Water District
- South Farmingdale Water Authority
- Farmingdale Village Water Authority
- East Farmingdale Water District
- Dix Hills Water District

The total population served by these six water systems is 1,046,956. The nearest wells are located approximately 6400 ft southeast of the NTU facility, at the Suffolk County Water Authority's Gordon Avenue well field.

Ref. Nos. 2, 4, 5, 12, 13, 14, 15

2.4 SURFACE WATER ROUTE

The slope of the NTU site is less than 1 percent. The slope of the surrounding area is approximately 0-2 percent toward the south. The nearest surface waters are the Neguntatogue and Santapogue Creeks, each approximately 2 miles southeast of the site. However, there are no possible contaminant migration routes to these waters, as several roads and the Long Island Rail Road interrupt the pathway. There are no surface water intakes on either of these creeks, and no other known uses. There are no sensitive environments or critical habitats within 2 miles of the site, and the 1-year, 24-hour rainfall is 3 inches.

Ref. Nos. 10, 11, 16, 17

2.5 AIR ROUTE

No readings above background were detected in the ambient air on an Organic Vapor Analyzer or an HNu Photoionization Detector during the NUS Corporation Region 2 FIT site inspection of November 30, 1988. There are no national historic sites within 1 mile of the site.

Ref. No. 2

2.6 ACTUAL HAZARDOUS CONDITIONS

There have been no documented instances of direct physical contact by humans or domestic animals with hazardous materials at the site.

Additionally:

- Contamination has not been documented either in organisms in a food chain leading to humans or in organisms directly consumed by humans.
- There have been no documented incidents of damage to flora (e.g., stressed vegetation) or to fauna (e.g., fish kill) that can be attributed to hazardous material at the facility.
- There is no documented contamination of a sewer or storm drain.
- There is no direct evidence of release of a substance of concern from the facility to the groundwater.
- There is no threat of explosion or fire hazard on site.


Ref. Nos. 2, 4, 5

3.0 MAPS AND PHOTOS

**NTU CIRCUITS, INC.
BABYLON, NEW YORK**

CONTENTS

Figure 1: Site Location Map
Figure 2: Sample Location Map
Exhibit A: Photograph Log




(QUAD) AMITYVILLE, N.Y.

SITE LOCATION MAP
NTU CIRCUITS, INC., BABYLON, N.Y.

SCALE: 1" = 2000'

FIGURE 1





LEGEND

□ SEDIMENT SAMPLE

NOTE: ALL SAMPLES PRECEDED
BY NYEA

SAMPLE LOCATION MAP

NTU CIRCUITS, INC., BABYLON, N.Y.



APPROX. SCALE (FEET)

FIGURE 2



02-8811-13-SI
Rev. No. 0

EXHIBIT A

PHOTOGRAPH LOG

NTU CIRCUITS, INC.
BABYLON, NEW YORK
NOVEMBER 30, 1988

NTU CIRCUITS, INC.
BABYLON, NEW YORK
NOVEMBER 30, 1988

PHOTOGRAPH INDEX

ALL PHOTOGRAPHS TAKEN BY DAVID HEIM

<u>Photo Number</u>	<u>Description</u>	<u>Time</u>
1P-2	NTU parking lot; two drainage pools and Babylon Landfill visible.	1055
1P-3	R. Lorring augering for sample NYEA-S5.	1125
1P-4	R. Lorring collecting sample NYEA-S4.	1150
1P-5	B. Nies filling in borehole with clean sand.	1200
1P-6	Boring into drainage pool SD-7, for sample NYEA-S3.	1215
1P-7	R. Lorring collecting sample NYEA-S3.	1240
1P-8	R. Lorring collecting duplicate samples NYEA-S1, S2.	1300

NTU CIRCUITS, INC., BABYLON, NEW YORK



1P-2

November 30, 1988
NTU parking lot; two drainage pools and Babylon Landfill
visible.

1055



1P-3

November 30, 1988
R. Lorring augering for sample NYEA-S5.

1125

NTU CIRCUITS, INC., BABYLON, NEW YORK



1P-4

November 30, 1988
R. Lorring collecting sample NYEA-S4.

1150



1P-5

November 30, 1988
B. Nies filling in borehole with clean sand.

1200

NTU CIRCUITS, INC., BABYLON, NEW YORK



1P-6

November 30, 1988

1215

Boring into drainage pool SD-7, for sample NYEA-S3.



1P-7

November 30, 1988

1240

R. Lorfin collecting sample NYEA-S3.

NTU CIRCUITS, INC., BABYLON, NEW YORK



1P-8

November 30, 1988

1300

R. Lorring collecting duplicate samples NYEA-S1, S2.

4.0 SITE INSPECTION SAMPLING RESULTS

NUS Corporation Region 2 FIT conducted a site inspection of the former NTU Circuits facility on November 30, 1988, during which four sediment samples were collected from four leach pools. These samples were subsequently analyzed to determine whether any Target Compound List (TCL) substances were present on site. Sample locations are shown in Figure 2 of Section 3.0.

No volatile organic compounds were detected in any of the samples, nor were any pesticides or polychlorinated biphenyls (PCBs) detected.

Semivolatile analysis revealed the presence of three phthalate esters in sample NYEA-S3, collected from drainage pool SD-7. Butylbenzylphthalate was detected at 3300 ug/kg, bis(2-ethylhexyl) phthalate at 9100 ug/kg, and di-n-octylphthalate at 870 ug/kg.

Results of inorganic analyses indicate the presence of most metals within normal ranges for natural soils. However, cadmium was detected in sample NYEA-S3 in a concentration estimated at 21.6 mg/kg. This value is estimated because of insufficient spike recovery in the laboratory.

Ref. Nos. 2, 3

5.0 CONCLUSIONS AND RECOMMENDATIONS

The sample NYEA-S3 contained three different phthalate esters in concentrations less than 10,000 ug/kg. The presence of these substances can not be attributed to the activities of NTU Circuits, Inc. Di-n-octylphthalate, bis-(2-ethylhexyl)phthalate, and butylbenzylphthalate are used almost exclusively as plasticizers in the manufacture of polyvinyl chloride. This activity was not undertaken at NTU Circuits, Inc., and this contamination can not be attributed to NTU.

However, cadmium was also found in sample NYEA-S3, at a concentration estimated at 21.6 mg/kg. This contaminant had been used by NTU, and indeed, SCDHS had cited NTU several times for exceeding discharge limits of cadmium.

Although the groundwater migration route is of concern in this part of Long Island, the leach pools have been excavated and refilled, and the practices which led to the contamination have ceased. Therefore, a recommendation of **NO FURTHER REMEDIAL ACTION PLANNED (NFRAP)** is made.

Ref. Nos. 3, 7

6.0 REFERENCES

1. General Sciences Corporation, Graphical Exposure Modeling System (GEMS). Landover, Maryland, 1986.
2. Field Notebook No. 0371, NTU Circuits, Inc. TDD No. 02-8811-13, Site Inspection, NUS Corporation Region 2 FIT, Edison, New Jersey. November 30, 1988.
3. U.S. EPA Contract Laboratory Program, Industrial Corrosion Management and JTC Environmental Consultants, Case No. 10959, Laboratory Analysis from NUS Corporation Region 2 FIT Site Inspection conducted on November 30, 1988.
4. EA Science and Technology, Phase 1 Investigation of NTU Circuits, Inc. prepared for New York State Department of Environmental Conservation (NYSDEC), June 1987.
5. NUS Corporation, Preliminary Assessment, NTU Circuits, Inc. March 11, 1988.
6. NYSDEC, State Pollutant Discharge Elimination System (SPDES) Permit issued to NTU Circuits, Inc. August 26, 1980.
7. Suffolk County Department of Health Services (SCDHS) Notifications of Unsatisfactory Industrial Waste Sampling issued to NTU Circuits, Inc. 1979-1981.
8. Supreme Court of the State of New York, Stipulation of Discontinuance, NTU Circuits, Inc., April 30, 1982.
9. Letter from Errol S. Kitt, Fanning, Phillips & Molnar, to Robert Abrams, Attorney General of the State of New York, February 21, 1984.
10. Three-Mile radius map, NTU Circuits, Inc. Based on U.S.G.S. 7.5 minute series maps, Amityville, Bay Shore West, Huntington, Greenlawn quadrangles topographic maps.
11. NYSDEC, Bureau of Wildlife, Significant Habitat Overlays No. 1 and 2, 1981, revised November 1985.
12. Pluhowski, E.J. and Kantrowitz, I.H., Hydrology of the Babylon-Islip Area Suffolk County, Long Island, New York. Geological Survey Water-Supply Paper 1768, 1964.
13. Jensen, H.M. and Soren, Julian. Hydrogeology of Suffolk County, Long Island, New York, 1974.
14. Soren, Julian and Cohen, Philip. Results of a Subsurface Exploration in the Mid-Island Area of Western Suffolk County, Long Island, New York, with a Section on Potential Development of Groundwater in the Mid-Island Area, U.S. Geological Survey, 1971.
15. New York State Department of Health, Bureau of Public Water Supply Protection, New York State Atlas Of Community Water Sources, 1982.
16. National Weather Service, Maps of Lake Evaporation, Annual Precipitation, and 1-year, 24-hour rainfall.
17. Telecon note: Conversation between B. Parker, SCDHS, and David Heim, NUS Corporation, March 29, 1989.

REFERENCE NO. 1

REFERENCE NO. 2

0012-F
02-8811-13

NUS CORPORATION

II

0371

NTU CIRCUITS INC.
02-8811-13
ASSIGNED TO-D. HEIM
LOGBOOK #0371
NOVEMBER 22, 1988

C-158-5-38-123

GUIDANCE FOR PROPER USE OF LOG BOOKS

Purpose

- o Serves to document on-site activities and be understandable to an outside reader.
- o Provides the basis for later written reports.
- o Used as an evidentiary document and may be used in legal proceedings.

Distribution

- o Controlled by the project manager and distributed as appropriate to personnel designated by the project manager.

General Procedures

- o Record information in language which is objective and factual.

- o Use ink. Waterproof ink is recommended.

- o Leave first two pages blank. They serve as space for the table of contents to be added when the log book is complete.

- o The first written page identifies the date, time, TDD number, site name, location, MTS personnel and their responsibilities, other non-MTS personnel and observed weather conditions.

- o Start on a new page at the start of each day's field activities. This page should identify date, time, TDD number, site name and location, MTS personnel and their responsibilities, other non-MTS personnel and observed weather conditions.

- o List all persons leaving or entering the site.

- o Information recorded in the log book should be in chronological order.

- o Sign and date each page, log all entries using a 24 hour clock. Entries should be time logged every 15 to 30 minutes.

- o Corrections are to be lined through and initialed. No erasures are to be made illegible.

- o Include a sketch or map of the site which can be used to locate photo or sample locations. Note landmarks, indicate north, and if possible include an approximate scale. Include as many sketches and maps as necessary.

Specific Field Activities To Be Documented

- o Record the who, what and where of field activities.

- o Indicate sampling and photo locations on a site sketch or map.

- o As part of the chain of custody procedures, recorded in-situ sampling information must include sample number, date, time, sampling personnel, sample type, designation of sample as a grab or composite, and any preservative used.

- o Information for in-situ measurements must include a sample ID number, the date, time, and personnel taking measurements. Personnel in-situ measurements include but are not limited to pH, temperature, conductivity, flow measurements, continuous air monitoring measurements, and stack gas analysis. If field calculations are necessary they must be checked and signed by a second team member.

- o Create a photo log to document photos taken in the field. These must include date, time, photograph, sample number, roll number, frame number, photo ID number and description. Indicate if the photo is for slides or prints in the column for roll number. Photo ID numbers can be added at the time the photo log is assembled.

- o Record onsite health and safety measures used. Describe observed potential hazards to health and safety. Document the level of protection used, decontamination procedure used and specific decontamination solutions.

- o When sampling is complete, a summary log is to be completed. It must include date, time, sample number, description, field book reference page, list, indicate whether or not the sample was split.

- o Record details regarding relevant information obtained during onsite interviews. Include names of persons interviewed, the interview group represented, their address and phone number.

- o Record any other relevant information which would be difficult to generate as a later date.

- o A person not present when field activities were being documented should read each completed page, and counter-sign and date when satisfied that the written notes are understandable.

CONTENTS

18	
3	Site Personnel
4-9	Onsite notes
21	Site map
22	Photograph log
25	Sample jar/bottle lot number
10	Post-SI observation

Susan M. Kennedy 7/21/88
David Klein 12/1/88

SITE PERSONNEL + DUTIES

D. Helm	SM
B. Nies	SSO
R. Lovfing	Sampler
K. Fendler	SMO

Susan M. Konrad 12/1/88

Randy Helm 11/30/88

1020 Arrive on site, mobilizing

BHs go to Midmen, Inc., active tenant
of building at 60 Dale St - they may pipe again.

1030 Target Safety Meeting

D. Herin	DH	11:30
B. Nies	DN	11:30
R. L. F. F.	DF	11:30/88
K. Fendler	DF	11:30-88

Workplan and QA requirements were discussed
with the above personnel.

Weather conditions: mostly DH ^{11:30}
wind 15 mph ^{~ 15 mph} ^{towards} ^{NE} approx 50°F.
~~11:30~~ ^{11:30}

Part Talk 11:30-88

Midmen Inc. make pipe again

UVA-M field only 11:25 PB
#469781 CR. label

HVH L field only 11:29 PCB
CP 40 409748
probe 409754

Steven M. Kennedy 12/1/86

David Hein
11/30/88

1170 Circuit ^{field} 0-88 11-13 1100 88
1045 B. M. ^{field} Calibrating air instruments
Minired EPA # 428522 Column needs
check.

1050 ON, DH do on-site level 3 run.
background settings OVA 1 ppm
MM 1 ppm

no readings above background down any of
down grates.

hole #2 ^{SD-7} appears to have water standing in it.
SD-2 ^{#4} " " " " " "
flat parking lot (with car) adjacent to
Crane Bldg. which was formerly occupied
(60 Dale St) approx. 18' air in use

1055 photo # 12 taken of lot, 2 down visible.
RL decomposing sample equipment.

Cats walking around site

1105 no readings above background on OVA,
Minired, MM.

B. H. D. Chirico arrives on site.

Spectrometer main office on Calist St.

well in parking lot, 2 more on
other side of Spectrometer Bldg.

Susan M. Karp

David N. Olin 11:30 88

1110 gw flow in Southwly direction here.
There's a pretest study report on Spectron
none of the drains are connected to
anything, only septic fields, according to the
DiChirico

1120 no sample will be drawn on
N side of bldg, no storm drain
inside of fence on MTU property
no readings above background on OVA, WNA, or in soil

1125 hole #1 ^{SD-2} approx 1 foot of water
standing in septic hole.
R. Lafigue pushing in auger
Sample will be collected at approx
2 feet below sediment surface.
photo #3 of R. Lafigue augering hole "1" ^{SD-2}

1130 sample S-5 collected - small amount
of top sediment dropping back into hole
sand with some gravel light tan
no air readings ^{on} above background on
sample or above liquid at 16".
(water has oil sheen)
sample drawn from 2 1/2 ^{4.5} feet below sed.
surface

Seamus McKenna 2/1/88 Daniel J. Cuccato 11:30

Soil surface 3' below surface.

Sample from 5.5 - 7.5 feet below pavement surface

1135 filling in clean soils when we removed auger hole.

1140 return to deck area to return sample & prepare for next sample location - drive #3 to SD-3 KCF collecting RSW 1

1145 drain hole #3 - soil in 3 feet below parking lot surface. SD-3 10 inch drain

in hole: approx 2' of cobble stones, 2 filled-in drain pipes leading to hole - larger opening below hole, approx 2' of dark ^{fine} sediment, then 1/2 ft of sand, much like other sample.

no readings above background on H₁₁, M₁₁ or C₁₁ V₁₁
auger hit refusal (concrete) at a depth of 8' below parking lot surface

1150 sample S-4 drawn from 6' to 8' below parking lot photo #4 of KCF collecting sample

Susan McKenney

David Heim
11-30-88

1200 photo 5 of B. Min putting clean sand into hole, R. LaFing removes grate from their hole #2

1205 at hole #2 \rightarrow SD-7
 below ground, air surface 3.5 ft
 below ground, air surface 9.5 ft
 below ground - adding another auger extension. It says the soil is very soft.

1210 1st auger bucket in black silty - hole cased in after auger removed.

this hole spreads out beneath the surface, has a drain pipe ~~to~~ leading out of building.



photo 6 of pipe

1220 begin sampling - grey black gravelly sand
 no reaction above background on HMA, OVA no mineral

sample looks oily, trace silt in sand.

odor of gasoline, but no OVA reading at hole
 oily sheen on water

Susan M. Keaney 12/1/88 David Klein 11:30 PM

1230 Sample collected from 10 - 11 feet below pavement surface

1240 photo #7 of RL collecting S-3 (ms. MSD)

1245 Open hole #1. \rightarrow SD-8
(dry hole, exposure below parking lot.)
light tan sand mottled with orange

1255 Samples S-1 and S-2 collected
from ~~4 to 10 ft~~ 11 to 12 1/2 feet
below pavement surface
no readings on OVA HMs, mixed
above background

1300 photo #8 of RL collecting
S-1 & S-2

1305 replace w/clean cover, replace
lid, return to decan area +
command post.

1325 breaking down decan area, KF
preparing samples.

1400 leave site

1700 leave samples at Federal Express

Susan M. Kennedy


David A. King
30-88

POST - \$I OBSERVATIONS

1. Discharge pool on North of site was not sampled because it is NOT on the property, ~~it is~~ not owned from present owner of property.
2. No evidence of migration potential from drainage pools other than through sand in pools.
3. No vegetation in parking lot to be stemmed.
4. No potential for direct contact ~~under~~^{12.22} to hazardous waste in drainage pool - someone would have to pull grates off of drainage pools.
5. No apparent pathway for surface water to run off - that's what the storm drains are for.

Alvin Lem 12.22.88

Dale St



Spectrum
Finishing

Spectrum
well

more
cars

Trischia
Basil &
Grand

David Klein 11/30/88

Steve McKenna 11/1/88

MTU Co. 11/30/88

PHOTO LOG

TIME	Photo #	Description
1055	1P-1, 1S-1, 1P-2, 1S-2	active parking lot, 2 of 3 stream chains visible
1125	1P-3 1S-3	R Logging, augering for S-1, S-5 at
1150	1P-4 1S-4	R Logging, collecting S-4
1200 1245	1P-5 1S-5	B Mns filling hole w/lean sand
1215	1P-6 1S-6	pipe extending into chain hole #2.
1240	1P-7 1S-7	RL collecting S-3
1300	1P-8 1S-8	RL collecting S-1, S-2

David Ham
11/30/88

Sam M. Kennedy 12/1/88

SAMPLE JAR/BOTTLE LOT NUMBERS

SAMPLE NO	VOA	TOTAL METALS	EXTRACTABLES
		(2 or Yes)	
S 1	D8200583	G8109223	G8109223
S 2 (435)	D8200583	G8109223	G8109223
S 3 (435)	D8200583	G8109223	G8109223
S 4	D8200583	G8109223	G8109223
S 5	D8200583	G8109223	G8109223
S 6	B8288063	B8288063	
S 7 (435)	B8288063	C8221063 C8238363	C8216223
S 8	B8288063	C82881063	C8216223

all containers from I-Chem

Susan McKenney 12/1/88

Rand Klein
11-25-88

REFERENCE NO. 3

- Copy of CLP Data
(Redlined & marked)

- Computer QA'd printout

Site Name: NTU Circuits, Inc.

Case : 10959

Brics #: NYEA

TDD# : 02-8811-13

SAMPLING DATE: 11/30/88

EPA CASE NO.: 10939 LAB: 10N

VOLATILES

Sample ID No.	NYEA-S1	NYEA-S2 (DUP)	NYEA-S3 (MS/MSD)	NYEA-S4	NYEA-S5	NYEA-R1M1 (MS/MSD)	NYEA-R1M2	NYEA-TDLK1
Traffic Report No.	BMB31	BMB32	BMB33	BMB34	BMB35	BMB32	BMB33	BMB36
Matrix	SOIL	SOIL	SOIL	SOIL	SOIL	WATER	WATER	WATER
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L	ug/L
Dilution Factor	1	1	5	1	1	1	1	1
Percent Moisture	8	9	24	9	18	—	—	—
Chloromethane								
Bromomethane								
Vinyl Chloride								
Chloroethane								
Methylene Chloride								
Acetone						B	B	B
Carbon Disulfide						B	B	B
1,1-Dichloroethane								
1,1-Dichloroethane								
Trans-1,2-Dichloroethane (total)								
Chloroform						J	6	6
1,2-Dichloroethane								
2-Butanone								
1,1,1-Trichloroethane							B	B
Carbon tetrachloride								
Vinyl Acetate								
Bromodichloromethane								
1,2-Dichloropropane								
cis-1,3-Dichloropropene								
Trichloroethene								
Dibromochloromethane								
1,1,2-Trichloroethane								
Benzene								
trans-1,3-Dichloropropene								
Bromoform								
4-Methyl-2-Pentanone								
2-Hexanone								
Tetrachloroethene								
Toluene						B	B	B
1,1,2,2-Tetrachloroethane								
Chlorobenzene								
Ethylbenzene								
Styrene								
Xylenes (Total)								

NOTES:

Blank space - compound analyzed for but not detected

B - compound found in lab blank as well as sample, indicates possible/probable blank contamination

E - estimated value

J - estimated value, compound present below CRQL but aboveIDL

R - analysis did not pass EPA QA/QC

N - Presumptive evidence of the presence of a compound, but can't be identified

NR - analysis not required

Detection limits elevated if Dilution Factor 11 and/or percent moisture 10%

SITE NO.: NTU-00000000
 ID#: 00000000-0000-0000-0000-00000000
 SAMPLING DATE: 11/30/88
 EPA CASE NO.: 10957 LAB: JCH

PESTICIDES

Sample ID No.	NYEA-S1	NYEA-S2 (DUP)	NYEA-S3 (MS/MSD)	NYEA-S4	NYEA-S5	NYEA-R1N1 (MS/MSD)	NYEA-R1N2	NYEA-TBLK1
Traffic Report No.	BMB31	BMB32	BMB33	BMB34	BMB35	BMB32	BMB33	BMB36
Matrix	SOIL	SOIL	SOIL	SOIL	SOIL	WATER	WATER	WATER
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L	ug/L
Dilution Factor/BPC Cleanup (Y)	1	1	5	1	1	1	1	N/A
Percent Moisture	8	9	24	9	18	—	—	N/A
alpha-BHC								NR
beta-BHC								NR
delta-BHC								NR
gamma-BHC (Lindane)								NR
Heptachlor								NR
Aldrin								NR
Heptachlor epoxide								NR
Endosulfan I								NR
Dieldrin								NR
4,4'-DDE								NR
Endrin								NR
Endosulfan II								NR
4,4'-DDD								NR
Endosulfan sulfate								NR
4,4'-DDT								NR
Methoxychlor								NR
Endrin ketone								NR
alpha-Chlordane								NR
gamma-Chlordane								NR
Toxaphene								NR
Aroclor-1016								NR
Aroclor-1221								NR
Aroclor-1232								NR
Aroclor-1242								NR
Aroclor-1248								NR
Aroclor-1254								NR
Aroclor-1260								NR

NOTES:

Blank space - compound analyzed for but not detected
 B - compound found in lab blank as well as sample, indicates possible/probable blank contamination
 E - estimated value
 J - estimated value, compound present below CREL but above IDL
 R - analysis did not pass EPA QA/QC
 N - Presumptive evidence of the presence of a compound, but can't be identified
 NR - analysis not required
 Detection limits elevated if Dilution Factor > 1 and/or percent moisture > 10%

SEMI VOLATILES

Sample ID No.	NYEA-S1	NYEA-S2 (DUP)	NYEA-S3 (NS/MSD)	NYEA-S4	NYEA-S5	NYEA-R1N1 (NS/MSD)	NYEA-R1N2	NYEA-TOLX1
Traffic Report No.	BM831	BM832	BM833	BM834	BM835	BM832	BM833	BM836
Matrix	SOIL	SOIL	SOIL	SOIL	SOIL	WATER	WATER	WATER
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L	ug/L
Dilution Factor/BPC Cleanup (Y)	1	1	2	1	1	1	1	N/A
Percent Moisture	8	9	24	9	18	--	--	N/A
Phenol								NR
bis(2-Chloroethyl)ether								NR
2-Chlorophenol								NR
1,3-Dichlorobenzene								NR
1,4-Dichlorobenzene								NR
Benzyl alcohol								NR
1,2-Dichlorobenzene								NR
2-Methylphenol								NR
bis(2-Chloroisopropyl)ether								NR
4-Methylphenol								NR
N-Nitroso-di-n-propylamine								NR
Hexachloroethane								NR
Nitrobenzene								NR
Isophorone								NR
2-Nitrophenol								NR
2,4-Dimethylphenol								NR
Benzoic acid								NR
bis(2-Chloroethoxy)methane								NR
2,4-Dichlorophenol								NR
1,2,4-Trichlorobenzene								NR
Naphthalene								NR
4-Chloroaniline								NR
Hexachlorobutadiene								NR
4-Chloro-3-Methylphenol								NR
2-Methylnaphthalene								NR
Hexachlorocyclopentadiene								NR
2,4,6-Trichlorophenol								NR
2,4,5-Trichlorophenol								NR
2-Chloronaphthalene								NR
2-Nitroaniline								NR
Dimethylphthalate								NR
Acenaphthylene								NR
2,6-Dinitrotoluene								NR
3-Nitroaniline								NR
Acenaphthene								NR
2,4-Dinitrophenol								NR
4-Nitrophenol								NR
Dibenzofuran								NR
2,4-Dinitrotoluene								NR
Diethylphthalate								NR
4-Chlorophenyl-phenyl ether								NR
Fluorene								NR
4-Nitroaniline								NR
4,6-Dinitro-2-methylphenol								NR
N-nitrosodiphenylamine								NR
4-Bromophenyl-phenyl ether								NR
Hexachlorobenzene								NR

ID: 12-881-13
 SPMPLING DATE: 11/30/88
 EPA CASE NO.: 10959 LAB: JCM

SEMI VOLATILES

Sample ID No.	NYEA-S1	NYEA-S2 (DUP)	NYEA-S3 (MS/MSD)	NYEA-S4	NYEA-S5	NYEA-R1N1 (MS/MSD)	NYEA-R1N2	NYEA-TOLK1
Traffic Report No.	BMB31	BMB32	BMB33	BMB34	BMB35	BMB32	BMB33	BMB36
Matrix	SOIL	SOIL	SOIL	SOIL	SOIL	WATER	WATER	WATER
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L	ug/L
Dilution factor/BPC Cleanup (Y)	1	1	2	1	1	1	1	N/A
Percent Moisture	8	9	24	9	18	—	—	N/A

Pentachlorophenol								NR
Phenanthrene			J					NR
Anthracene								NR
Di-n-butylphthalate								NR
Fluoranthene			J					NR
Pyrene			J					NR
Butylbenzylphthalate			3300					NR
3,3'-Dichlorobenzidine								NR
Benzo(a)anthracene								NR
Chrysene								NR
bis(2-Ethylhexyl)phthalate			9100					NR
Di-n-octylphthalate			870					NR
Benzo(b)fluoranthene								NR
Benzo(k)fluoranthene								NR
Benzo(a)pyrene								NR
Indeno(1,2,3-cd)pyrene								NR
Dibenz(a,h)anthracene								NR
Benzo(g,h,i)perylene								NR

NOTES:

Blank space - compound analyzed for but not detected
 B - compound found in lab blank as well as sample, indicates possible/probable blank contamination
 E - estimated value
 J - estimated value, compound present below CML but above IDL
 R - analysis did not pass EPA QA/QC
 N - Presumptive evidence of the presence of a compound, but can't be identified
 NR - analysis not required
 Detection limits elevated if Dilution Factor >1 and/or percent moisture >10%

SITE NAME: MTU CIRCUITS, INC.
 ID#: 02-8811-13
 SAMPLING DATE: 11/30/88
 EPA CASE NO.: 10957
 LAB NAME: JTC

INORGANICS

Sample ID No.	NYEA-S1	NYEA-S2 (DUP)	NYEA-S3 (NS/MSD)	NYEA-S4	NYEA-S5	NYEA-R1M1 (NS/MSD)	NYEA-R1M2	NYEA-TBLK1
Traffic Report No.	MBR978	MBR979	MBR980	MBR981	MBR982	MBR983	MBR984	N/A
Matrix	SOIL	SOIL	SOIL	SOIL	SOIL	WATER	WATER	N/A
Units	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	ug/L	ug/L	ug/L
Aluminum	1840 E	1730 E	947 E	1050 E	1070 E	R	R	NR
Antimony								NR
Arsenic	J	J	2.5					NR
Barium	J	J	J	J	J			NR
Beryllium								NR
Cadmium	1.3 E		21.6 E	3.2 E	2.2 E			NR
Calcium			22200	J				NR
Chromium	3.6	5.5	53.5	3.5	5.5			NR
Cobalt	J							NR
Copper	9.4 E	8.7 E	82 E	6 E				NR
Iron	3780	4990	7610	3060	3010	J	146	NR
Lead	R	R	R	R	R	R	R	NR
Magnesium	J	J	11700	J	J			NR
Manganese	R	R	R	R	R			NR
Mercury				0.13	0.63	R	R	NR
Nickel	R	R	R	R	R			NR
Potassium								NR
Selenium								NR
Silver								NR
Sodium								NR
Thallium								NR
Vanadium	J	J	J	J	J			NR
Zinc	15.5	17.1	145	15.3	9.6 E	J		NR

NOTES:

Blank space - compound analyzed for but not detected

E - estimated value

J - estimated value, compound present below CREL but above IDL

R - analysis did not pass EPA QA/QC

NR - analysis not required

02-8811-13-STR
Rev No. 0

SAMPLING TRIP REPORT

SITE NAME: NTU Circuits, Inc.
TDD NO.: 02-8811-13
SAMPLING DATE: November 30, 1988
EPA CASE NO.: 10959

1. Site Location: See Figure 1
2. Sampling Locations: See Figure 2
3. Sample Descriptions: See Table 1
4. Laboratories Receiving Samples:

Sample Type

Name and Address of Laboratory

Organic

Industrial Corrosion Management
1152 Route 10
Randolph, NJ 07869

Inorganic

JTC Environmental Consultants
4 Research Place
Suite L-10
Rockville, MD 20850

5. Sample Dispatch Data:

A total of five soil and three aqueous samples for organic analysis were shipped by FIT 2 personnel via Federal Express under airbill No. 9276045704 to Industrial Corrosion Management on November 30, 1988 at 1700 hours.

A total of five soil and two aqueous samples for inorganic analysis were shipped by FIT 2 personnel via Federal Express under Airbill No. 9276045715 to JTC Environmental Consultants on November 30, 1988 at 1700 hours.

TABLE I
SAMPLE DESCRIPTIONS
NTU Circuits, Inc.
Babylon, New York
Case No. 10959

	NUS Sample Number	CLP Organic Sample Number	CLP Inorganic Sample Number	Collection Time	Sample Type	Sample Location
2F 1-1-1	NYEA-S1	2-8 BW831	5-5 MBR978	1300	Soil	Soil sample from drainage pool SD-8; 3-4 feet below soil surface.
1-1-1	NYEA-S2**	9-9 BW832	MBR979	1300	Soil	Same location as S-1.
5-2-5	NYEA-S3*	24-24 BW833	MBR980	1230	Soil	Soil sample from drainage pool SD-7; 1-2 feet below soil surface.
1-1-1	NYEA-S4	9-9 BW834	MBR981	1150	Soil	Soil sample from drainage pool SD-3; 3-5 feet below soil surface.
1-1-1	NYEA-S5	18-18 BW835	MBR982	1130	Soil	Soil sample from drainage pool SD-2; 2-4 feet below soil surface.
1-1-1	NYEA-RIN1*	BW852	MBR983	1140	Aqueous	Trowel rinsate collected in field.
1-1-1	NYEA-RIN2	BW853	MBR984	1200	Aqueous	Auger rinsate collected in field.
1 N/A N/A	NYEA-TBLK1	N/A BW836	N/A	N/A	Aqueous	Trip blank, demonstrated analyte-free water obtained from NUS FIT 2.

* MS/MSD - Indicates that a sample was designated as a matrix spike (MS) and matrix spike duplicate (MSD) Additional sample volume was collected and shipped to the lab for MS/MSD analysis.

** Duplicate - Indicates that a sample was designated for duplicate analysis.

N/A Not Applicable

Qualification of Metals Data for the
Contract Laboratory Program
Appendix A.2: Data Assessment Narrative

Date: Dec. 1988

Number: HW-2

Revision: 8

Case# 10959 Site NTU CIRCUITS Matrix: Soil 5
Reviewer JOHN BULICH JB Lab JTC Water 2
Contractor NUS (FIT2) Other —

A.2.1 All data are of acceptable quality? Yes — No ✓

If no, exceptions are noted below with reason(s) for rejection or qualification as estimated value (J).

A) The following analytes are qualified as estimated (flagged with "J") because of not meeting the criteria:

1) CRDL labs Cd → MBR 978, 981, 982 Zn MBR 982

2) Spiked sample Cu, Mn → MBR 978-982 Cl → MBR 980
Hg → MBR 978-984

3) Lab duplicates Pb, Co → MBR 978-982

4) Field duplicates Cd → MBR 979, 983, 984

B) The following analytes are qualified as rejected (red-lined) because of not meeting the criteria:

1) Lab duplicates Hg → MBR 983, 984 Pb → MBR 983, 984
Mn, Ni → MBR 978-982

2) Field duplicates Pb → MBR 978-982

U.S. EPA - CLP

COVER PAGE - INORGANIC ANALYSES DATA PACKAGE

5 Name: ITC ENVIRONMENTAL CNSLTS.

Contract: SE-WG-0022

Code: JTC

Case No.: 10959

SAS No. :

EDC No. : MBP979

J No. : 7/97

EPA Sample No.

Lat Sample II.

MEPO78

740826

M29079

740937

MEP990

740939

MEP0000

740939D

MEP9809

7409299

34901

140939

MP9902

740000

3000000

7-42931

MEP983D

7408312

2000

7408210

MEP994

740833

ICP interelement corrections applied?

Yes/No NO

ICP background corrections applied?

Yes/No YES

If yes-were raw data generated before application of background corrections?

Yes/No NO

entis:

Use of the data contained in this hardcopy data package and in the
 later-readable data submitted on floppy diskette has been authorized by
 Laboratory Manager or the Manager's designee, as verified by the
 following signature.

E. J. [Signature]

Lab Manager:

Date: 01/03/89

COVER PAGE - IN

000002

U.S. EPA - CLP

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MEP978

Name: JTC ENVIRONMENTAL CNSLTS.

Contract: 68-W9-0029

Code: JTC

Case No.: 10959

SAS No.:

SDG No.: MEP978

Matrix (soil/water): SOIL

Lab Sample ID: 740825

Level (low/med): LOW

Date received: 12/01/98

Sludge: 92.5

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1840.0	U	*	P
7440-36-0	Antimony	10.4	U		P
7440-38-2	Arsenic	1.7	U		P
7440-39-9	Barium	6.4	U		P
7440-41-7	Beryllium	.84	U		P
7440-43-9	Cadmium	ND 1.3	U	UN*	P
7440-70-2	Calcium	214 214.0	U	*	P
7440-47-3	Chromium	3.6	U	*	P
7440-48-4	Cobalt	3.7	U	*	P
7440-50-8	Copper	9.4	U	UN*	P
7439-92-1	Lead	3780.0		*	P
7439-95-4	Magnesium	203.0	B	*	P
7439-96-5	Manganese	78.3	U	UN*	P
7439-97-6	Mercury	.11	U		CV
7440-02-0	Nickel	3.0	U	*	P
7440-09-7	Potassium	124.0	U		A
7782-49-2	Selenium	.78	U		P
7440-22-4	Silver	ND 2.0	U	UN	P
7440-23-5	Sodium	923 924.0	U		P
7440-38-0	Thallium	.48	U		P
7440-62-2	Vanadium	6.1	U		P
7440-66-6	Zinc	15.5		*	P
	Cyanide				NR

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: COLORLESS

Clarity After:

Artifacts:

Comments:

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MBP979

Name: JTC ENVIRONMENTAL CNLSLTS.

Contract: 68-W8-0023

Code: JTC

Case No.: 10959

SAS No.:

SDG No.: MBP979

Matrix (soil/water): SOIL

Lab Sample ID: 740827

Level (low/med): LOW

Date received: 12/01/88

pH: 92.0

Concentration Units (ug/L or mg/Kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1730.0		+	P
7440-06-0	Antimony	10.4			P
7440-06-2	Arsenic	1.1			P
7440-06-3	Barium	1.1			P
7440-41-7	Beryllium	1.0			P
7440-43-0	Cadmium	1.0		IN	P
7440-70-2	Calcium	1215.0		+	P
7440-47-3	Chromium	1.1		+	P
7440-48-4	Cobalt	1.0		+	P
7440-50-8	Copper	1.1		IN	P
7429-90-5	Iron	480.0			P
7429-90-5	Lead	1.1		*	P
7429-90-5	Magnesium	150.0		*	P
7429-90-5	Manganese	1.1		*	P
7429-90-5	Mercury	1.1			P
7440-02-0	Nickel	1.1		*	P
7440-09-7	Potassium	125.0			P
7782-49-2	Selenium	1.78			P
7440-22-4	Silver	1.1		IN	P
7440-23-5	Sodium	92.0			P
7440-28-0	Thallium	1.48			P
7440-62-2	Vanadium	7.0			P
7440-66-6	Zinc	17.1		*	P
	Cyanide				NR

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: COLORLESS

Clarity After:

Artifacts:

Notes:

000004

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MEP990

Name: JTC ENVIRONMENTAL CNLSLTS.

Contract: 68-W8-0028

Code: JTC

Case No.: 10959

SAS No.:

SDC No.: MEP979

Matrix (soil/water): SOIL

Lab Sample ID: 740928

Level (low/med): LOW

Date received: 12/01/99

Solids: 91.5

Concentration Units (ug/L or mg/Kg dry weight): MG/KG

CAS No.	Analyte	Concentration	Q	M
7440-00-0	Aluminum	947.0	*	U
7440-00-0	Antimony	10.0	*	U
7440-00-0	Arsenic	10.0	*	U
7440-00-0	Boron	10.0	*	U
7440-41-0	Beryllium	10.0	*	U
7440-43-0	Cadmium	31.0	*	U
7440-70-0	Calcium	12300.0	*	U
7440-47-0	Chromium	10.0	*	U
7440-48-4	Cobalt	10.0	*	U
7440-50-0	Copper	10.0	*	U
7439-98-0	Iron	7610.0	*	U
7439-98-3	Lead	10.0	*	U
7439-98-4	Magnesium	11700.0	*	U
7439-98-8	Manganese	10.0	*	U
7439-97-6	Mercury	.11	*	U
7440-03-0	Nickel	10.0	*	U
7440-09-7	Potassium	136.0	*	U
7782-49-2	Selenium	.70	*	U
7440-22-4	Silver	3.0	*	U
7440-23-5	Sodium	1030.0	*	U
7440-39-0	Thallium	.40	*	U
7440-52-2	Vanadium	7.5	*	U
7440-66-6	Zinc	145.0	*	U
	Oxide			NR

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: COLORLESS

Clarity After:

Artifacts:

Remarks:

000005

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MBP981

Name: JTC ENVIRONMENTAL CNSLTS.

Contract: 68-WS-0022

Code: JTC

Case No.: 10959

SAS No.:

SDC No.: MBP979

mat (soil/water): SOIL

Lab Sample ID: 740829

ex (low/med): LOW

Date received: 12/01/98

solids: 92.1

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1050.0		*	
7440-36-0	Antimony	10.4			
7440-38-2	Arsenic	1.1			
7440-39-3	Boron	1.1			
7440-41-7	Beryllium	10.1			
7440-43-0	Cadmium	10.1			
7440-70-9	Calcium	10.1			
7440-47-7	Chromium	10.1			
7440-48-4	Cobalt	10.1			
7440-50-9	Copper	10.1			
7440-50-9	Iron	10.1			
7440-50-9	Lead	10.1			
7440-50-9	Magnesium	10.1			
7440-50-9	Manganese	10.1			
7440-50-9	Mercury	10.1			
7440-03-0	Nickel	10.1			
7440-09-7	Potassium	10.1			
7440-48-4	Selenium	10.1			
7440-33-4	Silver	10.1			
7440-33-4	Sodium	927.0			
7440-39-3	Thallium	10.1			
7440-62-3	Vanadium	10.1			
7440-66-6	Zinc	10.1			
	Oxide				

or Before: BROWN

Clarity Before:

Texture: MEDIUM

or After: COLORLESS

Clarity After:

Artifacts:

ments:

000006

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MBP982

Name: JTC ENVIRONMENTAL CNSLTS.

Contract: 68-W8-0023

Code: JTC

Case No.: 10959

SAS No.:

SDG No.: MBP978

Matrix (soil/water): SOIL

Lab Sample ID: 740890

Level (low/med): LOW

Date received: 12/01/98

Solids: 82.9

Concentration Units (ug/L or mg/Kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1070.0		*	
7440-36-0	Antimony	11.0			
7440-38-2	Arsenic	1.3			
7440-39-0	Barium	10.0			
7440-41-7	Beryllium	0.04			
7440-43-0	Cadmium	0.03		*	
7440-70-2	Calcium	230.0		*	
7440-47-3	Chromium	10.0		*	
7440-48-4	Cobalt	10.0		*	
7440-50-8	Copper	10.0		*	
7440-51-9	Iron	2010.0			
7440-53-4	Lead	10.0		*	
7440-55-4	Manganese	10.0		*	
7440-56-4	Magnesium	10.0		*	
7440-58-3	Mercury	10.0		*	
7440-59-0	Nickel	10.0		*	
7440-60-0	Potassium	10.0			
7440-62-2	Selenium	10.0			
7440-63-4	Silver	10.0		*	
7440-63-4	Sodium	103.0			
7440-64-0	Tellurium	10.0			
7440-65-0	Vanadium	10.0			
7440-66-0	Zinc	10.0		*	
7440-67-0	Chloride	10.0			

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: COLORLESS

Clarity After:

Artifacts:

Comments:

000007

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MBP982

Name: JTC ENVIRONMENTAL CNSLTS.

Contract: 68-W2-0023

Code: JTC

Case No.: 10959

SAS No.:

EDC No.: MBP979

mat (soil/water): WATER

Lab Sample ID: 740831

ex (low/med): LOW

Date received: 12/01/88

solids: .0

Concentration Units (ug/L or mg/Kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	100.0		*	
7440-36-0	Antimony	10.0			
7440-38-2	Arsenic	10.0			
7440-39-3	Barium	10.0			
7440-41-7	Beryllium	10.0			
7440-43-9	Cadmium	10.0			
7440-70-2	Calcium	10.0			
7440-47-3	Chromium	10.0			
7440-48-4	Cobalt	10.0			
7440-50-8	Copper	10.0			
7439-89-6	Iron	10.0			
7439-92-1	Lead	10.0			
7439-95-4	Magnesium	10.0			
7439-96-5	Manganese	10.0			
7439-97-6	Mercury	10.0		*	
7440-02-0	Nickel	10.0			
7440-09-7	Potassium	10.0			
7782-49-2	Selenium	10.0			
7440-22-4	Silver	10.0			
7440-23-5	Sodium	10.0			
7440-28-0	Thallium	10.0			
7440-62-2	Vanadium	10.0			
7440-66-6	Zinc	10.0			
	Cyanide				

Ion Before: COLORLESS

Clarity Before: CLEAR

Texture:

Ion After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

000008

U.S. EPA - CLP

INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

Name: JTC ENVIRONMENTAL CNSLTS.

Contract: 68-W9-0033

MPP984

Code: JTC

Case No.: 10959

EAS No.:

EDC No.: MBR978

mat (soil/water): WATER

Lab Sample ID: 740832

el (low/med): LOW

Date received: 12/01/88

oids: .0

Concentration Units (ug/L or mg/Kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	@	M
7429-90-5	Aluminum	100.0		*	
7440-36-0	Antimony	40.0			
7440-38-2	Arsenic	10.0			
7440-39-1	Barium	10.0			
7440-41-7	Beryllium	10.0			
7440-43-6	Cadmium	4.0			
7440-70-2	Calcium	100.0			
7440-47-3	Chromium	7.0			
7440-48-4	Cobalt	14.0			
7440-50-8	Copper	10.0			
7439-96-6	Iron	140.0			
7439-96-1	Lead	1.0			
7439-96-4	Magnesium	40.0			
7439-96-5	Manganese	10.0			
7439-97-6	Mercury	1.0		*	
7440-02-0	Nickel	10.0			
7440-09-7	Potassium	10.0			
7782-49-2	Selenium	10.0			
7440-22-4	Silver	10.0			
7440-23-5	Sodium	40.0			
7440-28-0	Thallium	10.0			
7440-62-2	Vanadium	10.0			
7440-56-5	Zinc	15.0			
	Cyanide				

Before: COLORLESS

Clarity Before: CLEAR

Texture:

After: COLORLESS

Clarity After: CLEAR

Artifacts:

Notes:

000005

organic

STANDARD OPERATING PROCEDURE

Page 3

Title: Attachment 2 - CLP Data Assessment Checklist
(GC and GC/MS Analysis)
PART II: MMB Review - TOTAL REVIEW

Date: Nov. 2, 1989
Number: M--
Revision: 3

CASE # 10959 LAB ICM SITE NTL Circuits

19.0 Conclusions: (NOTE: Reviewers must red-line unacceptable data on sample data (FORM I) sheets; red-line data does not imply the compound is not present). Only the MMB reviewer has the authority to red-line unacceptable data. The letter J indicates an estimated value. In addition to the two definitions stated in the contract, it also implies that the analyte is present but the quantitative value contains an unspecified degree of error. If an accurate quantity is desired, resampling/analysis is recommended.

19.1 Data Assessment 1) Blanks are analysed along with environmental samples to determine contamination not indigenous to the samples. In the volatile fraction the method blanks contained methylene chloride, acetone, 1,1,1-trichloroethane, toluene and a TIC. The samples were flagged (u) non-detected (R) reject for the TIC: BW 831, 832, 833, 834, 835.

In the semi-volatile fraction the soil blank contained di-n-butylphthalate and some TICs. The samples were flagged (u) non-detected and (R) reject for the TICs: BW 831, 832, 833, 834, 835.

2) Calibrations are required to ensure that the instrument is capable of producing acceptable quantitative data.

19.2 Contract Problems/Non-compliance

Reviewer's Signature: Pamela Greenlaw

Date: 2/2/89

Verified By: Terry J. Burns

Date: 2/10/89

DATA ASSESSMENT : (cont.)

#10959

2/2/89 Pamela Greenlaw

In the VOA fraction the calibrations for water samples had %D/%RSD > 25/30% for acetone, 2-butanone, 4-methyl-2-pentanone and 2-hexanone. The samples were flagged (J) estimated: BW 853, 853, 853. The soil calibrations had %D/%RSD > 25/30% for chloroethane, acetone, 2-butanone and 1,1,1-trichloroethane. The samples were flagged (J) estimated: BW 831-835. The continuing calibration associated with BW 834 was also non-compliant for bromomethane and xylene which were flagged (J) estimated.

In the semivolatile fraction the initial calibration had %D/%RSD greater than 25/30% for nitrobenzene; 1,2,4-trichlorobenzene; 4-chloroaniline and 4-nitroaniline. The samples were flagged (J) estimated: BW 831-835, 852, 853. The continuing calibration associated with samples BW 831, 832, 834 and 835 had %D > 25% for 3-nitroaniline, 4-nitrophenol and hexachlorobenzene. The samples were flagged (J) estimated. The continuing calibration associated with BW 833 had %D > 25% for benzoic acid; 2,4-dichlorophenol and pyrene which were flagged (J) estimated.

3) In the pesticide fraction the laboratory had some problems with sample BW 833 (high DBC recovery, unconfirmable but for DDT, high spike recoveries). Since these all appeared to be matrix problems no action was taken.

REJECTION SUMMARY FORM
(No. of Compounds/No. of Fractions (Samples))

Type of Review: totalDate: 2/2/89Case #: 10959Project: NTU CircuitsLab Name: ICMReviewer's Initials: PJNumber of Samples: 55015/3waters**Analytes Rejected Due to Exceeding Review Criteria:**

	Surrogates	Holding Time	Calibration	Contamination	ID	Other	Total # Samples	Total # Rejected/ Total # in all Samples
Acids (15)							7	0/105
B/N (50)				5/5			7	5/350
VOA (35)				20/5			8	20/280
PEST (20)							7	0/140
PCB (7)							7	0/49
TCDD (1)								

Analytes Estimated Due to Exceeding Review Criteria for:

Acids (15)			6/5				7	6/105
B/N (50)			37/1				7	37/350
VOA (35)			30/8	30/10- 18			8	30/280
PEST (20)							7	0/140
PCB (7)							7	0/49
TCDD (1)								

ORGANIC REGIONAL DATA ASSESSMENT

CASE NO. 10959 SITE NTU Courts
LABORATORY ICM NO. OF SAMPLES/
MATRIX 3water/5soil
SDG # BW 831 REVIEWER (IF NOT ESD) NUS/FIT
SOW# _____ REVIEWER'S NAME Pamela Greenlaw
DPO: ACTION _____ FYI _____ COMPLETION DATE 2/2/89

DATA ASSESSMENT SUMMARY

	VOA	BNA	PEST	OTHER
1. HOLDING TIMES	<u>0</u>	<u>0</u>	<u>0</u>	_____
2. GC/MS TUNE/INSTR. PERFORM.	<u>0</u>	<u>0</u>	<u>0</u>	_____
3. CALIBRATIONS	<u>0</u>	<u>0</u>	<u>0</u>	_____
4. BLANKS	<u>0</u>	<u>0</u>	<u>0</u>	_____
5. SURROGATES	<u>0</u>	<u>0</u>	<u>0</u>	_____
6. MATRIX SPIKE/DUP	<u>0</u>	<u>0</u>	<u>0</u>	_____
7. OTHER QC	<u>0</u>	<u>0</u>	<u>0</u>	_____
8. INTERNAL STANDARDS	<u>0</u>	<u>0</u>	<u>0</u>	_____
9. COMPOUND IDENTIFICATION	<u>0</u>	<u>0</u>	<u>0</u>	_____
10. SYSTEM PERFORMANCE	<u>0</u>	<u>0</u>	<u>0</u>	_____
11. OVERALL ASSESSMENT	<u>0</u>	<u>0</u>	<u>0</u>	_____

O = Data had no problems/or qualified due to minor problems.
M = Data qualified due to major problems.
Z = Data unacceptable.
X = Problems, but do not affect data.

ACTION ITEMS: _____

AREAS OF CONCERN: _____

NOTABLE PERFORMANCE: _____

NTU CIRCUITS Int.
P17/ST
5 >
3 W

ICM LABORATORIES
1152 Route 10
Randolph, NJ 07869
201-584-0330
FAX #201-584-0515

January 9, 1989

Contract Number 68-W8-0046

Region II

CASE # 10959
SDG # BW831

Date of Receipt of Final Sample in SDG: 12/01/88

Samples Included:

BW831 S
BW832 S
BW833 S
BW834 S
BW835 S
BW836 W
BW852 W
BW853 W

ICM
Richard S. Levine
President

Supelco (although Di-n-butyl phthalate is not a specified matrix spike compound in the SOW).

2. Sample BW852 had a tentatively identified compound detected at 20.28 minutes. Although this compound was not detected in the corresponding method blank, it is commonly found and is a laboratory contaminant.

Pesticides/PCBs

1. On the quant reports for the Pest/PCB analyses, the injected at time says 110111 11:11. The reason for this "default" time is that the Pesticide/PCB samples are run on HP Model 5890 GC using an HP3392 integrator, which collects the data. In order to generate the diskette and form deliverables, the data file from the 3392 integrator is transferred to the GC/MS mainframe computer - the HP1000. Only data points are transferred. Other data such as date and time of injection, inject size, etc. must be manually entered into the HP1000 under the miscellaneous section. The "injected at" section of the quant report and chromatogram is entered automatically by the HP1000 computer only for those samples run on the GC/MS system.

2. On the GC primary column 2250/2401, Endrin Ketone coelutes with DBC.

3. On the GC confirmation column OV-1, Endrin Aldehyde coelutes with 4,4'DDD and breakdown was therefore reported on Form VIII Pest-1 as combined.

4. On the confirmation column, OV-1, the DBC retention time shift did not meet criteria for BW833, BW833MS, BW833MSD. We believe this is due to matrix interference by a co-eluting compound for the following reasons:

a) DBC retention times shifted very little on all samples and standards run before and after BW833, BW833MS, BW833MSD and instrumental conditions did not change.

b) DBC recoveries calculated for these samples on this column are BW833 - 884%, BW833MS - 751%, BW833MSD - 1066%. The co-eluting compound could be a phthalate as detected in the BNA analysis.

5. DBC recovery is also high (406% to 421%) for the primary column, 2250/2401, for BW833, BW833MS, BW833MSD. This is probably due to a co-eluting compound, in particular bis-(2-ethyl hexyl) phthalate, also detected in the BNA fraction.

6. Spike recoveries for heptachlor and DDT are also inflated by co-eluting compounds. If these are recalculated by subtracting the co-eluting, but unconfirmed, peaks in the unspiked sample BW833, recoveries are:

	BW833MS	BW833MSD
Heptachlor	86%	89%
DDT	61%	64%

7. On sample BW833, DDT appeared as a "hit" in the windows of both columns. We do not, however, believe this compound is present in the sample since the calculated concentration levels from the two dissimilar columns are different, 330 pg for 2250/2401 and 900 pg for OV-1.

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE

BW831

Lab Code: 10M

Contract: 88-W8-0046

Lab Code: 10M

Case No.: 10959

SAB No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 5.0 (g/mL) G

Lab File ID: A3637

Level: (low/med) LOW

Date Received: 12/ 1/83

% Moisture: not dec. B.

Date Analyzed: 12/ 9/83

Column: (pack/cap) PACK

Dilution Factor: 1.00

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

g

74-87-3	Chloromethane	11.	U
74-83-9	Bromomethane	11.	U
75-01-6	Vinyl Chloride	11.	U
75-00-3	Chloroethane	11.	U
75-08-2	Methylene Chloride	5.	U
67-64-1	Acetone	13.	U
75-15-0	Carbon Disulfide	5.	U
75-35-4	1,1-Dichloroethene	5.	U
75-34-3	1,1-Dichloroethane	5.	U
540-59-0	1,2-Dichloroethene (total)	5.	U
67-66-3	Chloroform	5.	U
107-06-2	1,2-Dichloroethane	5.	U
78-93-3	2-Butanone	11.	U
71-55-6	1,1,1-Trichloroethane	7.5	U
56-23-5	Carbon Tetrachloride	5.	U
108-05-4	Vinyl Acetate	11.	U
75-27-4	Bromodichloromethane	5.	U
78-87-5	1,2-Dichloropropane	5.	U
10061-01-5	cis-1,3-Dichloropropene	5.	U
79-01-6	Trichloroethene	5.	U
124-48-1	Dibromochloromethane	5.	U
79-00-5	1,1,2-Trichloroethane	5.	U
71-43-2	Benzene	5.	U
10061-02-6	trans-1,3-Dichloropropene	5.	U
75-25-2	Bromoform	5.	U
108-10-1	4-Methyl-2-Pentanone	11.	U
591-78-6	2-Hexanone	11.	U
127-18-4	Tetrachloroethene	5.	U
79-34-5	1,1,2,2-Tetrachloroethane	5.	U
108-88-3	Toluene	7.5	U
108-90-7	Chlorobenzene	5.	U
100-41-4	Ethylbenzene	5.	U
100-42-5	Styrene	5.	U
1330-20-7	Xylene (total)	5.	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

8W831

Sample ICM

Cont. No.: 88-WG-0046

Code: ICM

Date No.: 10950

CAS No.:

SDG No.: 8W831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 5.0 (g/mL) g

Lab File ID: A0687

Level: (low/med) LOW

Date Received: 12/ 1/88

Moisture: not dec. g.

Date Analyzed: 12/ 9/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

Number TICs found: 1

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN HEXANE ISOMER	21.60	30.	NR
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BWG3L

Lab Name: ICM

Contract: 88-W8-0048

Lab Code: ICM

Case No.: 10855

CAS No.:

SDG No.: BWG3L

Matrix: Soil/Water SOIL

Lab Sample ID:

Sample Wt/Vol: 3.0 (g/mL) G

Lab File ID: A9675

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 9.

Date Analyzed: 12/ 9/88

Column: (pack/cap) PACK

Dilution Factor: 1.50

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG C

74-87-3	-----Chloromethane	11.	U
74-83-9	-----Bromomethane	11.	U
75-01-4	-----Vinyl Chloride	11.	U
75-00-3	-----Chloroethane	11.	U
75-09-2	-----Methylene Chloride	2.5	U
67-64-1	-----Acetone	14.	U
75-15-0	-----Carbon Disulfide	5.	U
75-35-4	-----1,1-Dichloroethene	5.	U
75-34-3	-----1,1-Dichloroethane	5.	U
540-59-0	-----1,2-Dichloroethene (total)	5.	U
67-66-3	-----Chloroform	5.	U
107-06-2	-----1,2-Dichloroethane	5.	U
78-93-3	-----2-Butanone	11.	U
71-55-6	-----1,1,1-Trichloroethane	2.5	U
56-23-5	-----Carbon Tetrachloride	5.	U
108-05-4	-----Vinyl Acetate	11.	U
75-27-4	-----Bromodichloromethane	5.	U
78-87-5	-----1,2-Dichloropropane	5.	U
10061-01-5	-----cis-1,3-Dichloropropene	5.	U
79-01-6	-----Trichloroethene	5.	U
124-48-1	-----Dibromochloromethane	5.	U
79-00-5	-----1,1,2-Trichloroethane	5.	U
71-43-2	-----Benzene	5.	U
10061-02-6	-----trans-1,3-Dichloropropene	5.	U
75-25-2	-----Bromoform	5.	U
108-10-1	-----4-Methyl-2-Pentanone	11.	U
591-78-6	-----2-Hexanone	11.	U
127-18-4	-----Tetrachloroethene	5.	U
79-34-5	-----1,1,2,2-Tetrachloroethane	5.	U
108-88-3	-----Toluene	2.5	U
108-90-7	-----Chlorobenzene	5.	U
100-41-4	-----Ethylbenzene	5.	U
100-42-5	-----Styrene	5.	U
1330-20-7	-----Xylene (total)	5.	U

3 2

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. /

BW830

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

CAD No.:

SDS No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 1.0 (g/mL) G

Lab File ID: A9692

Level: (low/med) LDW

Date Received: 12/ 1/88

% Moisture: not dec. 24.

Date Analyzed: 12/ 9/88

Column: (pack/cap) PACK

Dilution Factor: 5.00

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG 0

74-87-3	-----Chloromethane	66.	U
74-83-9	-----Bromomethane	66.	U
75-01-4	-----Vinyl Chloride	66.	U
75-00-3	-----Chloroethane	66.	U
75-09-2	-----Methylene Chloride	24.33	U
67-64-1	-----Acetone	99.	U
75-15-0	-----Carbon Disulfide	33.	U
75-35-4	-----1,1-Dichloroethene	33.	U
75-34-3	-----1,1-Dichloroethane	33.	U
540-59-0	-----1,2-Dichloroethene (total)	33.	U
67-66-3	-----Chloroform	33.	U
107-06-2	-----1,2-Dichloroethane	33.	U
78-93-8	-----2-Butanone	66.	U
71-55-6	-----1,1,1-Trichloroethane	15.33	U
55-23-5	-----Carbon Tetrachloride	33.	U
108-05-4	-----Vinyl Acetate	66.	U
75-27-4	-----Bromodichloromethane	33.	U
78-87-5	-----1,2-Dichloropropane	33.	U
10061-01-5	-----cis-1,3-Dichloropropene	33.	U
79-01-6	-----Trichloroethene	33.	U
124-48-1	-----Dibromochloromethane	33.	U
79-00-5	-----1,1,2-Trichloroethane	33.	U
71-43-2	-----Benzene	33.	U
10061-02-6	-----trans-1,3-Dichloropropene	33.	U
75-25-2	-----Bromoform	33.	U
108-10-1	-----4-Methyl-2-Pentanone	66.	U
591-78-6	-----2-Hexanone	66.	U
127-18-4	-----Tetrachloroethene	33.	U
79-34-5	-----1,1,2,2-Tetrachloroethane	33.	U
108-88-3	-----Toluene	12.33	U
108-90-7	-----Chlorobenzene	33.	U
100-41-4	-----Ethylbenzene	33.	U
100-42-5	-----Styrene	33.	U
1330-20-7	-----Xylene (total)	33.	U

UNION OF ORGANIC ANALYTICAL DATA SHEET
TENTATIVELY IDENTIFIED COMPONENTS

DATA SHEET

Name: ICM

Contract: 68-WR-1145

64337

Code: ICM

Case No.: 10959

SAS No.:

SDS No.: BW831

Matrix: Soil/Water: SDIL

Lab Sample ID:

Conc. (ug/L): 1.0 (ug/mL) 3

Lab File ID: A9692

Rel: (ug/mad) LOW

Date Received: 12/1/88

Moisture: not det. 24.

Date Analyzed: 12/9/88

Comp: (ug/kg) PACH

Dilution Factor: 3.16

Number TICs found: 3

CONCENTRATION UNITS:
(ug/L or ug/kg) UG/KG

CAS NUMBER	COMPONENT NAME	RT	EST. CONC.	Q
1.	UNKNOWN HEXANE ISOMER	21.60	100.	2 R
2.	80-56-8 1,4-dichlorobenzene (ACN)	26.99	200.	J
3.	UNKNOWN HYDROCARBON	73.58	40.	J
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				
31.				
32.				
33.				
34.				
35.				
36.				
37.				
38.				
39.				
40.				
41.				
42.				
43.				
44.				
45.				
46.				
47.				
48.				
49.				
50.				

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW834

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt vol: 5.0 (g/mL) G

Lab File ID: A9707

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture (not dec): 9.

Date Analyzed: 12/10/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG G

74-87-3	-----Chloromethane	11.	U
74-83-9	-----Bromomethane	11.	UJ
75-01-4	-----Vinyl Chloride	11.	U
75-00-3	-----Chloroethane	11.	UJ
75-09-1	-----Methylene Chloride	2.5	BU
67-64-1	-----Acetone	11.	BUJ
75-15-0	-----Carbon Disulfide	5.	U
75-35-4	-----1,1-Dichloroethene	5.	U
75-34-3	-----1,1-Dichloroethane	5.	U
540-59-0	-----1,2-Dichloroethene (total)	5.	U
67-68-3	-----Chloroform	5.	U
107-08-2	-----1,2-Dichloroethane	5.	U
78-93-3	-----2-Butanone	11.	UJ
75-35-6	-----1,1,1-Trichloroethane	2.5	BUJ
56-23-5	-----Carbon Tetrachloride	5.	U
108-65-4	-----Vinyl Acetate	11.	U
75-27-4	-----Bromodichloromethane	5.	U
78-87-5	-----1,2-Dichloropropane	5.	U
10061-01-5	-----cis-1,3-Dichloropropene	5.	U
79-01-6	-----Trichloroethene	5.	U
124-48-1	-----Dibromochloromethane	5.	U
79-00-5	-----1,1,2-Trichloroethane	5.	U
71-43-2	-----Benzene	5.	U
10061-02-6	-----trans-1,3-Dichloropropene	5.	U
75-25-2	-----Bromoform	5.	U
108-10-1	-----4-Methyl-2-Pentanone	11.	U
591-78-6	-----2-Hexanone	11.	U
127-18-4	-----Tetrachloroethene	5.	U
79-04-5	-----1,1,2,2-Tetrachloroethane	5.	U
108-88-3	-----Toluene	2.5	BU
108-90-7	-----Chlorobenzene	5.	U
100-41-4	-----Ethylbenzene	5.	U
100-42-5	-----Styrene	5.	U
1330-20-7	-----Xylene (total)	5.	UJ

VOLATILE ORGANIC COMPOUNDS
 TENTATIVELY IDENTIFIED

BW501

Contract: 88-WF-0048

Lab Name: ICM

Lab Code: ICM

Case No.: 10551

CAS No.:

SDG No.: RW501

Lab Sample ID:

Lab File ID: A9707

Date Received: 12/ 1/88

Date Analyzed: 12/10/88

Dilution Factor: 1.00

Matrix: (soil/water) SOIL

Sample wt/vol: 5.0 (g/mL) G

Level: (low/med) LOW

% Moisture: not dec. 9.

Column: (pack/cap) PACK

CONCENTRATION UNITS:
 (ug/L or ug/Kg) UG/KG

Number TICs found: 1

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN HEXANE ISOMER	21.63	20.	25 R
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

FORM I VOA-TIC

1/87 Rev

ICM

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

BL0835

Lab Name: ICM

Contract: 68-W8-

Lab Code: ICM

Case No.: 10959

SAS No.:

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 5.0 (g/mL) G

Lab File ID: A9677

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 18.

Date Analyzed: 12/ 8/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
74-87-3	Chloromethane	12.	U
74-83-9	Bromomethane	12.	U
75-01-4	Vinyl Chloride	12.	U
75-00-3	Chloroethane	12.	U
75-09-2	Methylene Chloride	2.6	U
67-64-1	Acetone	17.	U
75-15-0	Carbon Disulfide	6.	U
75-35-4	1,1-Dichloroethene	6.	U
75-34-3	1,1-Dichloroethane	6.	U
540-59-0	1,2-Dichloroethene (total)	6.	U
67-66-3	Chloroform	6.	U
107-06-2	1,2-Dichloroethane	6.	U
78-93-3	2-Butanone	12.	U
71-55-6	1,1,1-Trichloroethane	2.6	U
56-23-5	Carbon Tetrachloride	6.	U
108-05-4	Vinyl Acetate	12.	U
75-27-4	Bromodichloromethane	6.	U
78-87-5	1,2-Dichloropropane	6.	U
10061-01-5	cis-1,3-Dichloropropene	6.	U
79-01-6	Trichloroethene	6.	U
124-48-1	Dibromochloromethane	6.	U
79-00-5	1,1,2-Trichloroethane	6.	U
71-43-2	Benzene	6.	U
10061-02-6	trans-1,3-Dichloropropene	6.	U
75-25-2	Bromoform	6.	U
108-10-1	4-Methyl-2-Pentanone	12.	U
591-78-6	2-Hexanone	12.	U
127-18-4	Tetrachloroethene	6.	U
79-34-5	1,1,2,2-Tetrachloroethane	6.	U
108-88-3	Toluene	2.6	U
108-90-7	Chlorobenzene	6.	U
100-41-4	Ethylbenzene	6.	U
100-42-5	Styrene	6.	U
1330-20-7	Xylene (total)	6.	U

1C
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

PTA SAMPLE ID:

BWS35

Lab Name: JCM

Contract: 68-WS-0045

Lab Code: JCM

Case No.: 10959

RAF No.:

SDG No.: BWS31

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample Wt/Vol: 5.0 (g/mL) G

Lab File ID: A9677

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 18.

Date Analyzed: 12/ 8/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Number TICS found: 6

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	D
1. - -	UNKNOWN HEXANE ISOMER	21.64	10.	NR
2. 80-56-8	.alpha.-Pinene (ACN)	28.97	10.	J
3. 1878-92-8	PROPYL CYCLOHEXANE	34.98	10.	J
4. - -	UNKNOWN	29.75	10.	J
5. - -	UNKNOWN	30.17	10.	J
6. - -	UNKNOWN	37.62	10.	J
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

FORM 1 VOA-TIC

1/87 Rev.

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW852

Contract: 68-W8-0046

Lab Name: ICM

SDG No.: BW831

Lab Code: ICM

Case No.: 10959

SAS No.:

Lab Sample ID:

Matrix: (soil/water) WATER

Lab File ID: A9649

Sample wt/vol:

5. (g/mL) ML

Date Received: 12/ 1/88

Level: (low/med) LOW

Date Analyzed: 12/ 7/88

% Moisture: not dec.100.

Dilution Factor: 1.00

Column: (pack/cap) PACK

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	0
74-87-3	-----Chloromethane	10.	10
74-83-9	-----Bromomethane	10.	10
75-01-4	-----Vinyl Chloride	10.	10
75-00-3	-----Chloroethane	10.	10
75-09-2	-----Methylene Chloride	.8	BJ
67-64-1	-----Acetone	45.	BJ
75-15-0	-----Carbon Disulfide	5.	10
75-35-4	-----1,1-Dichloroethene	5.	10
75-34-3	-----1,1-Dichloroethane	5.	10
540-59-0	-----1,2-Dichloroethene (total)	5.	10
67-66-3	-----Chloroform	5.	10
107-06-2	-----1,2-Dichloroethane	10.	10
78-93-3	-----2-Butanone	5.	10
71-55-6	-----1,1,1-Trichloroethane	5.	10
56-23-5	-----Carbon Tetrachloride	10.	10
108-05-4	-----Vinyl Acetate	5.	10
75-27-4	-----Bromodichloromethane	5.	10
78-87-5	-----1,2-Dichloropropane	5.	10
10061-01-5	-----cis-1,3-Dichloropropene	5.	10
79-01-6	-----Trichloroethene	5.	10
124-48-1	-----Dibromochloromethane	5.	10
79-00-5	-----1,1,2-Trichloroethane	5.	10
71-43-2	-----Benzene	5.	10
10061-02-6	-----trans-1,3-Dichloropropene	5.	10
75-25-2	-----Bromoform	10.	10
108-10-1	-----4-Methyl-2-Pentanone	10.	10
501-78-6	-----2-Hexanone	5.	10
127-18-4	-----Tetrachloroethene	5.	10
79-34-5	-----1,1,2,2-Tetrachloroethane	.5	BJ
108-88-3	-----Toluene	5.	10
108-90-7	-----Chlorobenzene	5.	10
100-41-4	-----Ethylbenzene	5.	10
100-42-5	-----Styrene	5.	10
1330-20-7	-----Xylene (total)		

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW852

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5. (g/mL) ML

Lab File ID: A9649

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100.

Date Analyzed: 12/ 7/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

Number TICs found: 0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

BW853

Contract: 68-W8-0046

Lab Name: ICM

SDS No.: BW831

Lab Code: ICM

Case No.: 10009

SAS No.:

Lab Sample ID:

Matrix: (soil/water) WATER

Lab File ID: A9652

Sample wt/vol: 5. (g/mL)

Date Received: 12/ 1/88

Level: (low/med) LOW

Date Analyzed: 12/ 7/88

% Moisture: not det. 100.

Dilution Factor: 1.00

Column: (pack/cap) PACK

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND		
74-87-3	Chloromethane	10.	U
74-83-9	Bromomethane	10.	U
75-01-4	Vinyl Chloride	10.	U
75-00-3	Chloroethane	10.	U
75-09-2	Methylene Chloride	4.	BJ
67-64-1	Acetone	23.	BJ
75-15-0	Carbon Disulfide	5.	U
75-35-4	1,1-Dichloroethene	5.	U
75-34-3	1,1-Dichloroethane	5.	U
540-59-0	1,2-Dichloroethene (total)	5.	U
67-66-3	Chloroform	5.	U
107-06-2	1,2-Dichloromethane	10.	U
78-93-3	2-Butanone	0.	BJ
71-55-6	1,1,1-Trichloroethane	5.	U
56-23-5	Carbon Tetrachloride	10.	U
108-05-4	Vinyl Acetate	5.	U
75-27-4	Bromodichloromethane	5.	U
78-87-5	1,2-Dichloropropane	5.	U
10061-01-5	cis-1,3-Dichloropropene	5.	U
79-01-6	Trichloroethene	5.	U
124-48-1	Dibromochloromethane	5.	U
79-00-5	1,1,2-Trichloroethane	5.	U
71-43-2	Benzene	5.	U
10061-02-6	trans-1,3-Dichloropropene	5.	U
75-25-2	Bromoform	10.	U
108-10-1	4-Methyl-2-Pentanone	10.	U
591-78-6	2-Hexanone	5.	U
127-18-4	Tetrachloroethene	5.	U
79-34-5	1,1,2,2-Tetrachloroethane	2.	BJ
108-88-3	Toluene	5.	U
108-90-7	Chlorobenzene	5.	U
100-41-4	Ethylbenzene	5.	U
100-42-5	Styrene	5.	U
1330-20-7	Xylene (total)		

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA 821-R-87-001

BW853

Contract: 68-W8-0046

Lab Name: ICM

Lab Code: ICM

Case No.: 10959

SAS No.:

SDS No.: BW831

Lab Sample ID:

Lab File ID: A9652

Date Received: 12/ 1/88

Date Analyzed: 12/ 7/88

Dilution Factor: 1.00

Matrix: (soil/water) WATER

Sample wt/vol: 5. (g/mL) ML

Level: (low/med) LOW

% Moisture: not dec.100.

Column: (pack/cap) PACK

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

Number TIDs found: 1

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN HEXANE ISOMER	21.61	10.	BJ
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

FORM I VOA-TIC

1/87 Rev.

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW836

Lab Name: ICM

Contract: 68-W3-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5. (g/mL) ML

Lab File ID: A9653

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100.

Date Analyzed: 12/ 7/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

G

74-87-3	-----Chloromethane	10.	U
74-83-9	-----Bromomethane	10.	U
75-01-4	-----Vinyl Chloride	10.	U
75-00-3	-----Chloroethane	10.	U
75-09-2	-----Methylene Chloride	4.	BJ
67-64-1	-----Acetone	74.	BJ
75-15-0	-----Carbon Disulfide	5.	U
75-35-4	-----1,1-Dichloroethene	5.	U
75-34-3	-----1,1-Dichloroethane	5.	U
540-59-0	-----1,2-Dichloroethene (total)	5.	U
67-66-3	-----Chloroform	6.	U
107-06-2	-----1,2-Dichloroethane	5.	U
78-93-3	-----2-Butanone	10.	UJ
71-55-6	-----1,1,1-Trichloroethane	3.	BJ
56-23-5	-----Carbon Tetrachloride	5.	U
108-05-4	-----Vinyl Acetate	10.	U
75-27-4	-----Bromodichloromethane	5.	U
78-87-5	-----1,2-Dichloropropane	5.	U
10061-01-5	-----cis-1,3-Dichloropropene	5.	U
79-01-6	-----Trichloroethene	5.	U
124-48-1	-----Dibromochloromethane	5.	U
79-00-5	-----1,1,2-Trichloroethane	5.	U
71-43-2	-----Benzene	5.	U
10061-02-6	-----trans-1,3-Dichloropropene	5.	U
75-25-2	-----Bromoform	5.	U
108-10-1	-----4-Methyl-2-Pentanone	10.	UJ
591-78-6	-----2-Hexanone	10.	UJ
127-18-4	-----Tetrachloroethene	5.	U
79-34-5	-----1,1,2,2-Tetrachloroethane	5.	U
106-80-3	-----Toluene	5.	BJ
108-90-7	-----Chlorobenzene	5.	U
100-41-4	-----Ethylbenzene	5.	U
100-42-5	-----Styrene	5.	U
1330-20-7	-----Xylene (total)	5.	U

12
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW836

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDS No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 5. (g/mL) ML

Lab File ID: A9653

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100.

Date Analyzed: 12/ 7/88

Column: (pack/cap) PACK

Dilution Factor: 1.00

Number TICs found: 2

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. - -	UNKNOWN	12.94	6.	J
2. - -	UNKNOWN HEXANE ISOMER	21.62	10.	BJ
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

18
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW831

Lab Name: ICM

Contract: 69-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 30. (g/mL) G

Lab File ID: 02320

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 8. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N

pH: 6.8

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

108-95-2	Phenol	360.	U
111-44-4	bis(2-Chloroethyl)ether	360.	U
95-57-8	2-Chlorophenol	360.	U
541-73-1	1,3-Dichlorobenzene	360.	U
106-46-7	1,4-Dichlorobenzene	360.	U
100-51-6	Benzyl alcohol	360.	U
95-50-1	1,2-Dichlorobenzene	360.	U
95-48-7	2-Methylphenol	360.	U
108-60-1	bis(2-Chloroisopropyl)ether	360.	U
106-44-5	4-Methylphenol	360.	U
621-64-7	N-Nitroso-di-n-propylamine	360.	U
67-72-1	Hexachloroethane	360.	U
98-95-3	Nitrobenzene	360.	U
78-59-1	Isophorone	360.	U
88-75-5	2-Nitrophenol	360.	U
105-67-9	2,4-Dimethylphenol	360.	U
65-85-0	Benzoic acid	1800.	U
111-91-1	bis(2-Chloroethoxy)methane	360.	U
120-83-2	2,4-Dichlorophenol	360.	U
120-82-1	1,2,4-Trichlorobenzene	360.	U
91-20-3	Naphthalene	360.	U
106-47-8	4-Chloroaniline	360.	U
87-68-3	Hexachlorobutadiene	360.	U
59-50-7	4-Chloro-3-methylphenol	360.	U
91-57-6	2-Methylnaphthalene	360.	U
77-47-4	Hexachlorocyclopentadiene	360.	U
88-06-2	2,4,6-Trichlorophenol	360.	U
95-95-4	2,4,5-Trichlorophenol	1800.	U
91-58-7	2-Chloronaphthalene	360.	U
38-74-4	2-Nitroaniline	1800.	U
131-11-3	Dimethylphthalate	360.	U
208-96-8	Acenaphthylene	360.	U
606-20-2	2,6-Dinitrotoluene	360.	U

10
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW831

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 30. (g/mL) G

Lab File ID: C2320

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 8. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N pH: 6.8

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
99-09-2	3-Nitroaniline	1800.	UJ
83-32-9	Acenaphthene	360.	U
51-28-5	2,4-Dinitrophenol	1800.	U
100-02-7	4-Nitrophenol	1800.	UJ
132-84-9	Dibenzofuran	360.	U
121-14-2	2,4-Dinitrotoluene	360.	U
84-66-2	Diethylphthalate	360.	U
7005-72-3	4-Chlorophenyl-phenylether	360.	U
86-73-7	Fluorene	360.	U
100-01-6	4-Nitroaniline	1800.	UJ
534-52-1	4,6-Dinitro-2-methylphenol	1800.	U
86-30-6	N-Nitrosodiphenylamine (1)	360.	U
101-55-3	4-Bromophenyl-phenylether	360.	U
118-74-1	Hexachlorobenzene	360.	UJ
87-86-5	Pentachlorophenol	1800.	U
85-01-8	Phenanthrene	360.	U
120-12-7	Anthracene	360.	U
84-74-2	Di-n-butylphthalate	360.	U
206-44-0	Fluoranthene	360.	U
129-00-0	Pyrene	360.	U
85-68-7	Butylbenzylphthalate	360.	U
91-94-1	3,3'-Dichlorobenzidine	720.	U
56-55-3	Benzo(a)anthracene	360.	U
218-01-9	Chrysene	360.	U
117-81-7	bis(2-Ethylhexyl)phthalate	360.	U
117-84-0	Di-n-octylphthalate	360.	U
205-99-2	Benzo(b)fluoranthene	360.	U
207-08-9	Benzo(k)fluoranthene	360.	U
50-32-8	Benzo(a)pyrene	360.	U
193-39-5	Indeno(1,2,3-cd)pyrene	360.	U
53-70-3	Dibenz(a,h)anthracene	360.	U
191-24-2	Benzo(g,h,i)perylene	360.	U

(1) - Cannot be separated from diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW831

Contract: 68-W8-0046

Lab Name: ICM

SDG No.: BW831

Lab Code: ICM

Case No.: 10959

SAS No.:

Lab Sample ID:

Matrix: (soil/water) SOIL

Lab File ID: 02320

Sample wt/vol: 30. (g/mL) g

Date Received: 12/ 1/88

Level: (low/med) LOW

Date Extracted: 12/ 7/88

% Moisture: not dec. 8. dec. 0.

Date Analyzed: 1/ 4/89

Extraction: (SepF/Cont/Sonc) SONC

Dilution Factor: 1.00

GPC Cleanup: (Y/N) N

pH: 6.8

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Number TICs found: 8

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 4127-47-3	Cyclopropane, 1,1,2,2-tetram	1.70	7000.	BJR
2. - -	UNKNOWN Condensation product	2.10	700.	BJR A
3. - -	UNKNOWN Condensation product	2.47	20000.	BJR A
4. - -	UNKNOWN Condensation product	3.83	900.	BJR A
5. - -	UNKNOWN Condensation product	6.50	300.	JR A
6. 1632-73-1	Bicyclo[2.2.1]heptan-2-ol, 1	8.29	200.	J
7. - -	UNKNOWN Compound	15.22	100.	J
8. - -	UNKNOWN PHTHALATE	18.18	600.	BJR
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

✓

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW832

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 30. (g/mL) G

Lab File ID: C2321

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 9. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N

pH: 6.4

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

0

108-95-2	Phenol	360.	U
111-44-4	bis(2-Chloroethyl)ether	360.	U
95-57-8	2-Chlorophenol	360.	U
541-73-1	1,3-Dichlorobenzene	360.	U
106-46-7	1,4-Dichlorobenzene	360.	U
100-51-6	Benzyl alcohol	360.	U
95-50-1	1,2-Dichlorobenzene	360.	U
95-48-7	2-Methylphenol	360.	U
108-60-1	bis(2-Chloroisopropyl)ether	360.	U
106-44-5	4-Methylphenol	360.	U
621-64-7	N-Nitroso-di-n-propylamine	360.	U
67-72-1	Hexachloroethane	360.	U
98-95-3	Nitrobenzene	360.	U
78-59-1	Isophorone	360.	U
88-75-5	2-Nitrophenol	360.	U
105-67-9	2,4-Dimethylphenol	360.	U
65-85-0	Benzoic acid	1800.	U
111-91-1	bis(2-Chloroethoxy)methane	360.	U
120-83-2	2,4-Dichlorophenol	360.	U
120-82-1	1,2,4-Trichlorobenzene	360.	U
91-20-3	Naphthalene	360.	U
106-47-8	4-Chloroaniline	360.	U
87-68-3	Hexachlorobutadiene	360.	U
59-50-7	4-Chloro-3-methylphenol	360.	U
91-57-6	2-Methylnaphthalene	360.	U
77-47-4	Hexachlorocyclopentadiene	360.	U
88-06-2	2,4,6-Trichlorophenol	360.	U
95-95-4	2,4,5-Trichlorophenol	1800.	U
91-58-7	2-Chloronaphthalene	360.	U
88-74-4	2-Nitroaniline	1800.	U
131-11-3	Dimethylphthalate	360.	U
208-96-8	Acenaphthylene	360.	U
606-20-2	2,6-Dinitrotoluene	360.	U

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW832

Contract: 68-W8-0046

Lab Name: ICM

SDG No.: BW831

Lab Code: ICM

Case No.: 10959

SAS No.:

Lab Sample ID:

Matrix: (soil/water) SOIL

Lab File ID: C2321

Sample wt/vol: 30. (g/mL) G

Date Received: 12/ 1/88

Level: (low/med) LOW

Date Extracted: 12/ 7/88

% Moisture: not dec. 9. dec. 0.

Date Analyzed: 1/ 4/89

Extraction: (SepF/Cont/Sonc) SONE

Dilution Factor: 1.00

GPC Cleanup: (Y/N) N

pH: 6.4

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO.	COMPOUND		
99-09-2	3-Nitroaniline	1800.	UJ
83-32-9	Acenaphthene	360.	U
51-28-5	2,4-Dinitrophenol	1800.	U
100-02-7	4-Nitrophenol	1800.	UJ
132-64-9	Dibenzofuran	360.	U
121-14-2	2,4-Dinitrotoluene	360.	U
84-66-2	Diethylphthalate	360.	U
7005-72-3	4-Chlorophenyl-phenylether	360.	U
96-73-7	Fluorene	1800.	UJ
100-01-6	4-Nitroaniline	1800.	U
534-52-1	4,6-Dinitro-2-methylphenol	360.	U
86-30-6	N-Nitrosodiphenylamine (1)	360.	U
101-55-3	4-Bromophenyl-phenylether	360.	UJ
118-74-1	Hexachlorobenzene	1800.	U
87-86-5	Pentachlorophenol	360.	U
85-01-8	Phenanthrene	360.	U
120-12-7	Anthracene	360.	U
84-74-2	Di-n-butylphthalate	360.	U
206-44-0	Fluoranthene	360.	U
129-00-0	Pyrene	360.	U
85-68-7	Butylbenzylphthalate	720.	U
91-94-1	3,3'-Dichlorobenzidine	360.	U
56-55-3	Benzo(a)anthracene	360.	U
218-01-9	Chrysene	360.	U
117-81-7	bis(2-Ethylhexyl)phthalate	360.	U
117-84-0	Di-n-octylphthalate	360.	U
205-99-2	Benzo(b)fluoranthene	360.	U
207-08-9	Benzo(k)fluoranthene	360.	U
50-32-8	Benzo(a)pyrene	360.	U
193-33-5	Indeno(1,2,3-cd)pyrene	360.	U
53-70-3	Dibenz(a,h)anthracene	360.	U
191-24-2	Benzo(g,h,i)perylene	360.	U

(1) - Cannot be separated from diphenylamine

FORM I SV-2

7 8

1/87 P

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW832

Contract: 68-W8-0046

Lab Name: ICM

SDS No.: BW831

Lab Code: ICM

Case No.: 10959

SAS No.:

Lab Sample ID:

Matrix: (soil/water) SOIL

Lab File ID: C2321

Sample wt/vol: 30. (g/mL) G

Date Received: 12/ 1/88

Level: (low/med) LOW

Date Extracted: 12/ 7/88

% Moisture: not dec. 9. dec. 0.

Date Analyzed: 1/ 4/89

Extraction: (SepF/Cont/Sonc) SONC

Dilution Factor: 1.00

GPC Cleanup: (Y/N) N pH: 6.4

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Number TICs found: 10

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 4127-47-3	Cyclopropane, 1,1,2,2-tetram	1.63	100.	BJR
2. - -	UNKNOWN Condensation product	1.78	200.	BJR A
3. - -	UNKNOWN Condensation product	2.22	5000.	BJR A
4. - -	UNKNOWN Condensation product	3.88	2000.	BJR A
5. - -	UNKNOWN Compound	6.29	600.	J
6. - -	UNKNOWN Condensation product	6.52	300.	J R A
7. 74367-34-3	Propanoic acid, 2-methyl-, 3	12.36	100.	J
8. - -	UNKNOWN Compound	15.24	100.	J
9. - -	UNKNOWN PHTHALATE	18.20	1000.	BJR
10. 4337-65-9	Hexanedioic acid, mono(2-eth	23.11	200.	BJR
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

BW833

Name: 107

Contract: 66-W8-0046

Code: 107

Case No.: 10959

SAS No.:

SDG No.: BW801

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt.: 31. (g/mL) G

Lab File ID: 02830

Vel: low med. LOW

Date Received: 12/ 1/86

Moisture: not dec. 24. dec. 14.

Date Extracted: 12/ 7/86

traction: SepF/Cont/Stone) SONG

Date Analyzed: 1/ 5/86

D Cleanup: 100% N pH: 7.7

Dilution Factor: 1.

CONCENTRATION UNITS:

CHG: 107 COMPOUND (ug/L or ug/Kg) UG/KG 3

103-35-2	Phenol	860.	U
111-44-4	Bis(2-Chloroethyl)ether	860.	U
105-57-6	2-Chlorophenol	860.	U
141-73-1	1,3-Dichlorobenzene	860.	U
106-48-7	1,4-Dichlorobenzene	860.	U
100-51-6	Benzyl alcohol	860.	U
93-83-1	1,2-Dichlorobenzene	860.	U
98-42-7	2-Methylphenol	860.	U
102-60-1	Bis(2-Chloroisopropyl)ether	860.	U
123-11-5	4-Methylphenol	860.	U
821-64-7	N-Nitroso-di-n-propylamine	860.	U
174-71-1	Hexachloroethane	860.	U
98-95-2	Nitrobenzene	860.	U
132-21-1	Isophorone	220.	U
85-75-5	2-Nitrophenol	860.	U
121-27-3	2,4-Dimethylphenol	860.	U
65-85-0	Benzoic acid	4300.	U
111-91-1	Bis(2-Chloroethoxy)methane	860.	U
120-83-2	2,4-Dichlorophenol	860.	U
120-82-1	1,2,4-Trichlorobenzene	860.	U
91-20-3	Naphthalene	860.	U
106-47-8	4-Chloroaniline	860.	U
67-68-3	Hexachlorobutadiene	860.	U
33-50-7	4-Chloro-3-methylphenol	860.	U
31-57-6	2-Methylnaphthalene	860.	U
77-47-4	Hexachlorocyclopentadiene	860.	U
86-06-2	2,4,6-Trichlorophenol	860.	U
93-13-4	2,4,5-Trichlorophenol	4300.	U
91-58-7	2-Chloronaphthalene	860.	U
83-74-4	2-Nitroaniline	4300.	U
131-11-3	Dimethylnthalate	860.	U
135-98-5	Acenaphthylene	860.	U
600-20-2	2,6-Dinitrotoluene	860.	U

BW631

Contract: 68-W8-0046

Lab Name: ICM

Case No.: 10951

CAS No.:

SDG No.: BW631

Lab Code: ICM

Lab Sample ID:

Matrix: (soil/water) SOIL

Lab File ID: 02330

Sample wt/vol: 31. (g/mL) 3

Date Received: 12/ 1/68

Level: (low/med) LOW

Date Extracted: 12/ 7/68

Moisture: not dec. 24. dec. 14.

Date Analyzed: 1/ 5/69

Extraction: (SepF/Cont/Sond) SONC

Dilution Factor: 2.00

SPC Cleanup: (Y/N) N pH: 7.7

CONCENTRATION UNITS:
(ug/L or ug/kg) UG/KG

CAS NO.	COMPOUND		
09-09-2	3-Nitroaniline	4300.	10
63-32-3	Acenaphthene	860.	10
51-25-5	2,4-Dinitrophenol	4300.	10 J
100-02-7	4-Nitrophenol	4300.	10
181-84-9	Dibenzofuran	860.	10
121-14-2	2,4-Dinitrotoluene	860.	10
84-66-2	Diethylphthalate	860.	10
1005-72-0	4-Chlorophenyl phenylether	860.	10
86-73-7	Fluorene	4300.	10 J
100-01-6	4-Nitroaniline	4300.	10
534-52-1	4,6-Dinitro-2-methylphenol	860.	10
56-30-0	N-Nitrosodiphenylamine (1)	860.	10
31-55-3	4-Bromophenyl phenylether	860.	10
16-74-1	Hexachlorobenzene	4300.	10
87-86-5	Pentachlorophenol	360.	10
85-01-3	Phenanthrene	860.	10
120-12-7	Anthracene	360.	10
84-74-2	Di-n-butylphthalate	170.	10
206-44-0	Fluoranthene	280.	10
120-00-0	Pyrene	3300.	10
85-68-7	Butylbenzylphthalate	1700.	10
51-34-1	3,3'-Dichlorobenzidine	860.	10
56-55-3	Benzo(a)anthracene	860.	10
113-01-9	Chrysene	9100.	10
117-81-7	bis(2-Ethylhexyl)phthalate	870.	10
117-81-0	Di-n-octylphthalate	860.	10
205-99-2	Benzo(b)fluoranthene	360.	10
207-00-3	Benzo(k)fluoranthene	860.	10
50-32-8	Benzo(a)pyrene	360.	10
193-35-5	Indeno(1,2,3-cd)pyrene	860.	10
53-70-3	Dibenz(a,h)anthracene	860.	10
191-24-2	Benzo(g,h,i)perylene	860.	10

(1) - Cannot be separated from diphenylamine

SEMI-VOLATILE ORGANIC ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

34-11

Lab Name: ICM

Contract: 68-W8-004a

Lab Code: ICM

Case No.: 10555

SAS No.:

EDG No.: BWB31

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 31. (g/mL) G

Lab File ID: 02330

Level: (low/med) LOW

Date Received: 12/ 1/86

% Moisture: not dec. 24. dec. 14.

Date Extracted: 12/ 7/86

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 5/89

GPC Cleanup: (Y/N) N

pH: 7.7

Dilution Factor: 1.00

CONCENTRATION UNITS:

(ug/L or ug/kg) 33/ 1

Number TICs found: 28

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	- - UNKNOWN Condensation product	1.35	3000.	BCR A
2.	- - UNKNOWN Condensation product	2.40	60000.	BCR A
3.	- - UNKNOWN Condensation product	3.60	1000.	BCR A
4.	1120-21-4 Undecane	8.07	1000.	J
5.	7045-71-8 Undecane, 2-methyl- (801901)	9.31	5000.	J
6.	17301-28-9 Undecane, 3,6-dimethyl- (801	10.01	2000.	J
7.	62108-21-8 Decane, 6-ethyl-2-methyl- (9	11.35	6100.	J
8.	74645-38-0 Dodecane, 2,7,10-trimethyl-	12.40	1000.	J
9.	- - UNKNOWN HYDROCARBON	12.75	4000.	J
10.	3891-98-3 Dodecane, 2,6,10-trimethyl-	14.04	5000.	J
11.	- - UNKNOWN HYDROCARBON	14.38	2000.	J
12.	- - UNKNOWN HYDROCARBON	14.65	1000.	J
13.	- - UNKNOWN HYDROCARBON	14.78	1000.	J
14.	544-76-3 Hexadecane (801901)	15.23	4000.	J
15.	- - UNKNOWN HYDROCARBON	15.78	6000.	J
16.	- - UNKNOWN HYDROCARBON	16.33	5000.	J
17.	1921-70-8 Pentadecane, 2,6,10,14-tetra	16.44	3000.	J
18.	21164-95-4 Hexadecane, 7,9-dimethyl- (6	17.46	3000.	J
19.	638-36-8 Hexadecane, 2,6,10,14-tetra	17.54	3000.	J
20.	629-32-5 Nonadecane (801901)	18.43	3000.	J
21.	112-95-6 Eicosane (801901)	19.48	6000.	J
22.	- - UNKNOWN HYDROCARBON	20.19	1000.	J
23.	54030-48-8 Heptadecane, 2,6,10,14-tetra	20.43	7000.	J
24.	- - UNKNOWN HYDROCARBON	21.33	5000.	J
25.	- - UNKNOWN HYDROCARBON	21.40	3000.	J
26.	- - UNKNOWN HYDROCARBON	23.04	1000.	J
27.	7210-64-1 Heptadecane, 9-octyl	23.84	2000.	J
28.	- - UNKNOWN Cholesterol isomer	23.13	1000.	J
29.				
30.				

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW834

Lab Name: ICM

Contract: 68-WB-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 31. (g/mL) G

Lab File ID: 02322

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 9. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N

pH: 7.2

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

108-95-2	Phenol	360.	U
111-44-4	bis(2-Chloroethyl)ether	360.	U
95-57-8	2-Chlorophenol	360.	U
541-73-1	1,3-Dichlorobenzene	360.	U
106-46-7	1,4-Dichlorobenzene	360.	U
100-51-6	Benzyl alcohol	360.	U
95-50-1	1,2-Dichlorobenzene	360.	U
95-48-7	2-Methylphenol	360.	U
108-60-1	bis(2-Chloroisopropyl)ether	360.	U
106-44-5	4-Methylphenol	360.	U
621-64-7	N-Nitroso-di-n-propylamine	360.	U
67-72-1	Hexachloroethane	360.	U
98-95-3	Nitrobenzene	360.	U
78-59-1	Isophorone	360.	U
88-75-5	2-Nitrophenol	360.	U
105-67-9	2,4-Dimethylphenol	360.	U
65-85-0	Benzoic acid	1800.	U
111-91-1	bis(2-Chloroethoxy)methane	360.	U
120-83-2	2,4-Dichlorophenol	360.	U
120-82-1	1,2,4-Trichlorobenzene	360.	U
91-20-3	Naphthalene	360.	U
106-47-8	4-Chloroaniline	360.	U
87-68-3	Hexachlorobutadiene	360.	U
59-50-7	4-Chloro-3-methylphenol	360.	U
91-57-6	2-Methylnaphthalene	360.	U
77-47-4	Hexachlorocyclopentadiene	360.	U
88-06-2	2,4,6-Trichlorophenol	360.	U
95-95-4	2,4,5-Trichlorophenol	1800.	U
91-58-7	2-Chloronaphthalene	360.	U
88-74-4	2-Nitroaniline	1800.	U
131-11-3	Dimethylphthalate	360.	U
208-96-8	Acenaphthylene	360.	U
606-20-2	2,6-Dinitrotoluene	360.	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW834

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 31. (g/mL) G

Lab File ID: C2322

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 9. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N

pH: 7.3

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

99-09-2-----	3-Nitroaniline	1800.	UJ
83-32-9-----	Acenaphthene	360.	U
51-28-5-----	2,4-Dinitrophenol	1800.	U
100-02-7-----	4-Nitrophenol	1800.	UJ
132-64-9-----	Dibenzofuran	360.	U
121-14-2-----	2,4-Dinitrotoluene	360.	U
84-66-2-----	Diethylphthalate	360.	U
7005-72-3-----	4-Chlorophenyl-phenylether	360.	U
86-73-7-----	Fluorene	360.	U
100-01-6-----	4-Nitroaniline	1800.	UJ
534-52-1-----	4,6-Dinitro-2-methylphenol	1800.	U
86-30-6-----	N-Nitrosodiphenylamine (1)	360.	U
101-55-3-----	4-Bromophenyl-phenylether	360.	U
118-74-1-----	Hexachlorobenzene	360.	UJ
87-86-5-----	Pentachlorophenol	1800.	U
85-01-8-----	Phenanthrene	360.	U
120-12-7-----	Anthracene	360.	U
84-74-2-----	Di-n-butylphthalate	360.	U
206-44-0-----	Fluoranthene	360.	U
129-00-0-----	Pyrene	360.	U
85-68-7-----	Butylbenzylphthalate	360.	U
91-94-1-----	3,3'-Dichlorobenzidine	720.	U
56-55-3-----	Benzo(a)anthracene	360.	U
218-01-9-----	Chrysene	360.	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	360.	U
117-84-0-----	Di-n-octylphthalate	360.	U
205-99-2-----	Benzo(b)fluoranthene	360.	U
207-08-9-----	Benzo(k)fluoranthene	360.	U
50-32-8-----	Benzo(a)pyrene	360.	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	360.	U
53-70-3-----	Dibenz(a,h)anthracene	360.	U
191-24-2-----	Benzo(g,h,i)perylene	360.	U

(1) - Cannot be separated from diphenylamine

1F
SEMI-VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW934

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample Wt/vol: 31. (g/mL) G

Lab File ID: 02322

Level: (low/med) LOW

Date Received: 12/ 1/88

Moisture: not dec. 9. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

PC Cleanup: (Y/N) N

pH: 7.3

Dilution Factor: 1.00

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/KG

Number TICs found: 10

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. - -	UNKNOWN Condensation product	1.82	300.	BJR A
2. - -	UNKNOWN Condensation product	2.28	10000.	BJR A
3. - -	UNKNOWN Condensation product	3.92	3000.	BJR A
4. - -	UNKNOWN Condensation product	6.52	400.	JR A
5. - -	UNKNOWN Compound	12.03	100.	J
6. 74067-34-3	Propanoic acid, 2-methyl-, 3	12.34	200.	J
7. - -	UNKNOWN Compound	15.23	200.	J
8. 55045-11-9	Tridecane, 5-propyl- (9CI)	16.50	100.	J
9. - -	UNKNOWN PHTHALATE	18.19	1000.	BJR
10. 4307-65-9	Hexanedioic acid, mono(2-eth	23.09	100.	BJR
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW825

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 34. (g/mL) G

Lab File ID: 02323

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 18. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N

pH: 7.1

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

108-95-2-----	Phenol	360.	U
111-44-4-----	bis(2-Chloroethyl)ether	360.	U
95-57-8-----	2-Chlorophenol	360.	U
541-73-1-----	1,3-Dichlorobenzene	360.	U
106-46-7-----	1,4-Dichlorobenzene	360.	U
100-51-6-----	Benzyl alcohol	360.	U
95-50-1-----	1,2-Dichlorobenzene	360.	U
95-48-7-----	2-Methylphenol	360.	U
108-60-1-----	bis(2-Chloroisopropyl) ether	360.	U
106-44-5-----	4-Methylphenol	360.	U
621-64-7-----	N-Nitroso-di-n-propylamine	360.	U
67-72-1-----	Hexachloroethane	360.	U
98-95-3-----	Nitrobenzene	360.	U
78-59-1-----	Isophorone	360.	U
88-75-5-----	2-Nitrophenol	360.	U
105-67-9-----	2,4-Dimethylphenol	360.	U
65-85-0-----	Benzoic acid	1800.	U
111-91-1-----	bis(2-Chloroethoxy)methane	360.	U
120-83-2-----	2,4-Dichlorophenol	360.	U
120-82-1-----	1,2,4-Trichlorobenzene	360.	U
91-20-3-----	Naphthalene	360.	U
106-47-8-----	4-Chloroaniline	360.	U
87-68-3-----	Hexachlorobutadiene	360.	U
59-50-7-----	4-Chloro-3-methylphenol	360.	U
91-57-6-----	2-Methylnaphthalene	360.	U
77-47-4-----	Hexachlorocyclopentadiene	360.	U
88-06-2-----	2,4,6-Trichlorophenol	360.	U
95-95-4-----	2,4,5-Trichlorophenol	1800.	U
91-58-7-----	2-Chloronaphthalene	360.	U
88-74-4-----	2-Nitroaniline	1800.	U
131-11-3-----	Dimethylphthalate	360.	U
208-96-8-----	Acenaphthylene	360.	U
606-20-2-----	2,6-Dinitrotoluene	360.	U

10
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW835

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDS No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 34. (g/mL) G

Lab File ID: C2323

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 18. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

GPC Cleanup: (Y/N) N

pH: 7.1

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

99-09-2-----	3-Nitroaniline	1800.	UJ
83-32-9-----	Acenaphthene	360.	U
51-28-5-----	2,4-Dinitrophenol	1800.	U
100-02-7-----	4-Nitrophenol	1800.	UJ
132-64-9-----	Dibenzofuran	360.	U
121-14-2-----	2,4-Dinitrotoluene	360.	U
84-66-2-----	Diethylphthalate	360.	U
7005-72-3-----	4-Chlorophenyl-phenylether	360.	U
86-73-7-----	Fluorene	360.	U
100-01-6-----	4-Nitroaniline	1800.	UJ
534-52-1-----	4,6-Dinitro-2-methylphenol	1800.	U
86-30-6-----	N-Nitrosodiphenylamine (1)	360.	U
101-55-3-----	4-Bromophenyl-phenylether	360.	U
118-74-1-----	Hexachlorobenzene	360.	UJ
87-86-5-----	Pentachlorophenol	1800.	U
85-01-8-----	Phenanthrene	360.	U
120-12-7-----	Anthracene	360.	U
84-74-2-----	Di-n-butylphthalate	360.	U
206-44-0-----	Fluoranthene	360.	U
129-00-0-----	Pyrene	360.	U
85-68-7-----	Butylbenzylphthalate	360.	U
91-94-1-----	3,3'-Dichlorobenzidine	720.	U
56-55-3-----	Benzo(a)anthracene	360.	U
218-01-9-----	Chrysene	360.	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	360.	U
117-84-0-----	Di-n-octylphthalate	360.	U
205-99-2-----	Benzo(b)fluoranthene	360.	U
207-08-9-----	Benzo(k)fluoranthene	360.	U
50-32-8-----	Benzo(a)pyrene	360.	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	360.	U
53-70-3-----	Dibenz(a,h)anthracene	360.	U
191-24-2-----	Benzo(g,h,i)perylene	360.	U

(1) - Cannot be separated from diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW835

Sample Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 34. (g/mL) G

Lab File ID: 02323

Level: (low/med) LOW

Date Received: 12/ 1/88

Moisture: not dec. 18. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 1/ 4/89

PC Cleanup: (Y/N) N

pH: 7.1

Dilution Factor: 1.00

Number TICs found: 13

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 4127-47-3	Cyclopropane, 1,1,2,2-tetram	1.67	5000.	BJR
2. - -	UNKNOWN Condensation product	1.81	200.	BJR A
3. - -	UNKNOWN Condensation product	2.27	9000.	BJR A
4. - -	UNKNOWN Condensation product	2.71	100.	JR A
5. - -	UNKNOWN Condensation product	3.92	2000.	BJR A
6. - -	UNKNOWN Compound	6.33	600.	J
7. - -	UNKNOWN Condensation product	6.53	500.	JR A
8. - -	UNKNOWN Compound	7.35	100.	J
9. 74017-34-3	Propanoic acid, 2-methyl-, 3	12.35	200.	J
10. - -	UNKNOWN Compound	15.22	200.	J
11. - -	UNKNOWN PHTHALATE	18.18	1000.	BJR
12. - -	UNKNOWN HYDROCARBON	19.32	300.	J
13. 4337-65-9	Hexanedioic acid, mono(2-eth	23.10	200.	BJR
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO. ✓

BW852

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 1000. (g/mL) ML

Lab File ID: C2310

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100. dec. 0.

Date Extracted: 12/ 2/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 1/ 3/89

GPC Cleanup: (Y/N) N

pH: 5.8

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO. COMPOUND

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
108-95-2	Phenol	10.	U
111-44-4	bis(2-Chloroethyl)ether	10.	U
95-57-8	2-Chlorophenol	10.	U
541-73-1	1,3-Dichlorobenzene	10.	U
106-46-7	1,4-Dichlorobenzene	10.	U
100-51-6	Benzyl alcohol	10.	U
95-50-1	1,2-Dichlorobenzene	10.	U
95-48-7	2-Methylphenol	10.	U
108-60-1	bis(2-Chloroisopropyl)ether	10.	U
106-44-5	4-Methylphenol	10.	U
621-64-7	N-Nitroso-di-n-propylamine	10.	U
67-72-1	Hexachloroethane	10.	U
98-95-3	Nitrobenzene	10.	U
78-59-1	Isophorone	10.	U
88-75-5	2-Nitrophenol	10.	U
105-67-9	2,4-Dimethylphenol	10.	U
65-85-0	Benzoic acid	50.	U
111-91-1	bis(2-Chloroethoxy)methane	10.	U
120-83-2	2,4-Dichlorophenol	10.	U
120-82-1	1,2,4-Trichlorobenzene	10.	U
91-20-3	Naphthalene	10.	U
106-47-8	4-Chloroaniline	10.	U
87-68-3	Hexachlorobutadiene	10.	U
59-50-7	4-Chloro-3-methylphenol	10.	U
91-57-6	2-Methylnaphthalene	10.	U
77-47-4	Hexachlorocyclopentadiene	10.	U
88-06-2	2,4,6-Trichlorophenol	10.	U
95-95-4	2,4,5-Trichlorophenol	50.	U
91-58-7	2-Chloronaphthalene	10.	U
88-74-4	2-Nitroaniline	50.	U
131-11-3	Dimethylphthalate	10.	U
208-96-8	Acenaphthylene	10.	U
606-20-2	2,6-Dinitrotoluene	10.	U

10
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW852

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 1000. (g/mL) ML

Lab File ID: C2310

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100. dec. 0.

Date Extracted: 12/ 2/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 1/ 3/89

GPC Cleanup: (Y/N) N

pH: 5.8

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/L

Q

99-09-2-----	3-Nitroaniline	50.	U
83-32-9-----	Acenaphthene	10.	U
51-28-5-----	2,4-Dinitrophenol	50.	U
100-02-7-----	4-Nitrophenol	50.	U
132-64-9-----	Dibenzofuran	10.	U
121-14-2-----	2,4-Dinitrotoluene	10.	U
84-66-2-----	Diethylphthalate	10.	U
7005-72-3-----	4-Chlorophenyl-phenylether	10.	U
86-73-7-----	Fluorene	10.	U
100-01-6-----	4-Nitroaniline	50.	U
534-52-1-----	4,6-Dinitro-2-methylphenol	50.	U
86-30-6-----	N-Nitrosodiphenylamine (1)	10.	U
101-55-3-----	4-Bromophenyl-phenylether	10.	U
118-74-1-----	Hexachlorobenzene	10.	U
87-86-5-----	Pentachlorophenol	50.	U
85-01-8-----	Phenanthrene	10.	U
120-12-7-----	Anthracene	10.	U
84-74-2-----	Di-n-butylphthalate	10.	U
206-44-0-----	Fluoranthene	10.	U
129-00-0-----	Pyrene	10.	U
85-68-7-----	Butylbenzylphthalate	10.	U
91-94-1-----	3,3'-Dichlorobenzidine	20.	U
56-55-3-----	Benzo(a)anthracene	10.	U
218-01-9-----	Chrysene	10.	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10.	U
117-84-0-----	Di-n-octylphthalate	10.	U
205-99-2-----	Benzo(b)fluoranthene	10.	U
207-08-9-----	Benzo(k)fluoranthene	10.	U
50-32-8-----	Benzo(a)pyrene	10.	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10.	U
53-70-3-----	Dibenz(a,h)anthracene	10.	U
191-24-2-----	Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EP- SAMPLE NO.

BW851

Lab Name: ICM

Contract: 68-W8-0048

Lab Code: ICM

Case No.: 10959

SAS No.:

SDS No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 1000. (g/mL) ML

Lab File ID: 00310

Level: (low/med) LOW

Date Received: 12/ 1/88

Moisture: not dec.100. dec. 0.

Date Extracted: 12/ 2/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 1/ 3/89

IPC Cleanup: (Y/N) N

pH: 5.5

Dilution Factor: 1.00

Number TICs found: 2

CONCENTRATION UNITS:
(ug/L or ug/kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. - -	UNKNOWN Compound	20.28	10.	J
2. 1569-02-4	2-Propanol, 1-methoxy-	6.41	10.	BC
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW853

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 1000. (g/mL) ML

Lab File ID: C2011

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100. dec. 0.

Date Extracted: 12/ 2/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 1/ 3/89

GPC Cleanup: (Y/N) N

pH: 6.4

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

108-95-2	Phenol	10.	U
111-44-4	bis(2-Chloroethyl)ether	10.	U
95-57-8	2-Chlorophenol	10.	U
541-73-1	1,3-Dichlorobenzene	10.	U
106-46-7	1,4-Dichlorobenzene	10.	U
100-51-6	Benzyl alcohol	10.	U
95-50-1	1,2-Dichlorobenzene	10.	U
95-48-7	2-Methylphenol	10.	U
108-60-1	bis(2-Chloroisopropyl)ether	10.	U
106-44-5	4-Methylphenol	10.	U
621-64-7	N-Nitroso-di-n-propylamine	10.	U
67-72-1	Hexachloroethane	10.	U
98-95-3	Nitrobenzene	10.	U
78-59-1	Isophorone	10.	U
88-75-5	2-Nitrophenol	10.	U
105-67-9	2,4-Dimethylphenol	10.	U
65-85-0	Benzoic acid	50.	U
111-91-1	bis(2-Chloroethoxy)methane	10.	U
120-83-2	2,4-Dichlorophenol	10.	U
120-82-1	1,2,4-Trichlorobenzene	10.	U
91-20-3	Naphthalene	10.	U
106-47-8	4-Chloroaniline	10.	U
87-68-3	Hexachlorobutadiene	10.	U
59-50-7	4-Chloro-3-methylphenol	10.	U
91-57-6	2-Methylnaphthalene	10.	U
77-47-4	Hexachlorocyclopentadiene	10.	U
88-06-2	2,4,6-Trichlorophenol	10.	U
95-95-4	2,4,5-Trichlorophenol	50.	U
91-58-7	2-Chloronaphthalene	10.	U
88-74-4	2-Nitroaniline	50.	U
131-11-3	Dimethylphthalate	10.	U
208-96-8	Acenaphthylene	10.	U
606-20-2	2,6-Dinitrotoluene	10.	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW853

Lab Name: ICM

Contract: 68-WB-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 1000. (g/mL) ML

Lab File ID: C2311

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100. dec. 0.

Date Extracted: 12/ 2/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 1/ 3/89

GPC Cleanup: (Y/N) N

pH: 6.4

Dilution Factor: 1.00

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

99-09-2	3-Nitroaniline	50.	U
83-32-9	Acenaphthene	10.	U
51-28-5	2,4-Dinitrophenol	50.	U
100-02-7	4-Nitrophenol	50.	U
132-64-9	Dibenzofuran	10.	U
121-14-2	2,4-Dinitrotoluene	10.	U
84-66-2	Diethylphthalate	10.	U
7005-72-3	4-Chlorophenyl-phenylether	10.	U
86-73-7	Fluorene	10.	U
100-01-6	4-Nitroaniline	50.	U
534-52-1	4,6-Dinitro-2-methylphenol	50.	U
86-30-6	N-Nitrosodiphenylamine (1)	10.	U
101-55-3	4-Bromophenyl-phenylether	10.	U
118-74-1	Hexachlorobenzene	10.	U
87-86-5	Pentachlorophenol	50.	U
85-01-8	Phenanthrene	10.	U
120-12-7	Anthracene	10.	U
84-74-2	Di-n-butylphthalate	10.	U
206-44-0	Fluoranthene	10.	U
129-00-0	Pyrene	10.	U
85-68-7	Butylbenzylphthalate	10.	U
91-94-1	3,3'-Dichlorobenzidine	20.	U
56-55-3	Benzo(a)anthracene	10.	U
218-01-9	Chrysene	10.	U
117-81-7	bis(2-Ethylhexyl)phthalate	10.	U
117-84-0	Di-n-octylphthalate	10.	U
205-99-2	Benzo(b)fluoranthene	10.	U
207-08-9	Benzo(k)fluoranthene	10.	U
50-32-8	Benzo(a)pyrene	10.	U
193-39-5	Indeno(1,2,3-cd)pyrene	10.	U
53-70-3	Dibenz(a,h)anthracene	10.	U
191-24-2	Benzo(g,h,i)perylene	10.	U

(1) - Cannot be separated from diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

BW853

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) WATER

Lab Sample ID:

Sample wt/vol: 1000. (g/mL) ML

Lab File ID: C2311

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec.100. dec. 0.

Date Extracted: 12/ 2/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 1/ 3/89

GPC Cleanup: (Y/N) N

pH: 6.4

Dilution Factor: 1.00

Number TICs found: 1

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 1569-02-4	2-Propanol, 1-ethoxy- (8CI9C)	6.41	10.	BJ
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW831

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 30. (g/mL) G

Lab File ID: D0720

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 8. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 12/15/88

GPC Cleanup: (Y/N) N pH: 6.8

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO.

COMPOUND

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
319-84-6	alpha-BHC	8.6	U
319-85-7	beta-BHC	8.6	U
319-86-8	delta-BHC	8.6	U
58-89-9	gamma-BHC (Lindane)	8.6	U
76-44-8	Heptachlor	8.6	U
309-00-2	Aldrin	8.6	U
1024-57-3	Heptachlor epoxide	8.6	U
959-98-8	Endosulfan I	17.	U
60-57-1	Dieldrin	17.	U
72-55-9	4,4'-DDE	17.	U
72-20-8	Endrin	17.	U
33213-65-9	Endosulfan II	17.	U
72-54-8	4,4'-DDD	17.	U
1031-07-8	Endosulfan sulfate	17.	U
50-29-3	4,4'-DDT	86.	U
72-43-5	Methoxychlor	17.	U
53494-70-5	Endrin ketone	86.	U
5103-71-9	alpha-Chlordane	86.	U
5103-74-2	gamma-Chlordane	86.	U
8001-35-2	Toxaphene	170.	U
12674-11-2	Aroclor-1016	86.	U
11104-28-2	Aroclor-1221	86.	U
11141-16-5	Aroclor-1232	86.	U
53469-21-9	Aroclor-1242	86.	U
12672-29-6	Aroclor-1248	86.	U
11097-69-1	Aroclor-1254	170.	U
11096-82-5	Aroclor-1260	170.	U

PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW831

Name: ICM

Contract: 68-W8-0046

Site: ICM

Case No.: 10959

SAS No.:

SDS No.: BW831

Media: (soil/water) SOIL

Lab Sample ID:

Conc: wt/vol: 30. (g/mL) G

Lab File ID: D0716

Exposure: (low/med) LOW

Date Received: 12/ 1/88

Exposure: not dec. 9. dec. 0.

Date Extracted: 12/ 7/88

Action: (SepF/Cont/Sonc) SONC

Date Analyzed: 12/15/88

Cleanup: (Y/N) N

pH: 6.4

Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO.

COMPOUND

(ug/L or ug/Kg) UG/KG

Q

319-84-6	alpha-BHC	8.6	U
319-85-7	beta-BHC	8.6	U
319-86-8	delta-BHC	8.6	U
58-89-9	gamma-BHC (Lindane)	8.6	U
76-44-8	Heptachlor	8.6	U
309-00-2	Aldrin	8.6	U
1024-57-3	Heptachlor epoxide	8.6	U
359-98-8	Endosulfan I	8.6	U
60-57-1	Dieldrin	17.	U
72-55-9	4,4'-DDE	17.	U
72-20-8	Endrin	17.	U
30213-65-9	Endosulfan II	17.	U
72-54-8	4,4'-DDD	17.	U
1031-07-8	Endosulfan sulfate	17.	U
50-29-3	4,4'-DDT	17.	U
72-43-5	Methoxychlor	86.	U
30494-70-5	Endrin ketone	17.	U
101-0-71-9	alpha-Chlordane	86.	U
101-0-74-2	gamma-Chlordane	86.	U
101-0-35-2	Toxaphene	170.	U
101-0-11-2	Aroclor-1016	86.	U
101-0-18-2	Aroclor-1221	86.	U
101-0-16-5	Aroclor-1232	86.	U
101-0-21-9	Aroclor-1242	86.	U
101-0-23-6	Aroclor-1248	86.	U
101-0-29-1	Aroclor-1254	170.	U
101-0-81-5	Aroclor-1260	170.	U

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW833

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 31. (g/mL) G

Lab File ID: D0713

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 24. dec. 14.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 12/14/88

GPC Cleanup: (Y/N) N

pH: 7.7

Dilution Factor: 5.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/KG Q

319-84-6-----	alpha-BHC	51.	U
319-85-7-----	beta-BHC	51.	U
319-86-8-----	delta-BHC	51.	U
58-89-9-----	gamma-BHC (Lindane)	51.	U
76-44-8-----	Heptachlor	51.	U
309-00-2-----	Aldrin	51.	U
1024-57-3-----	Heptachlor epoxide	51.	U
959-98-8-----	Endosulfan I	51.	U
60-57-1-----	Dieldrin	100.	U
72-55-9-----	4,4'-DDE	100.	U
72-20-8-----	Endrin	100.	U
33213-65-9-----	Endosulfan II	100.	U
72-54-8-----	4,4'-DDD	100.	U
1031-07-8-----	Endosulfan sulfate	100.	U
50-29-3-----	4,4'-DDT	100.	U
72-43-5-----	Methoxychlor	510.	U
53494-70-5-----	Endrin ketone	100.	U
5103-71-9-----	alpha-Chlordane	510.	U
5103-74-2-----	gamma-Chlordane	510.	U
8001-35-2-----	Toxaphene	1000.	U
12674-11-2-----	Aroclor-1016	510.	U
11104-28-2-----	Aroclor-1221	510.	U
11141-16-5-----	Aroclor-1232	510.	U
53469-21-9-----	Aroclor-1242	510.	U
12672-29-6-----	Aroclor-1248	510.	U
11097-69-1-----	Aroclor-1254	1000.	U
11096-82-5-----	Aroclor-1260	1000.	U

504

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: ICM

Contract: 68-W8-0046

BW834

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 31. (g/mL) G

Lab File ID: D0719

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 9. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 12/15/88

GPC Cleanup: (Y/N) N

pH: 7.3

Dilution Factor: 1.00

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	
---------	----------	---	--

319-84-6	alpha-BHC	8.6	U
319-85-7	beta-BHC	8.6	U
319-86-8	delta-BHC	8.6	U
58-89-9	gamma-BHC (Lindane)	8.6	U
76-44-8	Heptachlor	8.6	U
309-00-2	Aldrin	8.6	U
1024-57-3	Heptachlor epoxide	8.6	U
959-98-8	Endosulfan I	8.6	U
60-57-1	Dieldrin	17.	U
72-55-9	4,4'-DDE	17.	U
72-20-8	Endrin	17.	U
33213-65-9	Endosulfan II	17.	U
72-54-8	4,4'-DDD	17.	U
1031-07-8	Endosulfan sulfate	17.	U
50-29-3	4,4'-DDT	17.	U
72-43-5	Methoxychlor	86.	U
53494-70-5	Endrin ketone	17.	U
5103-71-9	alpha-Chlordane	86.	U
5103-74-2	gamma-Chlordane	86.	U
8001-35-2	Toxaphene	170.	U
12674-11-2	Aroclor-1016	86.	U
11104-28-2	Aroclor-1221	86.	U
11141-16-5	Aroclor-1232	86.	U
53469-21-9	Aroclor-1242	86.	U
12672-29-6	Aroclor-1248	86.	U
11097-69-1	Aroclor-1254	170.	U
11096-82-5	Aroclor-1260	170.	U

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

BW835

Lab Name: ICM

Contract: 68-W8-0046

Lab Code: ICM

Case No.: 10959

SAS No.:

SDG No.: BW831

Matrix: (soil/water) SOIL

Lab Sample ID:

Sample wt/vol: 34. (g/mL) G

Lab File ID: D0718

Level: (low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 18. dec. 0.

Date Extracted: 12/ 7/88

Extraction: (SepF/Cont/Sonc) SONC

Date Analyzed: 12/15/88

GPC Cleanup: (Y/N) N

pH: 7.1

Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO.

COMPOUND

Q

319-84-6-----alpha-BHC	8.6	U
319-85-7-----beta-BHC	8.6	U
319-86-8-----delta-BHC	8.6	U
58-89-9-----gamma-BHC (Lindane)	8.6	U
76-44-8-----Heptachlor	8.6	U
309-00-2-----Aldrin	8.6	U
1024-57-3-----Heptachlor epoxide	8.6	U
959-98-8-----Endosulfan I	17.	U
60-57-1-----Dieldrin	17.	U
72-55-9-----4,4'-DDE	17.	U
72-20-8-----Endrin	17.	U
33213-65-9-----Endosulfan II	17.	U
72-54-8-----4,4'-DDD	17.	U
1031-07-8-----Endosulfan sulfate	17.	U
50-29-3-----4,4'-DDT	86.	U
72-43-5-----Methoxychlor	17.	U
53494-70-5-----Endrin ketone	86.	U
5103-71-9-----alpha-Chlordane	86.	U
5103-74-2-----gamma-Chlordane	170.	U
8001-35-2-----Toxaphene	86.	U
12674-11-2-----Aroclor-1016	86.	U
11104-28-2-----Aroclor-1221	86.	U
11141-16-5-----Aroclor-1232	86.	U
53469-21-9-----Aroclor-1242	86.	U
12672-29-6-----Aroclor-1248	170.	U
11097-69-1-----Aroclor-1254	170.	U
11096-82-5-----Aroclor-1260		

PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA 84-112-101

BW851

Lab Name: IOM

Contract: 88-W6-0046

Lab Code: IOM

Case No.: 10959

SAS No.:

SDG No.: BW83.

Matrix: (Soil/Water) WATER

Lab Sample ID:

Sample At Vol: 1000. (g/mL) ML

Lab File ID: D0693

Level: (Low/med) LOW

Date Received: 12/ 1/88

% Moisture: not dec. 100. dec. 0.

Date Extracted: 12/ 1/88

Extraction: (SepF/Cont/Sonc) SEPF

Date Analyzed: 12/13/88

QAC (Yes/No): (Y/N) N

pH: 5.6

Dilution Factor: 1.00

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Q

LAB NO.

COMPOUND

LAB NO.	COMPOUND	CONCENTRATION UNITS:	Q
319-84-8	alpha-BHC	.050	U
319-85-7	beta-BHC	.050	U
319-86-8	delta-BHC	.050	U
58-89-9	gamma-BHC (Lindane)	.050	U
76-44-8	Heptachlor	.050	U
309-00-2	Alorin	.050	U
1124-57-3	Heptachlor epoxide	.050	U
505-98-6	Endosulfan I	.050	U
51-57-1	Dieldrin	.10	U
71-35-9	4,4'-DDE	.10	U
71-10-8	Endrin	.10	U
5051-01-9	Endosulfan II	.10	U
71-64-8	4,4'-DDT	.10	U
1001-07-5	Endosulfan sulfate	.10	U
50-19-3	4,4'-DDT	.10	U
71-43-3	Metoxychlor	.50	U
50494-70-5	Endrin ketone	.10	U
5103-71-9	alpha-Chlordane	.50	U
5103-74-2	gamma-Chlordane	.50	U
3001-35-2	Toxaphene	1.0	U
11874-11-2	Aroclor-1016	.50	U
11104-28-2	Aroclor-1221	.50	U
11141-16-5	Aroclor-1232	.50	U
53489-21-9	Aroclor-1242	.50	U
12671-25-8	Aroclor-1248	.50	U
11091-59-1	Aroclor-1254	1.0	U
11031-81-5	Aroclor-1260	1.0	U

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

BW853

Contract: 68-W8-0046

Lab Name: ICM

SDG No.: BW831

Lab Code: ICM

Case No.: 10959

SAS No.:

Lab Sample ID:

Matrix: (soil/water) WATER

Lab File ID: D0694

Sample wt/vol: 1000. (g/mL) ML

Date Received: 12/ 1/88

Level: (low/med) LOW

Date Extracted: 12/ 2/88

% Moisture: not dec.100. dec. 0.

Date Analyzed: 12/13/88

Extraction: (SepF/Cont/Sonc) SEPF

Dilution Factor: 1.00

GPC Cleanup: (Y/N) N pH: 6.4

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

		.050	U
319-84-6----	alpha-BHC	.050	U
319-85-7----	beta-BHC	.050	U
319-86-8----	delta-BHC	.050	U
58-89-9----	gamma-BHC (Lindane)	.050	U
76-44-8----	Heptachlor	.050	U
309-00-2----	Aldrin	.050	U
1024-57-3----	Heptachlor epoxide	.050	U
959-98-8----	Endosulfan I	.10	U
60-57-1----	Dieldrin	.10	U
72-55-9----	4,4'-DDE	.10	U
72-20-8----	Endrin	.10	U
33213-65-9----	Endosulfan II	.10	U
72-54-8----	4,4'-DDD	.10	U
1031-07-8----	Endosulfan sulfate	.10	U
50-29-3----	4,4'-DDT	.50	U
72-43-5----	Methoxychlor	.10	U
53494-70-5----	Endrin ketone	.50	U
5103-71-9----	alpha-Chlordane	.50	U
5103-74-2----	gamma-Chlordane	1.0	U
8001-35-2----	Toxaphene	.50	U
12674-11-2----	Aroclor-1016	.50	U
11104-28-2----	Aroclor-1221	.50	U
11141-16-5----	Aroclor-1232	.50	U
53469-21-9----	Aroclor-1242	.50	U
12672-29-6----	Aroclor-1248	1.0	U
11097-69-1----	Aroclor-1254	1.0	U
11090-82-5----	Aroclor-1260		

1/87 Rev.

FORM 1 PEST

REFERENCE NO. 4

ENGINEERING INVESTIGATIONS AT INACTIVE HAZARDOUS WASTE SITES

PHASE 1 INVESTIGATION

NTU Circuits, Inc.

Site No. 152086

Town of Babylon, Suffolk County

Final - June 1987

RECEIVED

SEP 16 1987

**BUREAU OF
HAZARDOUS SITE CONTROL
DIVISION OF SOLID AND
HAZARDOUS WASTE**



**New York State
Department of
Environmental Conservation**

50 Wolf Road, Albany, New York 12233

Henry G. Williams, Commissioner

Division of Solid and Hazardous Waste

Norman H. Nosenchuck, P.E., Director

Prepared by:



**EA SCIENCE AND
TECHNOLOGY**

A Division of EA Engineering, Science, and Technology, Inc.

**ENGINEERING INVESTIGATIONS AT
INACTIVE HAZARDOUS WASTE SITES
IN THE STATE OF NEW YORK
PHASE I INVESTIGATIONS**

**NTU CIRCUITS, INC.
TOWN OF BABYLON, SUFFOLK COUNTY
NEW YORK I.D. NO. 152086**

Prepared for

**Division of Solid and Hazardous Waste
New York State Department of Environmental Conservation
50 Wolf Road
Albany, New York 12233-0001**

Prepared by

**EA Science and Technology
R.D. 2, Goshen Turnpike
Middletown, New York 10940**

A Division of EA Engineering, Science, and Technology, Inc.

June 1987

CONTENTS

	<u>Page</u>
1. EXECUTIVE SUMMARY	1-1
2. PURPOSE	2-1
3. SCOPE OF WORK	3-1
4. SITE ASSESSMENT	4-1
4.1 Site History	4-1
4.2 Site Topography	4-5
4.3 Site Hydrogeology	4-6
4.4 Site Contamination	4-10
5. NARRATIVE SUMMARY	5-1
6. ASSESSMENT OF DATA ADEQUACY AND RECOMMENDATIONS	6-1
6.1 Adequacy of Existing Data	6-1
6.2 Recommendations	6-1
6.3 Phase II Work Plan	6-1
APPENDIX 1	
APPENDIX 2	

1. EXECUTIVE SUMMARY

The NTU Circuits, Inc. site (New York I.D. No. 152086 and EPA I.D. No. "New") is the former business location of NTU Circuits, where they manufactured printed circuit boards for electric applications. NTU leased the eastern portion of a building located at 60 Dale Street, Town of Babylon, Suffolk County, New York (Figures 1-1 and 1-2 and Photos 1 through 7) between 1978 and 1983. Spectrum Finishing Corp. is the current owner of the building, having purchased the property from Mr. James Gray in 1981. The site is located in an industrial park.

Six leach pools were present at the site during NTU's operations. NTU Circuits was repeatedly notified by the Suffolk County Department of Health Services (SCDHS) that the contents of the leaching pools were in violation of ground-water effluent standards and NTU's SPDES permit. Samples collected from the pools by SCDHS from 1979 until 1982 contained elevated levels of copper, cadmium, lead, silver, iron, flouride, and total solids. Analyses also indicated that the pH of the leachate was often outside the NYS Ground-Water Standards. Site visits by SCDHS staff produced evidence that foamy, bluish liquids were being discharged into the SPDES pool. On two occasions, the pool SD-3 was observed to be overflowing onto the ground and/or into adjacent storm drains.

In 1982, a case was filed against NTU Circuits, Inc. by the New York State Attorney General. The settlement, which took place on 30 April 1982, resulted in NTU having to clean up all six of the existing pools at the site. The company moved to a new site in September of 1983. Approximately two months later, the clean-up plan was implemented based on the Stipulation of

Discontinuance written by the Attorney General. The contaminated liquid was removed from the leach pools and taken to NTU's new building where it was treated in their wastewater treatment system. Three pools (SP-A, SD-2, and SD-3) were then lime slurried, the pipes were concreted closed, and each pool backfilled and paved over. The other pools (SD-7, SD-8, and SD-N1) were allowed to remain open after 1-2 ft of the bottom material was removed and replaced with clean sand.

The cleanup was performed in the presence of SCDHS officials, who affirmed that the leaching pools were cleaned properly. During EA's site inspection on 22 January 1986, it was found that the closed, paved over SD-3 pool had since been reopened. The tampering with this closed pool reportedly occurred after cleaning and closure by NTU, and did not involve NTU.

The available data are not adequate to prepare a final score. Although there is analytical data for samples of the waste, ground-water quality data are lacking. The preliminary HRS scores for this site are as follows: Migration Score (S_M) = 31.03 (Ground Water Score (S_{GW}) = 53.69, Surface Water Score (S_{SW}) = 0, Air Score (S_A) = 0); Fire and Explosion Score S_{FE} = 0; Direct Contact Score (S_{DC}) = 0.

In order to confirm a release of contaminants from the site to the ground water, a Phase II investigation is recommended. The proposed Phase II study would include the installation of four test boring/monitoring wells, and the collection and analysis of ground-water samples. The estimated cost to complete the Phase II investigation is \$50,700.





Figure 1-2. Site sketch. NTU Circuits, Inc., 22 January 1986.






PHOTO LOG - NTU CIRCUITS

<u>Photo</u>	<u>Description</u>
1-1 and 1-2	A view approximately west across the south and east (Photo 1-2) sides of the former NTU building.
1-3	A view approximately southwest across the north side of the former NTU building.
1-4 thru 1-6	A panoramic view northwest to north of the south side of the former NTU building. Pool SD-3 is located between the white pickup truck and the dumpster on Photo 1-4. Pool SD-7 is located near the right rear tire of the van on Photo 1-5. Pool SD-8 is located beneath the rear license plate of the station wagon on Photo 1-6.
1-7	Close up of the re-exposed grate which covers Pool SD-3.

2. PURPOSE

The NTU Circuits, Inc. site was listed in the New York State Registry of Inactive Hazardous Wastes Sites because hazardous wastes were found in onsite leachpools.

The goal of the Phase I investigation of this site was to: (1) obtain available records on the site history from state, federal, county, and local agencies; (2) obtain information on site topography, geology, local surface water and ground-water use, previous contamination assessments, and local demographics; (3) interview site owners, operators, and other groups or individuals knowledgeable of site operations; (4) conduct a site inspection to observe current conditions; and (5) prepare a Phase I report. The Phase I report includes a preliminary Hazard Ranking Score (HRS), an assessment of the available information, and a recommended work plan for Phase II studies.

3. SCOPE OF WORK

The Phase I investigation of the NTU Circuits, Inc. site involved a site inspection by EA Science and Technology, as well as record searches and interviews. The following agencies or individuals were contacted:

<u>Contact</u>	<u>Information Received</u>
Mr. Wayne DeChirico Quality Control Manager Spectrum Finishing Corp. 50 Dale Street Babylon, New York 11704 (516) 694-0306	Site history/interview
Mr. Richard Gregorski Marketing Manager NTU Circuits, Inc. 1480 North Clinton Avenue Bay Shore, New York 11706 (516) 666-7211	Site history/interview
Mr. Errol Kitt Assistant Project Engineer Fanning, Phillips, and Molner Consulting Engineers 80 Skyline Drive Plainview, New York 11803 (718) 767-3337	Site history/interview
Mr. Dave Odrig/Mr. Bob Seaforth Public Health Sanitarians Suffolk County Department of Health Services Bureau of Environmental Health 15 Horseblock Place Farmingville, New York 11738 (516) 451-4633	Site interview

Contact

Information Received

Mr. Anthony Candela, P.E.
Senior Sanitary Engineer
New York State Department of
Environmental Conservation
Division of Solid Waste
SUNY Campus - Building 40
Stony Brook, New York 11794
(516) 751-7900

Site file

Mr. James H. Pim, P.E.
Suffolk County Department of Health Services
Hazardous Materials Management
15 Horseblock Place
Farmingville, New York 11738
(516) 451-4634

Interview and site file

Mr. Steve Carey/Mr. Dennis Moran
Suffolk County Department of Health Services
Bureau of Water Resources
225 Rabro Drive East
Hauppauge, New York 11788
(516) 348-2893

Ground-water use; public
water supplies and ground-
water monitoring information

Mr. Dan Fricke
Suffolk County Cooperative
Extension Association
264 Griffing Avenue
Riverhead, New York 11901
(516) 727-7850

Ground-water and surface
water use for irrigation

Mr. William Schickler/Mr. Robert Bowen
Suffolk County Water Authority
Sunrise Highway and Pond Road
Oakdale, New York 11769
(516) 589-5200

Public water supply and
distribution

Mr. Doug Pica
New York State Department of
Environmental Conservation
Division of Water
SUNY Campus - Building 40
Stony Brook, New York 11794
(516) 751-7900

Ground-water use for
irrigation

Mr. Allan S. Connell
District Conservationist
U.S. Department of Agriculture
Soil Conservation Survey
127 East Main Street
Riverhead, New York 11901

Ground-water use for
irrigation

Contact

Mr. Gil Hanse
Chief Fire Marshal
Town of Babylon
200 E. Sunrise Highway
Lindenhurst, New York 11757
(516) 957-3069

Mr. Kevin Walter, P.E.
New York State Department of
Environmental Conservation
Division of Hazardous Waste Enforcement
50 Wolf Road
Albany, New York 12233-0001
(518) 457-4346

Mr. John Iannotti, P.E.
New York State Department of
Environmental Conservation
Bureau of Remedial Action
50 Wolf Road
Albany, New York 12233-0001
(518) 457-5637

Mr. Earl Barcomb, P.E.
New York State Department of
Environmental Conservation
Bureau of Municipal Wastes
Section of Landfill Operations
Vatrano Road
Albany, New York 12205
(518) 457-2051

Mr. Peter Skinner, P.E.
New York State Attorney
General's Office
Room 221
Justice Building
Albany, New York 12224
(518) 474-2432

Mr. Ron Tramontano/Mr. Charlie Hudson
New York State Department of Health
Bureau of Toxic Substances Assessment
Nelson A. Rockefeller Empire State Plaza
Corning Tower Building, Room 342
Albany, New York 12237
(518) 473-8427

Information Received

Information regarding the
threat of fire and/or
explosion at the site

No site file

No site file

No site file

No site file

No site file

Contact

Mr. James Covey, P.E.
New York State Department of Health
Nelson A. Rockefeller Empire State Plaza
Corning Tower Building
Albany, New York 12237
(518) 473-4637

Mr. Rocky Paggione, Atty./
Mr. Louis A. Evans, Atty.
New York State Department of
Environmental Conservation
Division of Environmental Enforcement
202 Mamaroneck Avenue
White Plains, New York 10601-5381
(914) 761-6660

Mr. Marsden Chen, P.E.
New York State Department of
Environmental Conservation
Bureau of Site Control
50 Wolf Road
Albany, New York 12233-0001
(518) 457-0639

Mr. John W. Ozard
Senior Wildlife Biologist
New York State Department of
Environmental Conservation
Wildlife Resources Center
Significant Habitat Unit
Delmar, New York 12054
(518) 439-7486

Mr. Perry Katz
U.S. Environmental Protection Agency
Region II
Room 757
26 Federal Plaza
New York, New York 10278
(212) 264-4595

Mr. Johnson
District Superintendent
Farmingdale Village Water Authority
361 Main Street
Farmingdale, New York 11735
(516) 249-6770

Mr. John Ferrari
Senior Water Plant Operator
E. Farmingdale Water District
(516) 249-4211

Information Received

Community Water
Supply Atlas

No site file

Site file

Significant habitats

No site file

Water district information

Water district information

Contact

Mr. Charles Guthrie
Regional Fisheries Manager
New York State Department
of Environmental Conservation
SUNY Campus-Building 40
Stony Brook, New York 11794
(516) 751-7900

Information Received

Surface water use for
recreation

4. SITE ASSESSMENT - NTU CIRCUITS, INC.

4.1 SITE HISTORY

The NTU Circuits, Inc. site is the former business location of NTU Circuits, where they manufactured printed circuit boards for electronic applications (Appendix 1.1-1). The site is located at 60 Dale Street, Town of Babylon, Suffolk County, New York. Spectrum Finishing Corp. (Mr. William DeChirico, Vice President) is the current owner of the property, having purchased the 14-year-old building from Mr. James Gray in 1981 (Appendix 1.1-2). The building is separated into two sections, the eastern portion (4,000 ft²) of which was leased and operated by NTU Circuits, Inc. for a 6-year period from 1978 through September 1983 (Appendixes 1.1-1 and 1.1-3). Mr. Wayne DeChirico, Quality Control Manager for Spectrum, indicated that the site was occupied by a candy distributor for a 6-month period from April 1984 until September 1984. During EA's site reconnaissance, it was observed that the portion of the building, which had been leased by NTU was now being leased by a pipe organ manufacturer who had been there approximately 1 year. The western portion of the building was and still is occupied by Welding Metallurgy, Inc. (Appendixes 1.1-2 and 1.1-3).

Mr. Richard Gregorski, Marketing Manager for NTU Circuits, indicated that NTU's operation consisted of an office; a drilling room in the east portion; plating and scrubbers along the north wall; a yellow room (photodeveloping/printing) in the west section; a photodeveloping darkroom in the south-central area; and shipping, programming, and machine drilling in the southeastern portion

(Appendix 1.1-3 and Figure 1-2). The operation employed 10-15 people on a 6-day work week, drilling, cleaning, and electroplating 100 panels a day. According to a study performed at NTU in 1981, combined processes at the plant at that time produced an average effluent volume of 6,205 gal per day (Appendix 1.1-4). Although, all plating solutions were reportedly drummed and removed from the site for disposal by a liscensed hauler, some of the rinsewater was discharged to storm drain/industrial leach pools under a SPDES permit (Appendixes 1.1-1 and 1.1-5).

There are seven leach pools (cesspools) and one septic tank now located around the old NTU facility located at Dale Avenue. One pool (SD-N1) is located north of the building and reportedly received only storm runoff (Appendixes 1.1-2 and 1.1-3). The remaining pools and septic tank are located south of the building (Figure 1-2):

SP-A was the old (now abandoned and backfilled) sanitary pool which received sanitary waste from both NTU and Welding Metallurgy, Inc., plus waste from NTU's "slop sink" (Appendix 1.1-5).

SD-2 received roof drainage and surface runoff (Appendix 1.1-3).

New sanitary pool and new septic tank shown on Figure 1-2 are the current sanitary waste disposal system which replaced SP-A (Appendix 1.1-3).

SD-3 was permitted (SPDES) and received NTU's industrial wastewater (Appendix 1.1-3).

SD-7 received rinsewater from NTU's photoprinting operation and for an unknown period of time apparently beginning in July 1981 was connected to and received waste from SD-3 (Appendixes 1.1-3 and 1.1-5).

SD-8 received roof drainage and surface water runoff and for an unknown period was interconnected with and received waste from SD-3 and SD-7 (Appendix 1.1-3).

NTU Circuits was repeatedly notified by the Suffolk County Department of Health Services (SCDHS) that the contents of its leaching pools were in violation of NYS Ground-Water Standards and NTU's SPDES permit (Appendix 1.1-6). During site visits to NTU between 1979 and 1981 to perform site inspections and/or sampling activities, SCDHS personnel made a variety of observations including: (1) overflow of bluish liquids from SD-3 into the surrounding area, (2) presence of bluish liquids in SP-A, (3) presence of foamy fluid in SD-3, and (4) flow of a bluish, foamy liquid via a subsurface PVC pipe from SD-3 to SD-7 (Appendixes 1.1-5, 1.1-7 through 1.1-9). One inspector also noted blue-green stains on the floor inside the NTU building and outside the wall (Appendix 1.1-5). Although Welding Metallurgy also discharged sanitary wastewater into pool SP-A, SCDHS did not consider the company to be a contributor to the industrial waste found in the cesspool. No chemicals or prints were found on the Welding Metallurgy premises during a SCDHS site visit (Appendix 1.1-5).

NTU was the subject of a court action by the New York State Attorney General which was settled on 30 April 1982 (Appendixes 1.1-3, 1.1-10, and 1.1-11). The settlement of the case resulted in NTU having to clean up all of the existing

pools. During September 1983, NTU moved from the Dale Street facility in West Babylon to a new facility at 1480 North Clinton Avenue in Bayshore, New York. The new facility is located in a sewered area and includes an automated EPA-approved waste treatment system (Appendix 1.1-1).

In complying with the Stipulation of Discontinuance (Appendix 1.1-11), NTU performed drainage pool cleanup activities during 29 November and 1-2 December 1983 at the old Dale Street facility which they had already vacated. The cleanup work was supervised and approved by SCDHS personnel. The work included (Appendix 1.1-3):

SD-2 and SD-3 Pools - liquid removed and transported by a certified hauler to NTU's new (Clinton Street) facility for treatment in their wastewater treatment system. The bottom of each pool was lime slurried, the pipes cemented closed, and each pool filled with clean sand and paved over.

SP-A Pool - Cleaned out, filled in with clean sand, and paved over.

SD-7, SD-8, and SD-N1 Pools - Liquid removed and treated as stated previously for SD-2 and SD-3. The 1-2 ft of bottom material was removed for disposal by a certified waste hauler, and replaced with 1-2 ft of clean sand. These 3 pools were allowed to remain in use.

This remedial work involved only the cleanup of contaminated leach pools, and did not involve any ground-water monitoring to investigate the potential

migration of contaminants from the site. SCDHS has noted that such a ground-water investigation should still be performed under Superfund (Appendix 1.1-12).

During EA's January 1986 site reconnaissance, it was noted that someone had tampered with the SD-3 pool which NTU had closed and paved over. The over-paving had been removed and the grating exposed, through which an approximately 5-gal jerry can was observed just beneath the grating. Although, the source of this tampering is unknown, it occurred after NTU cleaned and paved it over and did not involve NTU (Appendix 1.1-3).

4.2 SITE TOPOGRAPHY

The NTU Circuits, Inc. site is situated along the southern side of Long Island, approximately 5 mi inland of Great South Bay (Appendix 1.2-1). The site is largely flat; however, the regional slope is approximately 0-2 degrees to the south.

NTU Circuits site is located in an industrial park on the west side of Dale Street. The NTU facility was located in the eastern portion of a building at 60 Dale Street. The western portion of the building was and still is occupied by Welding Metallory, Inc. The old NTU building is bordered by Dale Street to the east, commercial establishments to the north and west, and Spectrum Finishing Corp. (who owns the site property) to the south. Welding Metallory, Inc. is the nearest commercial establishment. The nearest private residence is located at the intersection of Dale Street and Edison Avenue, approximately 500 ft southeast of the site. The nearest well is in the SCWA Gordon Avenue

well field located approximately 1 mi southeast of the site. The nearest surface water is Neguntatogue Creek, a perennial stream located approximately 9,500 ft south-southeast of the site. However, there is no viable overland route to this surface waterbody because several highways, recharge basins, and a railroad interrupt the pathway. Also, surface water in the vicinity of the site is collected in storm drainage pools for subsurface discharge to the ground.

4.3 SITE HYDROGEOLOGY

The site is directly underlain by Pleistocene Age glacial outwash deposits. This deposit is then in turn underlain by Cretaceous Age Matawan Group-Magothy Formation (undifferentiated), the Clay Member and Lloyd Sand Member of the Raritan Formation and finally by Precambrian Age gneiss and schist bedrock (Appendix 1.3-1). The Pleistocene deposits are estimated to be 75 ft in thickness (ground surface elevation and Appendix 1.3-1) and largely comprised of stratified sand and gravel. The Matawan Group-Magothy Formation (undifferentiated) is estimated to be 800 ft in thickness in the vicinity of the site (Appendixes 1.3-1 and 1.3-2). The upper surface of this deposit is irregular because of considerable erosion during the Tertiary and Pleistocene times. Therefore, accurate prediction of formation thickness between control points (boreholes) is difficult. The most detailed description of this formation is provided by Soren (Appendix 1.3-3) and is as follows: generally composed of "beds and lenses of light gray fine to coarse sand and silt, intercalated with thin to thick beds and lenses of light- to dark-gray clay, silt, and clayey/silty sand." Thin beds of lignite are commonly found in the clay and silt beds, while disseminated lignite and pyrite are common in the sand beds.

Gravelly coarse sand is commonly present in the basal portion of the Magothy Formation, along with abundant interstitial clay and silt and lenses of clay, silt, and clayey/silty sand. The clay and silt beds are often apparently discontinuous lenses and not possible to correlate over significant distances as indicated on the geologic logs (Appendix 1.3-4) for two nearby deep water supply wells: Well S-51457 (733-ft total borehole depth) located approximately 2 mi east of the site; and Well S-20042 (585-ft total borehole depth) located about 2 mi northwest of the site.

Based upon Jensen and Soren (Appendix 1.3-2) it is estimated that in the vicinity of the site the Clay Member of the Raritan Formation is 150 ft in thickness, and the Lloyd Sand is estimated to be 350 ft in thickness. The most detailed stratigraphy information is provided by Soren (Appendix 1.3-3) and summarized in the following sentences. The Clay Member of the Raritan Formation consists mostly of beds/lenses of light- to dark-gray clay, silt, and clayey/silty fine sand and occasional thin-to-thick sandy lenses of limited lateral extent. Thin beds and disseminated particles of lignite and pyrite are common in the clay portion of this unit. The Lloyd Sand Member of the Raritan Formation "consists mostly of beds and lenses of light- to medium-gray sand and gravelly sand, commonly containing small to large amounts of interstitial clay and silt, that are intercalated with beds and lenses of light- to dark-gray clay, silt, and clayey/silty sand."

Water pumped from aquifers underlying Suffolk County is the sole source of water for public supply, agriculture, and industry (Appendix 1.3-2). The upper glacial and Magothy aquifers act as a single hydrological unit. However, only the Magothy portion is reportedly still developed by wells for water supply

within 3 mi of the site. Therefore, both the upper glacial and Magothy aquifers are designated as the aquifer of concern. The Lloyd aquifer, though moderately permeable (165 gpd/ft² estimated horizontal permeability at Brookhaven National Laboratory about 30 mi east of the site), has not been developed for water supply because more permeable aquifers are present at shallower depths, and water from the Lloyd commonly has undesirably high concentrations of iron. Additionally, the Lloyd aquifer is overlain by the extensive, thick, low permeability (confining) Raritan Clay (Appendix 1.3-3). Therefore, the Lloyd aquifer will not be considered further by this Phase I investigation.

The aquifers of Long Island are hydraulically interconnected and although beds and discontinuous layers of silt and clay within and between aquifers serve to confine water below them, they do not completely prevent the vertical movement of water through and around them. Soren (Appendix 1.3-3) presents data which reflect the high degree of hydraulic interconnection between the upper glacial and Magothy aquifers in the vicinity: (1) for wells completed in the upper glacial and Magothy aquifers in nearby Brentwood and Hauppauge, the head in these two aquifers decrease at a fairly uniform rate with increasing depth, and (2) water-level fluctuation in the same well groups were very similar. Soren also reports that the estimated downward velocity of water through the Magothy aquifer in the vicinity of the ground-water divide in 1968 (along which the site is located) was 0.006 ft/day (approximately 2.2 ft/year).

Recharge to the upper glacial aquifer is derived entirely from precipitation. Recharge to the Magothy and Lloyd aquifers is derived entirely from the downward movement of water from each overlying aquifer (Appendix 1.3-5). In

general, recharge to the lower aquifers occurs near the center of Long Island and discharge occurs along the edge of Long Island to the ocean and Long Island Sound. The average annual precipitation in the area is 46 in, of which 24 in. is estimated to infiltrate to the water table (Appendix 1.3-1). The remainder of the precipitation is returned to the atmosphere by evaporation and transpiration, except for a small amount of runoff to streams.

The upper glacial aquifer is the most permeable aquifer on Long Island with an estimated horizontal permeability of 1,000-1,500 gpd/ft² (Appendix 1.3-3). In 1968, it was estimated in the region that water in the upper glacial aquifer was moving horizontally at rates less than 0.5 ft/day in areas distant from centers of pumping and to hundreds of ft/day near the screens of pumping wells (Appendix 1.3-3). The permeability of the underlying Magothy aquifer ranges widely depending upon the presence and amount of clay and silt. In 1968, it was estimated in the region that water in the Magothy aquifer was moving horizontally at rates less than 0.2 ft/day in areas distance from pumping, and to hundreds of ft/day near screens of pumping wells.

Based upon the March 1985 ground-water table contour map (SCDHS), the depth to ground water is estimated to be approximately 15 ft below ground surface, and the regional ground-water natural (unaffected by pumping) flow direction appears to be toward the south southeast. Within 3 mi of the site, the Magothy portion of the aquifer of concern has been developed by eight Suffolk County Water Authority well fields, three East Farmingdale Water Authority well fields, and in Nassau County, one Farmingdale Village Water Authority well field. Appendix 1.3-6 provides a list of the municipal wells located within 3 mi of the site. The developed area within 3 mi of the site appears to be

served by four public water systems (Suffolk County Water Authority, East Farmingdale Water District, South Huntington Water District, and Dix Hills Water District) and two public water systems in Nassau County (Farmingdale Village Water Authority and South Farmingdale Water Authority).

4.4 SITE CONTAMINATION

Waste Types and Quantities

The average total industrial waste flow from NTU was estimated in 1981 to be 6,205 gal/day (Appendix 1.1-4). The SCDHS repeatedly sampled the contents of onsite leachpools from 1979 through 1982. Samples collected from all of the leach pools were found to be contaminated. The leach pool samples contained cadmium (0.03-0.07 mg/liter), silver (0.36-1.1 mg/liter), copper (3.8-440 mg/liter), iron (1.3-28 mg/liter), lead (0.2-4.6 mg/liter), hexavalent chromium (0.15 mg/liter), fluoride (3.2 mg/liter), and total solids (101-3,983 mg/liter) (Appendixes 1.1-6 and 1.4-1). The pH varied widely from 3 to 11 (Appendix 1.1-6). SCDHS inspectors observed a bluish and/or foamy liquid being discharged into the SD-3 pool and, from there, into adjoining pool SD-7 (Appendixes 1.1-5, and 1.1-7 through 1.1-9).

Ground Water

No data available.

Surface Water

No data available.

Soil

No data available.

Air

No HNU readings above background were detected from the old NTU building during EA's site inspection on 22 January 1986.

NTU CIRCUITS, INC.
TOWN OF BABYLON, SUFFOLK COUNTY

The NTU Circuits, Inc. site is the former business location of NTU Circuits, where they manufactured printed circuit boards for electronic applications. NTU leased the eastern portion of a building located at 60 Dale Street, Town of Babylon, Suffolk County, New York between 1978 and 1983. Spectrum Finishing Corp. is the current owner of the building, having purchased the property from Mr. James Gray in 1981. The site is located in an industrial park.

Six leach pools were present at the site during NTU's operations. The Suffolk County Department of Health Services (SCDHS) repeatedly notified NTU Circuits that the contents of the leaching pools were in violation of ground-water effluent standards and NTU's SPDES permit. SCDHS collected samples from the pools from 1979 until 1982, and the samples contained elevated levels of copper, cadmium, lead, silver, iron, flouride, and total solids. On two occasions, the pool SD-3 was observed to be overflowing onto the ground and/or into adjacent storm drains.

In 1982, the New York State Attorney General filed a case against NTU Circuits, Inc. The settlement took place on 30 April 1982, and resulted in NTU having to clean up all six of the existing pools at the site.

NTU Circuits performed the cleanup in the presence of SCDHS officials, who affirmed that the leaching pools were cleaned properly. In order to confirm a release of contaminants from the site to the ground water, further environmental study and sampling is recommended

Coordinates:

Latitude: 40° 43' 52"

Longitude: 73° 23' 23"

NTU CIRCUITS, INC.



AMITYVILLE & BAY SHORE WEST QUADS.

Scale 1: 24,000

Facility name NTU Circuits, Inc.

Location: Town of Babylon, Suffolk County

EPA Region II

Person(s) in charge of the facility: Mr. William DeChirico, Owner

50 Dale Street

Babylon, New York 11704

Name of Reviewer: EA Science and Technology Date 3 September 1986

General description of the facility:

(For example: landfill; surface impoundment; pile container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

The site is an inactive industrial site located on Dale Street, Town of Babylon, New York which operated from 1978 until 1983 and was involved in the production of circuit boards. NTU was repeatedly notified by the Suffolk County Department of Health Services that the contents of leaching pools on the premises were in violation of ground water effluent standards and NTU's SPDES permit. The liquid wastes contained heavy metals, flouride, and excessive total solids. In 1982, the New York State Attorney General filed a case against NTU. Based on the settlement, all leachpools at the site were cleaned by NTU in November-December 1983. In September 1983, NTU moved to a new location. During EA's site inspection, it was observed that the SD-3 leachpool, which had been paved over, was re-

Scores: $S_M = 31.03$ $S_{gw} = 53.69$ $S_{sw} = 0$ $S_a = 0$

$S_{FE} = N/A$

$S_{DC} = 0$

Maximum $S_M = 31.03$

FIGURE 1 HRS COVER SHEET

opened. The tampering with this closed pool reportedly occurred after cleaning and closure by NTU and did not involve NTU.

Ground Water Route Work Sheet:						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max Score	Ref (Section)	
1 Observed Release	0 45	1	0	45	3.1	
If observed release is given a score of 45, proceed to line 4 . If observed release is given a score of 0, proceed to line 2 .						
2 Route Characteristics					3.2	
Depth to Aquifer of Concern	0 1 2 3	2	6	6		
Net Precipitation	0 1 2 3	1	3	3		
Permeability of the Unsaturated Zone	0 1 2 3	1	3	3		
Physical State	0 1 2 3	1	3	3		
Total Route Characteristics Score			15	15		
3 Containment	0 1 2 3	1	3	3	3.3	
4 Waste Characteristics					3.4	
Toxicity/Persistence	0 3 6 9 12 15 18	1	18	18		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1	1	8		
Total Waste Characteristics Score			19	26		
5 Targets					3.5	
Ground Water Use	0 1 2 3	3	6	9		
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 20 24 30 32 35 40	1	30	40		
Total Targets Score			36	49		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			30,780	57,330		
7 Divide line 6 by 57,330 and multiply by 100			$S_{gw} = 53.69$			

FIGURE 2
GROUND WATER ROUTE WORK SHEET

Max.
Possibl

45

19

36

30,780

53.69

Surface Water Route Work Sheet:						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max Score	Ref (Section)	
1 Observed Release	(0) 45	1	0	45	4.1	
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .						
2 Route Characteristics					4.2	
Facility Slope and Intervening Terrain	(0) 1 2 3	1	0	3		
1-yr. 24-hr. Rainfall	0 1 (2) 3	1	2	3		
Distance to Nearest Surface Water	(0) 1 2 3	2	0	6		
Physical State	0 1 2 (3)	1	3	3		
Total Route Characteristics Score			5	15		
3 Containment	(0) 1 2 3	1	0	3	4.3	
4 Waste Characteristics					4.4	
Toxicity/Persistence	(0) 3 6 9 12 15 18	1	0	18		
Hazardous Waste Quantity	(0) 1 2 3 4 5 6 7 8	1	0	8		
Total Waste Characteristics Score			0	26		
5 Targets					4.5	
Surface Water Use	(0) 1 2 3	3	0	9		
Distance to a Sensitive Environment	(0) 1 2 3	2	0	6		
Population Served/Distance to Water Intake Downstream	(0) 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40		
Total Targets Score			0	55		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0	64,350		
7 Divide line 6 by 64,350 and multiply by 100			S _{sw} = 0			

FIGURE 7
SURFACE WATER ROUTE WORK SHEET

Air Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max Score	Ref Section	
1 Observed Release	0 45	1	0	45	5.1	
Date and Location:						
Sampling Protocol:						
If line 1 is 0, the $S_a = 0$. Enter on line 5 . If line 1 is 45, then proceed to line 2 .						
2 Waste Characteristics					5.2	
Reactivity and Incompatibility	0 1 2 3	1		3		
Toxicity	0 1 2 3	3		9		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8		
Total Waste Characteristics Score				20		
3 Targets					5.3	
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30	1		30		
Distance to Sensitive Environment	0 1 2 3	2		6		
Land Use	0 1 2 3	1		3		
Total Targets Score				39		
4 Multiply 1 x 2 x 3				35.100		
5 Divide line 4 by 35.100 and multiply by 100				$S_a = 0$		

FIGURE 9
AIR ROUTE WORK SHEET

	S	S ²
Groundwater Route Score (S _{gw})	53.69	2,882.62
Surface Water Route Score (S _{sw})	0	0
Air Route Score (S _a)	0	0
$S_{gw}^2 + S_{sw}^2 + S_a^2$		2,882.62
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		53.69
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		31.03

FIGURE 10
WORKSHEET FOR COMPUTING S_M

Maximum S_M = 31.03

Fire and Explosion Work Sheet:						
Rating Factor	Assigned Value (Circle One)		Multi- plier	Score	Max Score	Ref (Section)
1 Containment	1	3	1		3	7.1
2 Waste Characteristics						7.2
Direct Evidence	0	3	1		3	
Ignitability	0	1 2 3	1		3	
Reactivity	0	1 2 3	1		3	
Incompatibility	0	1 2 3	1		3	
Hazardous Waste Quantity	0	1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score					20	
3 Targets						7.3
Distance to Nearest Population	0	1 2 3 4 5	1		5	
Distance to Nearest Building	0	1 2 3	1		3	
Distance to Sensitive Environment	0	1 2 3	1		3	
Land Use	0	1 2 3	1		3	
Population Within 2-Mile Radius	0	1 2 3 4 5	1		5	
Buildings Within 2-Mile Radius	0	1 2 3 4 5	1		5	
Total Targets Score					24	
4 Multiply 1 x 2 x 3					1,440	
5 Divide line 4 by 1,440 and multiply by 100				SFE = N/A		

**FIGURE 11
FIRE AND EXPLOSION WORK SHEET**

Direct Contact Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max Score	Ref. (Section)	
1 Observed Incident	<u>0</u> 45	1	0	45	8.1	
If line 1 is 45, proceed to line 4 If line 1 is 0, proceed to line 2						
2 Accessibility	0 1 2 <u>3</u>	1	3	3	8.2	
3 Containment	<u>0</u> 15	1	0	15	8.3	
4 Waste Characteristics Toxicity	<u>0</u> 1 2 3	5	0	15	8.4	
5 Targets					8.5	
Population Within a 1-Mile Radius	0 1 2 3 4 <u>5</u>	4	20	20		
Distance to a Critical Habitat	<u>0</u> 1 2 3	4	0	12		
Total Targets Score			20	32		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0	21,600		
7 Divide line 6 by 21,600 and multiply by 100			SpC = 0			

FIGURE 12
DIRECT CONTACT WORK SHEET

**DOCUMENTATION RECORDS
FOR
HAZARD RANKING SYSTEM**

INSTRUCTIONS: As briefly as possible, summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference. Include the location of the document.

FACILITY NAME: NTU Circuits, Inc.

LOCATION: Town of Babylon, Suffolk County

DATE SCORED: 3 September 1986

PERSON SCORING: EA Science and Technology

PRIMARY SOURCES(S) OF INFORMATION (e.g., EPA region, state, FIT, etc.)

Suffolk County Department of Health Services
Mr. Wayne DeChirico, Spectrum Finishing Corp.
Mr. Richard Gregorski; NTU Circuits, Inc.
Mr. Errol Kit; Fanning, Phillips, and Molner Engineers

FACTORS NOT SCORED DUE TO INSUFFICIENT INFORMATION:

Air Route
Confirmation of a release to ground water

COMMENTS OR QUALIFICATIONS:

Ambient and downgradient ground-water quality are unavailable. The ground-water route is scored on the basis of confirmed contamination in onsite cesspools. The local fire marshal does not consider the site to be an imminent fire or explosion threat.

Direct contact score is based upon release of the waste fluids directly to the subsurface via leach pools.

GROUND WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected (5 maximum):

No analytical data available (Chapter 3).

Assigned value = 0.

Reference: 6.

Rationale for attributing the contaminants to the facility:

2 ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

The Pleistocene Age Upper Glacial deposits and the Cretaceous Age Magothy Formation.

References: 1, 2, and 3.

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table[s]) of the aquifer of concern:

15 ft.

References: 4 and 5.

Depth from the ground surface to the lowest point of waste disposal/storage:

Unknown. Estimate 6-ft depth of cesspool.

Depth to aquifer of concern is estimated to be 9 ft.

Assigned value = 3.

Reference: 6.

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

Mean annual lake or seasonal evaporation (list months for seasonal):

Net precipitation (subtract the above figures):

24 in.

Reference: 1.

Assigned value = 3.

Reference: 6.

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

Sand and gravel.

Reference: Report Section 4.3.

Permeability associated with soil type:

$>10^{-3}$ cm/sec.

Assigned value = 3.

Reference: 6.

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

Liquid.

References: 8 and 9.

Assigned value = 3.

Reference: 6.

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Wastes discharged via pipes to underground leach pools.

References: 8 and 9.

Method with highest score:

No containment in respect to ground water.

Assigned value = 3.

Reference: 6.

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

Cadmium, copper, iron, lead, hexavalent chromium, silver, flouride.

Reference: 10.

Compound with highest score:

Cadmium, copper, iron, lead, hexavalant chromium.

Reference = 6.

Assigned value = 18.

Reference: 6.

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

Unknown. According to a study performed by NTU in 1981, combined processes at the site at that time produced an average effluent volume of 6,205

gal/day; however, it is not clear how much of that effluent was actually discharged to the cesspools or how much of it was contaminated.

Reference: 26.

Basis of estimating and/or computing waste quantity:

Minimum quantity assumed.

Assigned value = 1.

Reference: 6.

5 TARGETS

Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Drinking water with municipal water from alternate sources presently available.

References: 11, 12, 13, and 14.

Assigned value = 2.

Reference: 6.

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Suffolk County Water Authority well located at the Gordon Avenue wellfield.

Reference: 14.

Distance to above well or building:

Approximately 6,400 ft from site.

References: 11 and 14.

Assigned value = 2.

Reference: 6.

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

Community Supplies:	Population:
Suffolk County Water Authority	207,689
Farmingdale Village Water Authority	10,000
E. Farmingdale Water Authority	<u>5,700</u>
	231,239

References: 11-14, 27, and 29.

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

Approximately 175 acres of land are used for agricultural purposes within a 3-mi radius of the site. However, irrigation wells on agricultural land in Suffolk County are not registered by any regulatory agency, so there are no lists or descriptions of the locations of these wells.

References: 15 through 19.

Total population served by ground water within a 3-mile radius:

225,539. Assigned value = 5. Combined assigned value = 35.

Reference: 6.

SURFACE WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

No data available (Chapter 3).

Assigned value = 0.

Reference: 6.

Rationale for attributing the contaminants to the facility:

2 ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

Zero. Site is a below-grade leaching pool.

Reference: 7.

Name/description of nearest downslope surface water:

Neguntatogue Creek.

Reference: 5.

Average slope of terrain between facility and above-cited surface water body in percent:

0-2 percent. Estimated using a Suunto clinometer and from topographic map.

References: 5 and 7.

Is the facility located either totally or partially in surface water?

No.

References: 5 and 7.

Is the facility completely surrounded by areas of higher elevation?

No.

References: 5 and 7.

Assigned value = 0.

Reference: 6.

1-Year, 24-Hour Rainfall in Inches

2.5 in.

Assigned value = 2.

Reference: 6.

Distance to Nearest Downslope Surface Water

2.3 mi.

Reference: 5

Assigned value = 0.

Reference: 6.

Physical State of Waste

Liquid.

References: 8 and 9.

Assigned value = 3.

Reference: 6.

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Wastes were discharged through pipes to underground leach pools, and even if a leach pool overflowed, the overflow would drain into another nearby catch basin/leach pool. Therefore, wastes were surrounded by diversion structures which were adequate to preclude runoff to a natural waterbody. In addition, the overland route for runoff to surface water is interrupted by several highways, recharge basins, and a railroad.

References: 5, 20, and 21.

Method with highest score:

Assigned value = 0.

Reference: 6.

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

Containment score = 0; therefore, waste characteristics are not evaluated.

Reference: 6.

Compound with highest score:

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

Basis of estimating and/or computing waste quantity:

5 TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Perennial stream. Not currently used.

Reference: 22.

Assigned value = 0.

Reference: 6.

Is there tidal influence?

No.

Reference: 5.

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

None within 2 mi.

Reference: 5.

Distance to 5-acre (minimum) freshwater wetland, if 1 mile or less:

None within 1 mi.

Reference: 5.

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

None within 1 mi.

Reference: 23.

Assigned value = 0.

Reference: 6.

Population Served by Surface Water

Location(s) of water supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static waterbodies) downstream of the hazardous substance and population served by each intake:

None.

References: 12 and 16.

Assigned value = 0.

Reference: 6.

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre).

None. The major source of irrigation water in Suffolk County is ground water from wells. Generally, surface water is not utilized for this purpose.

References: 15 and 16.

Total population served:

Zero.

References: 11, 12, 15, and 16.

Assigned value = 0.

Name/description of nearest of above waterbodies:

Distance to above-cited intakes, measured in stream miles:

AIR ROUTE

No data available from any of the agency files examined (Chapter 3). During EA's inspection (22 January 1986), total volatile organics were measured using a photoionization detector (HNU). No HNU readings above background were measured.

Assigned value = 0.

Reference: 6.

1 OBSERVED RELEASE

Contaminants detected:

Date and location of detection of contaminants

Methods used to detect the contaminants:

Rationale for attributing the contaminants to the site:

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Most incompatible pair of compounds:

Toxicity

Most toxic compound:

Hazardous Waste Quantity

Total quantity of hazardous waste:

Basis of estimating and/or computing waste quantity:

3 TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi 0 to 1 mi 0 to 1/2 mi 0 to 1/4 mi

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Distance to 5-acre (minimum) freshwater wetland, if 1 mile or less:

Distance to critical habitat of an endangered species, if 1 mile or less:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

FIRE AND EXPLOSION

The local fire marshal has not certified that the site presents a significant fire or explosion threat (Reference: 24). There are no analytical data available in any of the agency files (Chapter 3).

1 CONTAINMENT

Hazardous substances present:

Type of containment, if applicable:

2 WASTE CHARACTERISTICS

Direct Evidence

Type of instrument and measurements:

Ignitability

Compound used:

Reactivity

Most reactive compound:

Incompatibility

Most incompatible pair of compounds:

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility:

Basis of estimating and/or computing waste quantity:

3 TARGETS

Distance to Nearest Population

Distance to Nearest Building

Distance to Sensitive Environment

Distance to wetlands:

Distance to critical habitat:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

Population Within 2-Mile Radius

Buildings Within 2-Mile Radius

DIRECT CONTACT

1 OBSERVED INCIDENT

Date, location, and pertinent details of incident:

No observed incident on record.

Reference: Section 3.

Assigned value = 0.

Reference: 6.

2 ACCESSIBILITY

Describe type of barrier(s):

Barriers do not completely surround the facility.

Reference: 7.

Assigned value = 3.

Reference: 6.

3 CONTAINMENT

Type of containment, if applicable:

Leachpools are adequately covered.

Reference: 7.

Assigned value = 0.

Reference: 6.

4 WASTE CHARACTERISTICS

Toxicity

Compounds evaluated:

Containment score = 0. Therefore, waste characteristics are not evaluated.

Reference: 6.

Compound with highest score:

5 TARGETS

Population Within 1-Mile Radius

10,962. Estimated 25 percent of the population of Wyandoch (3,304), 15 percent of West Babylon (6,522), and 20 percent of East Farmingdale (1,136).

Assigned value = 5.

References: 6 and 28.

Distance to Critical Habitat (of Endangered Species)

None within 1 mi.

Reference: 23.

Assigned value = 0.

Reference: 6.

REFERENCES

1. Pluhowski, E.J., and I.H. Kantrowitz. 1964. Hydrology of the Babylon-Islip Area, Suffolk County, Long Island, New York. Geological Survey Water-Supply Paper, 1768 (Appendix 1.3-1.)
2. Jenson, H.M., and J. Soren. 1974. Hydrogeology of Suffolk County, Long Island (Appendix 1.3-2.)
3. Soren, J. 1971. Results of Subsurface Exploration in the Mid-Island Area of Western Suffolk County, Long Island (Appendix 1.3-3.)
4. Suffolk County Department of Health Services (SCDHS). 1985. Contour Map of the Water Table and Location of Observation Wells in Suffolk County, New York.
5. U.S. Geological Survey. 1979. 7.5-Minute Series. Amityville and Bay Shore West Quads. (Figure 1-2.)
6. U.S. Environmental Protection Agency. 1984. Uncontrolled Hazardous Waste Site Ranking System. A Users Manual (HW-10). Originally published in the 16 July 1982 Federal Register.
7. EA Site Inspection. 22 January 1986.
8. Affidavit. 1981. David Obrig. Supreme Court of the State of New York. 16 November 1981. (Appendix 1.1-5.)
9. Affidavit. 1981. Robert-Carl Olsen. Supreme Court of the State of New York. August 1981. (Appendix 1.1-7.)
10. SCDHS. 1979-1982. Analytical Data on Field Sampling (Appendixes 1.1-6 and 1.4-1.)
11. SCDHS, Water Resources Division. Supply and Monitoring Well Location Maps.
12. New York State Department of Health. 1982. New York State Atlas of Community Water System Sources.
13. New York State Department of Health. 1984. Inventory-Community Water Systems.
14. Suffolk County Water Authority (SCWA). 1985. Distribution of System Plates: 25N, 16N, 14M, 25M, and 26M.
15. Letter from A. Connell, District Conservationist, USDA Soil Conservation Service, to Mr. W. Going, EA Science and Technology, regarding irrigation in Suffolk County. Dated 13 March 1986. (Appendix 1.5-1.)
16. Fricke, D. 1986. Suffolk County Cooperative Extension Association. Personal Communication. 7 April. (Appendix 1.5-2.)

REFERENCES (Cont.)

17. Carey, S. 1986. Ground Water Section, Suffolk County Department of Health Services. Personal Communication. 7 April. (Appendix 1.5-3.)
18. Pica, D. 1986. Water Unit, Region 1, NYSDEC. Personal Communication. 7 April (Appendix 1.5-4.)
19. Long Island Regional Planning Board (LIRPB). 1982. Land Use in 1981, Quantification and Analysis of Land Use for Nassau and Suffolk Counties. Plate 5. (Appendix 1.5-9)
20. Kitt, Errol S. 1986. Fanning, Phillips, and Molner, Consulting Engineers. Report Review and Verification of Interview Acknowledgement Form for NTU Circuits Site. (Appendix 1.1-3.)
21. Letter from Kevin J. Phillips, Consulting Engineer, to Mr. Robert Schneck, Senior Sanitary Engineer, NYSDEC, regarding cleanup at NTU Circuits Inc. site. Dated 11 March 1985. (Appendix 1.1-11.)
22. Guthrie, C. 1986. Regional Fisheries Manager, Region I; NYSDEC. Personal Communication. 17 September. (Appendix 1.5-5.)
23. Ozard, J.W. 1986. Senior Wildlife Biologist. NYSDEC Wildlife Resources Center, Significant Habitat Unit. Personal Communication. 26 February (Appendix 1.5-6.)
24. Hanse, G. 1986. Chief Fire Marshal, Town of Babylon. Personal Communication. 19 September. (Appendix 1.5-7.)
25. Sax, N. Irving. 1979. Dangerous Properties of Industrial Materials. Van Nostrand Reinhold Company, New York.
26. NTU Circuits, Inc. Undated. Plant and Process Description Source: Suffolk County Department of Health Services (1986). Unpublished. (Appendix 1.1-4.)
27. Mr. Johnson. 1986. District Superintendent, Farmingdale Village Water District. Personal Communication. 21 April. (Appendix 1.3-6.)
28. LIRPB. 1985. Population Survey 1985. Current Population Estimates for Nassau and Suffolk Counties. Hauppauge, Long Island, New York.
29. SCWA. 1986. Active Service Estimates and Service Area Map. (Appendix 1.5-8.)

REFERENCE NO. 5

02-8801-20-PA
REV. NO. 0

02-8801-20-PA

REV. NO. 0

**PRELIMINARY ASSESSMENT
NTU CIRCUITS, INC.**

PREPARED UNDER

**TECHNICAL DIRECTIVE DOCUMENT NO. 02-8801-20
CONTRACT NO. 68-01-7346**

FOR THE


**ENVIRONMENTAL SERVICES DIVISION
U.S. ENVIRONMENTAL PROTECTION AGENCY**

MARCH 11, 1988

**NUS CORPORATION
SUPERFUND DIVISION**


SUBMITTED BY:

REVIEWED/APPROVED BY:



**ROBERT NIES
PROJECT MANAGER**

**RONALD M. NAMAN
FACILITY MANAGER**



N U S
CORPORATION

POTENTIAL HAZARDOUS WASTE SITE

PRELIMINARY ASSESSMENT

02-8801-20-PA

Rev. No. 0

NTU Circuits, Inc.

Site Name

NYD981562614

EPA Site ID Number

60 Dale Street, West Babylon, New York

Address

02-8801-20

TDD Number

Date of Site Visit: Off-site reconnaissance, 01/18/88

SITE DESCRIPTION

The NTU Circuits, Inc. Site is located in an industrial park in West Babylon, Suffolk County, New York. Printed circuit boards for electronic applications were manufactured at the facility. Part of the NTU Circuits building was occupied by Welding Metallurgy during the time that NTU was in operation.

The site consisted of six leaching pools which received discharge from the manufacture of printed circuit boards. The leaching pools were under SPDES regulations; however, NTU violated the SPDES effluent standards on several occasions. The Suffolk County Health Department (SCHD) also documented that the pools were overflowing and running into adjacent storm drains.

As a result of past violations, the SCHD obtained a Consent Order from NTU Circuits to clean up all existing leaching pools prior to their moving to a new facility located in Bayshore, New York. The waste that was removed was taken to the new facility and treated in their on-site waste treatment plant.

Presently, the site is occupied by Midmer, Inc. and Welding Metallurgy. The area of concern has been paved since 1983.

PRIORITY FOR FURTHER ACTION: High ☐ Medium ☐ No Further Action ☒

RECOMMENDATIONS

In December 1983, NTU Circuits excavated the leaching pits of all waste and several feet of natural soils from below the waste area. This was completed as a result of a Consent Order from the Suffolk County Health Department (SCHD). The SCHD was responsible for technical oversight of the removal procedures. (See Attachment)

Prepared by: Robert G. Nies
of NUS Corporation

Date: 03/11/88

POTENTIAL HAZARDOUS WASTE SITE

PRELIMINARY ASSESSMENT

02-8801-20-PA

Rev. No. 0

RECOMMENDATIONS

The New York State Department of Environmental Conservation (NYSDEC) has also been involved with the site. They have completed a Phase I investigation and are considering a Phase II investigation.

A preliminary HRS score for the NTU Circuits Site is $S_m = 28.97$. This score is based on information from sampling conducted prior to the SCD Consent Order for waste removal.

Based on the above information, it is recommended that no further action be taken at this time on the NTU Circuits Site under the Federal Superfund Program. A site followup inspection may be necessary to confirm the NYSDEC's course of action.

PRELIMINARY ASSESSMENT (PA) CHECKLIST

Part 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

State New York

Site Number NYD981562614

II. SITE NAME AND LOCATION

Site Name NTU Circuits, Inc.

Address 60 Dale Street, ~~West~~ Babylon, New York 11704

County Code 103

Congressional District 2

Coordinates (latitude and longitude in degrees, minutes, seconds, or Township and Ranger numbers). 40° 43' 52"N 73° 23' 23"W

Direction to site (starting from nearest public road). From Edison Avenue turn left onto Dale Street. The site is on the left hand side of the road.

III. RESPONSIBLE PARTIES

Owner(s) Spectrum Finishing Company

Address (business, mailing, residential) ^{51 Cabot Street} ~~51 Cabot Street, Babylon, New York~~

Telephone Number (516) 694-0306

Operator NTU Circuits

Address (business, mailing, residential) 60 Dale Street, ~~West~~ Babylon, New York

Telephone Number (516) 752-0265

Type of Ownership (specify private, Federal, state, county, municipal) Private

IV. REGULATORY STATUS

Clean Water Act (CWA)

- Does the facility have an SPDES permit? NTU Circuits has relocated but they did have a SPDES permit (No. NY010860) while at the facility. Ref. Nos. 1, 5
- Is the facility in compliance with conditions of the permit? No. The facility had discharge violations of copper, lead, iron, and cadmium. Ref. Nos. 2, 7, 8.

Solid Waste Disposal Act (SWDA) as amended by the Resource Conservation and Recovery Act (RCRA)

- Is the facility a hazardous waste treatment storage, or disposal facility, or a combination facility? Yes, the facility had a part 360 permit for the storage of waste drums. Ref. Nos. 3, 6.

V. SITE HISTORY

Site Operations (ongoing, abandoned) NTU Circuits is no longer located at this address. Presently, Midmer, Inc. is using the building space that NTU occupied previously. Ref. No. 13.

Years of Operation 1977 to October 1983

VI. INFORMATION SOURCE

Contact

Agency/Organization New York State Department of Environmental Conservation

Telephone Number (516) 751-7900

Person Responsible for Assessment Robert G. Nies

Agency/Organization NUS Corporation, Region 2 FIT

Telephone Number (201) 225-6160

Date of Completion March 11, 1988

Part 2 - WASTE INFORMATION

I. WASTE TYPE

Chemical Classification (organics, inorganics, pesticides, acids, bases, oily wastes, metals, etc.) Inorganics. Ref. Nos. 2, 4, 5.

II. HAZARDOUS SUBSTANCES

Description of Substances (type, volume) Copper, lead, iron, and cadmium. Volumes are unknown. Ref Nos. 2, 4, 5.

Physical State of Wastes as Deposited Liquid. Ref Nos. 1, 2.

Waste Quantity Unknown

Storage/Disposal Method Waste sludge and drag-out tank waste is stored in drums and hauled off every two weeks. SPDES discharge occurs during working hours Monday through Saturday.

Concentration if Known Copper - 4.5 mg/L, Lead - 8.6 mg/L. Ref. No. 4. Iron - 8.0 mg/L, cadmium - 0.03 mg/L, Ref. No. 2.

Waste Characteristics* Wastes are toxic and persistent. Ref. No. 15.

*Waste Characteristics: Toxic, corrosive, persistent, soluble, infectious, flammable, ignitable, highly volatile, explosive, reactive, incompatible.

- Does the facility have interim status? At the time the permit was issued, the facility had to upgrade their storage tanks and storage area to meet the regulations. Ref. Nos. 3, 4.
- Has the facility filed Part A and/or Part B permit applications? Unknown
- Is it in compliance with conditions of the permit? No violation has been reported
- Is it an on-going facility or is it in closure or post-closure status? Postclosure status
- Has an enforcement action been taken against the user or operator? Yes, NTU was forced by the Suffolk County Department of Health Services to empty the sanitary pools used for SPDES discharge. Ref. Nos. 9, 10, 11, 12.
- Are there units at the facility that are not covered by RCRA? No

Marine Protection, Research, and Sanctuaries Act of 1972

- Does the facility have a permit issued by EPA or the Corps of Engineers for the transport and dumping of dredged materials into ocean waters? No

Safe Drinking Water Act (SDWA)

- Does the facility have an underground injection control permit? No
- Are the substances involved subject to Maximum Contaminant Level (MCL) goals? Yes

Clean Air Act (CAA)

- Is the facility subject to primary and secondary ambient air quality standards under the Clean Air Act? No
- Is the facility subject to new stationary source performance standards? No
- Does the facility have a Part C or Part D permit? Unknown

Atomic Energy Act (AEA)

- Does the release involve source, by-product, or special nuclear incident and come within the financial protection requirements established by the Nuclear Regulatory Commission (NRC)? No
- Is the facility licensed by the NRC? No

Surface Mining Control and Reclamation Act (SMCRA)

- Is the site subject to the reclamation requirements for abandoned mine sites? No
- Does the facility have a surface mining permit? No

Nuclear Waste Policy Act (NWPAA) and the Low-Level Radioactive Waste Policy Amendments Act (LLRWPA)

- Is the facility a low-level radioactive waste disposal facility? No

Uranium Mill Tailings Radiation Control Act (UMTRCA)

- Is the site licensed by the NRC? No
- Have the licensing conditions been violated? No
- Is the site potentially subject to remedial action by a State or the NRC? No

Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA)

- Is the involved substance subject to and in compliance with registration requirements of FIFRA? No. This does not apply.

Toxic Substances Control Act (TSCA)

- Is the involved substance entered in the inventory maintained by EPA under the requirements of TSCA? No

III. WASTE CONTAINMENT

Methods of waste storage and disposal used. Solid waste was stored in 55-gallon drums and disposed of by a hauler biweekly. Liquid wastes were discharged into sanitary pools daily under a SPDES permit. Ref. Nos. 1, 2, 3, 4.

Describe the condition (effectiveness) of each storage disposal unit. The drums were stored in a bermed area on an impermeable surface. The sanitary pools were not effective because of the potential for groundwater contamination. Ref. Nos. 1, 2, 3, 4.

Is there a run-on diversion system for storage and disposal units at the site? The storage area was bermed but the disposal area had no run-on diversion systems. Ref. Nos. 3, 4.

Do any of the storage or disposal units have natural or artificial liners to prevent waste migration? The part 360 permit states that the waste drums must be placed on an impermeable surface with a dike or berm surrounding it. The sanitary pools discharge directly to the groundwater system. There are no liners below the sanitary pools. Ref. Nos. 1, 3, 8.

Does the site or individual storage or disposal units have any type of leachate collection system? No. Ref. Nos. 3, 4.

If waste piles are present on site, are they stabilized and/or covered? There is no waste presently on site. NTU removed it under a Consent Order from the Suffolk County Department of Health Services in December 1983.

PART 3 - SITE CHARACTERISTICS AND MIGRATION ROUTES**I. GROUND WATER ROUTE**

Does quantitative data exist for an observed groundwater release? If yes, note types of contamination and provide analytical findings (levels reported). No. There are several monitoring wells in the area of NTU Circuits; however, they are not sufficient to determine an observed release. Ref. No. 16.

Does qualitative evidence exist for a groundwater release (i.e., objectionable taste or smell)? If yes, explain. No. There is no documentation to support a qualitative release to groundwater.

Do monitoring wells exist? How many? There are a number of monitoring wells in the area at two nearby CERCLA sites; however, the exact number is unknown. There are no wells at the former NTU Circuits facility. Ref. Nos. 14, 16, 27.

Are monitoring wells contaminated? The wells near the Babylon Landfill Site which is 2 blocks east of the NTU Site, have confirmed contamination; however, it is not associated with the NTU Circuits facility. Ref. No. 17.

Are private, public and/or commercial wells contaminated? If yes, explain. There are no wells that have been closed due to contamination from the site. The NYSDEC is considering monitoring well installation to determine possible groundwater contamination. Ref. No. 16.

Describe the stratigraphy from the surface to the aquifer of concern (names, thickness, type of material). 1) Upper Glacial Aquifer - Pleistocene Age glacial outwash deposits made up of sand and gravel. The formation is approximately 75 feet thick. 2) Magothy Aquifer - Cretaceous Age sand, silt, and clay deposits approximately 800 feet thick. The Gardiners Clay may be present beneath the site in certain areas but it is not believed to be continuous. This clay would be positioned between the Upper Glacial and the Magothy Aquifers. Ref. Nos. 22, 23, 24, 25.

What is the distance to the nearest well? The Suffolk County Water Authority well located at the Gordon Avenue well field is approximately 6400 feet from the site. Ref. No. 26.

Which aquifers are the private, public and/or commercial wells screened in? Name and describe known or potential aquifers. The wells, private and public, are screened in the Upper Glacial and the Magothy Aquifers. Ref. Nos. 25, 27.

Types of aquifers/aquitards:

- Type Overburden (The Upper Glacial and the Magothy Aquifers are hydraulically connected.
- Thickness 0-800 feet
- Depth 800 feet
- Aquifer of Concern Upper Glacial and the Magothy Aquifers
- Contaminated? The Upper Glacial has documented TCE contamination. Ref. No. 27.

Does any evidence exist for aquifer/aquitard discontinuities or aquifer interconnections? Explain. There is evidence of the Gardiners Clay existing below the site; however, it is not known to be continuous within the 3-mile radius of the site.

Are background (upgradient) wells available? No. There are wells in the area but there are other potential sources in the area that may cause contamination. Ref. No. 16.

Estimate net precipitation (total precipitation minus evapotranspiration). 15 inches. Ref. No. 15.

Does site geology minimize the potential for migration of contaminants to underlying aquifers? If yes, explain. No. The soils below the site consist mainly of sand and gravel material which are highly permeable. Ref. Nos. 22, 24, 25, 27.

Do the containment procedures utilized at the facility prevent migration of contaminants to underlying aquifers? If yes, explain. No. They did not have any containment structures. The discharge was directly to the groundwater system. Ref. Nos. 1, 2, 4, 5, 7, 8.

Do any potential barriers to horizontal groundwater migration exist within 4 miles of the facility for (HRS purposes, a barrier must completely transect an aquifer)? If yes Explain. No. Geologic information does not indicate any barriers to exist within 4 miles of the site. Ref. Nos. 22, 24, 27.

Is groundwater used for drinking water? If yes, is it obtained from private well(s) or public supply well(s)? Describe the location, depth and screened interval(s) of each well. Yes. There are public wells in the area. See Reference Number 26 for description of wells. Ref. No. 26.

Is an unthreatened, alternate water source presently available with minimum hook-up requirements? If yes, explain. Yes. The Suffolk County Water Authority Water System consists of several well fields in the area; therefore, other wells could be utilized if a well were to become contaminated. Ref. Nos. 20, 26.

Is groundwater used for other purposes? Possibly for irrigation, but these wells are not regulated by any department. Ref. No. 28.

Estimate the population on groundwater within a 4-mile radius of the site (assume 3.8 persons per residence or residential well). The total population served by groundwater is 231,239. Ref. No. 26.

Do forage crops exist that are irrigated by water drawn from the aquifer of concern? If yes, estimate the number of acres. There may be some forage crops that are irrigated by groundwater but the wells are not registered with any state departments. Ref. No. 28.

Estimate the population served by groundwater indirectly through irrigation (assume 1.5 persons per acre). Unknown

II. SURFACE WATER ROUTE

Does quantitative data exist for an observed surface water release? If yes, note types of contamination and provide analytical findings (levels reported). No

Does qualitative evidence exist for a surface water release (i.e., objectionable color, taste or smell)? No

What is the type(s) of nearby surface water? There are no surface waters near the site that would have a direct migratory pathway from the site. Ref. No. 18.

Creek
Stream and/or River (continuously flowing)
Pond
Lake
Swamp/Marsh

Is the facility located in surface water (i.e., swamp/marsh)? No. Ref. No. 18.

Provide a 1-year, 24-hour rainfall estimate for the site in inches. 26 inches, Ref. No. 15.

Estimate facility slope and slope of intervening terrain, i.e., between beginning of overland migration path and probable point of entry into surface water (calculate from topographic map). The facility slope is less than 1 percent. The nature of the intervening terrain is not relevant because there is no surface water in the immediate vicinity of the site. Ref. Nos. 13, 15.

Does surface topography at the site minimize the potential for migration of contaminants to surface water? Yes. There are no surface waters in the immediate vicinity of the site; therefore, there is no potential for surface water contamination. Ref. No. 15.

What is the distance along the overland segment of the migration path(s) from the most downslope point of potential contamination (use site boundary as a first approximation) to the probable point of entry into surface water? Not applicable. Ref. No. 15.

What are the surface water uses in the vicinity of the site (5-mile distance downstream)? Not applicable

Drinking Water

Recreation

Irrigation Commercial or Industrial

Economically Important Resources (i.e., shellfish)

Is there a coastal wetland (5-acre minimum) within 2 miles maximum, which could be contaminated? How far? No. Ref. No. 15.

Is there a fresh water wetland (5-acre minimum) within 1 mile maximum, which could be contaminated? How far? No. Ref. No. 15

Is there a critical habitat of a Federally designated endangered species within 1 mile maximum, which could be contaminated? How far? No. Ref. No. 19.

What is the distance to the nearest drinking water intake within 3 stream or 1 static water miles? There are no drinking water intakes within 3 miles of the site. Ref. No. 20.

What is the population using surface water intakes within 3 miles of the site (assume 3.8 persons per household)? In the case of multiple intakes, show the number persons served by each intake. Not applicable

Do forage crops exist that are irrigated by water from surface water intakes? If yes, estimate the number of acres. No. Ref. No. 28.

Estimate the population served by surface water indirectly through irrigation (assume 1.5 persons per acre). Not applicable

What is the total population using surface water? Not applicable

III. AIR ROUTE

Does quantitative data exist for an observed air release? If yes, note types of contamination and provide analytical findings (levels reported). Describe the sampling methods and equipment used to collect the analytical data. No.

Does qualitative evidence exist for an air release (i.e., odor, poor containment, high volatility contaminants)? No.

Have any citizens complaints regarding potential air releases (i.e., odor, nausea, illness) been recorded? When did they occur and what was the nature of the complaint? None documented.

List the names of the most incompatible pairs of materials found on-site. Describe the extent to which their presence poses a hazard. There is no waste or raw materials on site. All material was removed when NTU Circuits relocated its facility. Ref. Nos. 10, 11, 12.

Evaluate the toxicity of the most hazardous materials (5 maximum) at the facility that are capable of migration by the air route (volatiles, particulates), and are imperfectly contained with respect to the potential for air migration. Not applicable. There is no possibility for air contamination because no waste is on site. Ref. Nos. 9, 10, 11, 12.

Determine the population potentially exposed to contaminant release for 1/4, 1/2, 1 and 4 miles from the source. The distance to targets is a radial distance from the site without consideration of the prevailing wind direction. Assume 3.8 persons per residence for population counts. Not applicable

Is there a coastal wetland (5-acre minimum) within 2 miles maximum of the site, which could be contaminated? How far? No. Ref. No. 18.

Is there a freshwater wetland (5-acre minimum) within 1 mile maximum of the site, which could be contaminated? How far? No. Ref. No. 18.

Is there a critical habitat of a Federally designated endangered species within 1 mile maximum which could be contaminated? How far? No. Ref. No. 19.

PART 4 - FACTORS AFFECTING REMOVAL ACTION DECISIONS

1. DIRECT CONTACT THREAT

Does quantitative evidence exist for on-site soil contamination? If yes, note contaminant sources and summarize analytical results (levels reported). No. The leaching pools have been cleaned of all waste and the site has been paved. Ref. Nos. 9, 10, 11, 12.

Does qualitative evidence exist for on-site soil contamination (i.e., photographic evidence of spill areas or stressed vegetation)? No. Ref. No. 13.

Estimate the area affected or potentially affected by soil contamination (acres). The area potentially affected is less than 1 acre. Ref. No. 12.

Is site access restricted to non-facility personnel? How? Site access is not restricted; however, the sanitary pools have been cleaned out, filled with sand, and paved over since December 1985. Ref. No. 12.

Does the potential exist for facility personnel to easily come in contact with hazardous materials? If yes, how? No. The sanitary pool area is now paved over. Ref. No. 12.

Estimate the population within 1 mile of the facility (assume 3.8 persons per residence). There are 4744 people within 1 mile. Ref. No. 21.

As a result of recreational activities, is direct contact possible. No. The site is located within an industrial park. Ref. No. 13.

II. FIRE/EXPLOSIVE CONDITIONS

Has the State and/or local Fire Marshall certified that the site is a fire/hazard or presents an explosive threat? If yes, when was the determination made, and what circumstances led to that finding? No

Are incompatible or ignitable wastes present at the site? If yes, list them. No. All wastes were removed under a Consent Order from the Suffolk County Department of Health Services. Ref. No. 12.

If there is no confirmed threat (i.e., certified fire or explosive hazard), is there a potential threat? If yes, explain the nature of the potential threat. No. There are no wastes on site. Ref. No. 12.

What is the distance to the nearest population? The nearest residential population is less than $\frac{1}{4}$ mile; however, there are people working on site and at adjacent properties. Ref. Nos. 12, 21

Estimate the population within 2 miles of the site (assume 3.8 persons per residence). There are 39,423 people within 2 miles of the site. Ref. No. 21.

What is the distance to the nearest building? On site. Ref. Nos. 1, 4, 13

PART 5 - OTHER INFORMATION AREAS

I. SAMPLE DATA

- | | | |
|----------------------|-----------------------|----------------|
| - Sample objective | - QA/QC | See Attachment |
| - Age/comparability | - Chain-of-custody | |
| - Analytical methods | - Sample preservation | |
| - Detection limits | - Sample shipment | |
| - Sampling methods | - Holding times | |

A brief narrative summary, addressing the above considerations, should be provided for each sample result.

II. CONTAMINATION OF FOOD CHAIN

Have there been contaminant impacts on food crops? If yes explain. If no, discuss the potential impacts. No

Have there been contaminant impacts on livestock (i.e., cattle, chickens)? If yes, explain. If no, discuss the potential impacts. No

III. DAMAGE TO FLORA AND FAUNA

Any observed occurrences (i.e., photo documentation) of damage to flora? If yes, give date and extent of damage. If no, describe the potential for damage. No. The site is within an industrial park; therefore, most of the surrounding property is void of any vegetation. Ref. No. 13.

Any observed occurrences of damage to fauna? If yes, give date and extent of damage. If no, describe the potential for damage. No. The site is located within an industrial park; therefore, the fauna population is limited in the area. Ref. No. 13.

IV. DAMAGE TO OFF-SITE PROPERTY

Have off-site properties (i.e., private/commercial real estate, storm drains, sewers, etc.) been damaged by site activities? If yes, give date(s) and describe event(s). If no, describe any potential problems. Yes. Storm drain contamination was confirmed on October 26, 1983 to be above the standard for the SPDES permit held by NTU Circuits. Ref. No. 2.

Has the facility received hazardous waste without a proper local, State and/or Federal permit(s)? If yes, give date(s) and describe event(s). No. They discharged waste into sanitary pools and also, stored it in drums on site. Ref. Nos. 1, 2, 3, 4.

Does site security (or lack of security) promote unauthorized dumping? Explain. No. The site is a building with only limited paved areas surrounding the facility. Ref. Nos. 4, 13.

ATTACHMENT

PART 5 - OTHER INFORMATION AREAS

I. SAMPLE DATA

On October 26, 1983 the Suffolk County Department of Health Services collected a sample from an on-site storm drain and sanitary cesspool, respectively. The sampling objective was to test for violation of a SPDES permit. The result showed the concentration to be higher than the maximum allowed in the SPDES permit. Lead, copper, iron, and cadmium all exceeded the standard for groundwater effluent. No other information is available on the sampling event or analyses. Ref. No. 2.

APPENDIX A
MAPS AND PHOTOS


NTU CIRCUITS, INC.
WEST BABYLON, NEW YORK

CONTENTS

Figure 1: Site Location Map

Figure 2: Site Map

Exhibit A: Photograph Log



(QUAD) AMITYVILLE, N.Y.


SITE LOCATION MAP

NTU CIRCUITS INC., WEST BABYLON, N.Y.

SCALE: 1" = 2000'

FIGURE 1





SITE MAP
NTU CIRCUITS INC., WEST BABYLON, N.Y.
 (NOT TO SCALE)

EXHIBIT A

PHOTOGRAPH LOG

NTU CIRCUITS, INC.
WEST BABYLON, NEW YORK

Off-Site Reconnaissance: 1-18-88

NTU CIRCUITS
WEST BABYLON, NEW YORK

PHOTOGRAPH INDEX

<u>Photo Number</u>	<u>Description</u>	<u>Time</u>
1P-9	View of building off Dale St. facing west.	1603
1P-10	View of back portion of building, which is occupied by Welding Metallurgy, from driveway facing north west.	1617

ALL PHOTOGRAPHS TAKEN BY MIKE GENTILS.

NTU CIRCUITS, WEST BABYLON, NEW YORK




1P-9

January 18, 1988

1603

View of building off Dale St. facing west.



1P-10

January 18, 1988

1617

View of back portion of building, which is occupied
by Welding Metallurgy from driveway facing north west.

REFERENCE NO. 6

Copies: SPDES File

Fac. ID No.

A. 0108260

Region #1

Suffolk Co. DHS

Effective Date (EDP) : October 1, 1980

Mr. Crandall - BPC

Expiration Date (ExDP) : October 1, 1985

Mr. Adamczyk - BIP

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM (SPDES)
DISCHARGE PERMIT

Special Conditions
(Part I)

This SPDES permit is issued in compliance with Title 8 of Article 17 of the Environmental Conservation Law of New York State and in compliance with the Clean Water Act, as amended, (33 U.S.C. §1251 et. seq.) (hereinafter referred to as "the Act").

NTU Circuits, Inc.
60 Dale Street
West Babylon, NY 11704

Attention: Mr. Tim Wu, Owner
is authorized to discharge from the facility described below:

N. T. U. Circuits, Inc.
60 Dale Street
Babylon (T), Suffolk Co.
West Babylon, New York

into receiving waters known as:

Groundwater

in accordance with the effluent limitations, monitoring requirements and other conditions set forth in this permit.

This permit and the authorization to discharge shall expire on midnight of the expiration date shown above and the permittee shall not discharge after the expiration date unless this permit has been renewed, or written authorization is given by the Department. In order to receive authorization to discharge beyond the expiration date, the permittee shall submit such information, forms, and fees as are required by the Department of Environmental Conservation no later than 180 days prior to the expiration date.

By Authority of George K. Hansen, P.E., Chief, PDES Permit Section
Designated Representative of Commissioner of the
Department of Environmental Conservation

AUG 26 1980

Date

George K. Hansen
Signature

SEP 29 1980

S.C. DEPT. OF
HEALTH SERVICES

REFERENCE NO. 7

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date July 25, 1979

WPU Laboratories, Inc.
60 Dale St.
W. Babylon, N.Y. 11704

Gentlemen:

On July 10, 1979 samples of your industrial waste were taken from your discharge into storm drain (s/s bldg.). Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|-------------|-----|
| 1. pH - 8.9 | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|-------------------|-----|
| 1. pH - 6.5 - 8.5 | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

Appendix 1.1-6

p. 1 of 28



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLINGDate Oct. 11, 1979

NTU Laboratories, Inc.
60 Dale Street
W. Babylon, N.Y. 11704

Gentlemen:


On Sept. 20, 1979 samples of your industrial waste were taken from your overflowing pool SPA see attached diagram. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|-----------------------|-----|
| 1. pH - 3.6 | 6. |
| 2. Copper - 32 mg/l | 7. |
| 3. Iron - 28 mg/l | 8. |
| 4. Cadmium - .07 mg/l | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|-----------------------|-----|
| 1. pH - 6.5 - 8.5 | 6. |
| 2. Copper - 1 mg/l | 7. |
| 3. Iron - .6 mg/l | 8. |
| 4. Cadmium - .06 mg/l | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.


Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)



p. 3 of 28

DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLINGDate Oct. 11, 1979

MTU Laboratories, Inc.
60 Dale Street
W. Babylon, N.Y. 11704

Gentlemen:

On Sept. 25, 1979 samples of your industrial waste were taken from your SPA - see attached diagram. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|------------------------|-----|
| 1. pH - 4.5 | 6. |
| 2. Fluoride - 3.2 mg/l | 7. |
| 3. Copper - 13.7 mg/l | 8. |
| 4. Iron - 13 mg/l | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|----------------------|-----|
| 1. pH - 6.5 - 8.5 | 6. |
| 2. Fluoride - 3 mg/l | 7. |
| 3. Copper - 1 mg/l | 8. |
| 4. Iron - .6 mg/l | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

COUNTY OF SUFFOLK

p. 4 of 28



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Oct. 11, 1979

RTU Laboratories, Inc.
60 Dale Street
W. Babylon, N.Y. 11704

Gentlemen:

On Sept. 25, 1979 samples of your industrial waste were taken from your storm drain #2 - see attached diagram. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|----------------------|-----|
| 1. pH - 4.3 | 6. |
| 2. Copper - 9.2 mg/l | 7. |
| 3. Iron - 2.1 mg/l | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|--------------------|-----|
| 1. pH - 6.5 - 8.5 | 6. |
| 2. Copper - 1 mg/l | 7. |
| 3. Iron - .6 mg/l | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

(016) 234-2022

COUNTY OF SUFFOLK



p. 5 of 28

DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Oct. 11, 1979

NTU Laboratories, Inc.
60 Dale Street
W. Babylon, N.Y. 11704

Gentlemen:

On Sept. 25, 1979 samples of your industrial waste were taken from your storm drain #3 - see attached diagram. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|-----------------------|-----|
| 1. Cadmium - .07 mg/l | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|-----------------------|-----|
| 1. Cadmium - .02 mg/l | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Oct. 11, 1979

NTU Laboratories, Inc.
60 Dale Street
W. Babylon, N.Y. 11704

Gentlemen:

On Oct. 2, 1979 samples of your industrial waste were taken from your SPA - see attached diagram. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|------------------------------------|-----|
| 1. pH - 3.2 | 6. |
| 2. Dissolved Solids - 3,983 mg/l7. | |
| 3. Copper - 55 mg/l | 8. |
| 4. Iron - 10.6 mg/l | 9. |
| 5. Lead - 4.6 mg/l | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|------------------------------------|-----|
| 1. pH - 6.5 - 8.5 | 6. |
| 2. Dissolved Solids - 1,000 mg/l7. | |
| 3. Copper - 1 mg/l | 8. |
| 4. Iron - .6 mg/l | 9. |
| 5. Lead - .02 mg/l | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Oct. 11, 1979

NTU Laboratories, Inc.
60 Dale Street
W. Babylon, N.Y. 11704

Gentlemen:


On Oct. 2, 1979 samples of your industrial waste were taken from your SD 47 - see attached diagram. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|-----------------------|-----|
| 1. Cadmium - .04 mg/l | 6. |
| 2. Silver - .36 mg/l | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|-----------------------|-----|
| 1. Cadmium - .02 mg/l | 6. |
| 2. Silver - .1 mg/l | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.


Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Nov. 30, 1979

NTU Laboratories, Inc.
50 Dale St.
W. Babylon, N.Y. 11704

Gentlemen:

On 11/20/79 samples of your industrial waste were taken from your discharge point to S.P.A.. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|----------------------|-----|
| 1. Copper - 3.8 mg/l | 6. |
| 2. Iron - 2.3 mg/l | 7. |
| 3. Lead - 0.2 mg/l | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|--------------------|-----|
| 1. Copper - 1 mg/l | 6. |
| 2. Iron - .6 mg/l | 7. |
| 3. Lead - .05 | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

FIELD

LABORATORY

PATIENT NO.

LAB NO.

11-77 - 239

99828

COLLECTED BY

NAME, NOT INITIALS

C. 15007 - Fisher

TYPE SAMPLE

Flood.

DATE COL.

11/20/79

DATE REC'D.

11/20/79

TIME REC'D.

12:00

TIME COL.

9:45am

DATE COMPLETED

11/21/79

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

NAME OR FIRM

N. T. U. Labs

ADDRESS OR LOCATION

60 Duke St. W.B.

POINT OF COLLECTION

Point Discharge into S.P.A.

REMARKS/INSTRUCTIONS

Heavy discharge at time of collection

TEST	RESULT	TEST	RESULT	TEST	RESULT
CONDUCT	umho	NITRATE-N		✓ COPPER	3.8 1.0
✓ pH	7.8	NITRITE-N		✓ IRON	2.3 6
TEST	RESULT	AMMONIA-N		MANGANESE	
PH ALKALINITY		TKN		✓ CHROMIUM	4.02
T. ALKALINITY		O-PO ₄ -P		NICKEL	
CHLORIDE				✓ ZINC	60.1
FLUORIDE				MAGNESIUM	
CYANIDE		TOT. SOLIDS		CALCIUM	
		SUS SOLIDS		✓ LEAD	0.2 .05
SULFATE		DISS. SOLIDS		✓ CADMIUM	1.02
MBAS				✓ SILVER	.02
✓ C.O.D.	3.1 x 10 ¹			SODIUM	
T.O.C.				POTASSIUM	
				BARIUM	
		FIELD D.O.			
		FIELD TEMP			
		FIELD pH			
		FIELD COND.	umho		

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date 12/10/79

WTU Laboratories, Inc.
60 Dale Street
W. Babylon, New York
11704

Gentlemen:

On 9/25/79 samples of your industrial waste were taken from your industrial waste. Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|----------------------------|-----|
| 1. pH - 4.5 | 6. |
| 2. Fluoride - 3.2 mg/liter | 7. |
| 3. Copper - 13.7 mg/liter | 8. |
| 4. Iron - 13 mg/liter | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|----------------------------|-----|
| 1. pH range - 6.5-8.5 | 6. |
| 2. Fluoride - 3.0 mg/liter | 7. |
| 3. Copper - 13.7 mg/liter | 8. |
| 4. Iron - .6 mg/liter | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

FIELD

204

LAB NO.

C-71-351 p 4828

BY

Olsen

NAME, NOT INITIALS

TYPE SAMPLE

IND.

DATE REC'D.

9/25

TIME REC'D.

NOON

DATE COMPLETED

9/26 JQ

COL.

09-25-79

COL.

10:50 AM

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

MC. F-?

MBAS 10/22

NAME OR FIRM

NTU Laboratories

ADDRESS OR LOCATION

60 Dale St, West Babylon

POINT OF COLLECTION

Sanitary Pool #A, being used

REMARKS/INSTRUCTIONS

as an industrial pool

if possible

TEST	RESULT	TEST	RESULT	mg. liter	TEST	RESULT	mg. liter
CONDUCT	umho	NITRATE-N	0.2		COPPER 1.0	13.7	
pH 6.5-8.5	4.5	NITRITE-N	0.07		IRON .6	13.	
TEST	RESULT	AMMONIA-N	12.		MANGANESE		
ph. ALKALINITY		TKN			CHROMIUM	0.02	
T. ALKALINITY		O-PO ₄ -P			NICKEL	0.5	
CHLORIDE 65					ZINC	<0.1	
FLUORIDE 3.0	3.2				MAGNESIUM		
CYANIDE		TOT. SOLIDS	330.		CALCIUM		
		SUS. SOLIDS	26.		LEAD	<0.2	
SULFATE		DISS. SOLIDS	304.		CADMIUM	<0.02	
MBAS .04					SILVER	<0.02	
C.O.D. 9. X 10'					SODIUM		
T.O.C.					POTASSIUM		
					BARIUM		
		FIELD D.O.					
		FIELD TEMP					
		FIELD pH					
		FIELD COND.		umho			

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Dec. 20, 1979

NTU Laboratories, Inc.
50 Dale St.
W. Babylon, N.Y. 11704

Gentlemen:

On 12/11/79 samples of your industrial waste were taken from your storm drain #2 (see diagram). Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|----------------------|-----|
| 1. Copper - 6.9 mg/l | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:-

- | | |
|--------------------|-----|
| 1. Copper - 1 mg/l | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

FIELD

LABORATORY

FILE NO.

203

COL BY

Felice, J.P.
NAME, NOT INITIALS

Received from:

Suffolk Co. Dept. of Health

LAB NO.

12-79-110

P. 13828

DATE REC'D.

12/11

TIME REC'D.

NOON

DATE COL.

12/11/79

TIME COL.

11:05AM

DATE COMPLETED

12/13/79 except C-76

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

NAME OR FIRM

N.T. V. LABS

ADDRESS OR LOCATION

50 DALE STREET, W. BABYLON

POINT OF COLLECTION

STORM DRAIN #2 - AT THE END OF THE

REMARKS/INSTRUCTIONS

BUILDING FURTHEST FROM DALE ST. (GREEN STAIN ON

GROUND LEADING TO THIS DRAIN.)

TEST	RESULT	TEST	RESULT	TEST	RESULT
CONDUCT	umho	NITRATE-N		✓ COPPER	1.0
✓ pH	8.6	NITRITE-N		✓ IRON	6.9
TEST	RESULT	AMMONIA-N		MANGANESE	.57
ph. ALKALINITY		TKN		✓ CHROMIUM	.24
T. ALKALINITY		O-PO ₄ -P		✓ NICKEL	<0.1
CHLORIDE				✓ ZINC	.05
FLUORIDE				MAGNESIUM	
CYANIDE		✓ TOT. SOLIDS	167.	CALCIUM	
		✓ SUS. SOLIDS	24.	✓ LEAD	0.3
SULFATE		✓ DISS. SOLIDS	143.	✓ CADMIUM	<.02
MBAS				✓ SILVER	<.02
C.O.D.				SODIUM	
B.C.C.				POTASSIUM	
				BARIUM	
		FIELD TEMP			
		FIELD pH			
		FIELD COND.	umho		

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Dec. 20, 1979

NTU Laboratories, Inc.
50 Dale St.
W. Babylon, N.Y. 11704

Gentlemen:


On 12/11/79 samples of your industrial waste were taken from your storm drain #3 (see diagram). Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|----------------------|-----|
| 1. Copper - 7.2 mg/l | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

- | | |
|--------------------|-----|
| 1. Copper - 1 mg/l | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.


Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

FIELD

LABORATORY

LD NO.

#202

COL. BY

FELICE, J.P.
NAME, NOT INITIALS

DATE COL

12/11/79

TIME COL

10:55 AM

LAB NO.

12-79-109 915828

TYPE SAMPLE

Ind.

DATE REC'D.

12/11

TIME REC'D.

NOON

DATE COMPLETED

12/13 jc

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

NAME OR FIRM

N.T.U. LABS

ADDRESS OR LOCATION

50 Dale Street W. Babylon

POINT OF COLLECTION

Storm Drain #23 - Between Side

REMARKS/INSTRUCTIONS

Delivery Does - new Pipe Leading to This Storm
Drain - Heavy Flow at This Time from Pipe.

TEST		RESULT	TEST		RESULT	TEST		RESULT
		umho			mg. liter			mg. liter
CONDUCT			NITRATE-N			✓ COPPER	1.0	7.2
✓ pH		7.05	NITRITE-N			✓ IRON		.27
	TEST	RESULT	AMMONIA-N				MANGANESE	
		mg. liter	TKN			✓ CHROMIUM		<.02
ph. ALKALINITY			0-PO ₄ -P			✓ NICKEL		0.1
T. ALKALINITY						✓ ZINC		.03
CHLORIDE							MAGNESIUM	
FLUORIDE							CALCIUM	
CYANIDE			✓ TOT. SOLIDS		299.		LEAD	<.2
			✓ SUS. SOLIDS		20.	✓ CADMIUM		<.02
			✓ DISS. SOLIDS		279.	✓ SILVER		<.02
SULFATE							SODIUM	
MBAS							POTASSIUM	
C.O.D.							BARIUM	
T.O.C.								
			FIELD D.O.					
			FIELD TEMP					
			FIELD pH					
			FIELD COND.		umho			

COUNTY OF SUFFOLK



Received from:
Suffolk Co. Dept. of
Health

DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Dec. 20, 1979

NTU Laboratories, Inc.
50 Dale St.
W. Babylon, N.Y. 11704

Gentlemen:

On 12/11/79 samples of your industrial waste were taken from your storm drain #7 (see diagram). Upon analysis, the following parameters were found to be unsatisfactory:

- | | |
|-----------------------|-----|
| 1. Cadmium - .07 mg/l | 6. |
| 2. Silver - 1.1 mg/l | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:-

- | | |
|-----------------------|-----|
| 1. Cadmium - .02 mg/l | 6. |
| 2. Silver - .1 mg/l | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.


Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

FIELD

LABORATORY

LD NO.

#201

COL BY

Felice, J.P.
NAME, NOT INITIALS

DATE COL.

12/11/79

TIME COL.

10:45 AM

LAB NO.

12-79-108

117828

TYPE SAMPLE

Ind.

DATE REC'D.

12/11

TIME REC'D.

NOON

DATE COMPLETED

12/13 Jc

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

NAME OR FIRM

N. T. U. LABS

ADDRESS OR LOCATION

50 DALE ST. WEST BABYLON

POINT OF COLLECTION

STORM DRAIN #17 NEAREST DALE ST. NEAR

REMARKS/INSTRUCTIONS

SIDE ENTRANCE DOOR - (SLIGHT FLOW FROM INLET
PIPE) AT TIME OF COLLECTION.

TEST	RESULT	TEST	RESULT	TEST	RESULT
CONDUCT	umho	NITRATE-N		✓ COPPER	.07
✓ pH	6.9	NITRITE-N		✓ IRON	37
TEST	RESULT	AMMONIA-N		MANGANESE	
ph. ALKALINITY		TKN		✓ CHROMIUM	<.02
T. ALKALINITY		O-PO ₄ -P		✓ NICKEL	<0.1
CHLORIDE				✓ ZINC	.09
FLUORIDE				MAGNESIUM	
CYANIDE		✓ TOT. SOLIDS	101.	CALCIUM	
		✓ SUS. SOLIDS	13.	✓ LEAD	<0.2
		✓ DISS. SOLIDS	88.	✓ CADMIUM .02	0.7
SULFATE				✓ SILVER .1	1.1
MBAS				SODIUM	
C.O.D.				POTASSIUM	
T.O.C.				BARIUM	
		FIELD C.O.			
		FIELD TEMP			
		FIELD pH			
		FIELD COND.	umho		

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTIFICATION OF UNSATISFACTORY INDUSTRIAL WASTE SAMPLING

Date Feb. 5, 1980

MTU Laboratories, Inc.
50 Dale St.
W. Babylon, N.Y. 11704

Gentlemen:

On Dec. 11, 1979 samples of your industrial waste were taken from your storm drain at end of building*. Upon analysis, the following parameters were found to be unsatisfactory:

1. Hexavalent Chromium - .15 mg/l
2. 7.
3. 8.
4. 9.
5. 10.

The acceptable limits on each of these parameters, according to New York State Groundwater Standards are as follows:

1. Hexavalent Chromium - .1 mg/l.
2. 7.
3. 8.
4. 9.
5. 10.

*furthest from Dale St.

You should be aware that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please see that they are corrected as soon as possible. If you have any questions or need any assistance, please do not hesitate to contact this office.

Stephen A. Costa
Stephen A. Costa, P.E.
Industrial Waste and Hazardous
Materials Control Section

(GW)

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTICE OF VIOLATION: N.Y.S. ENVIRONMENTAL CONSERVATION LAW

N.T.U. Circuits Inc.
60 Dale Street
West Babylon, New York 11704

Date July 6, 1981
SPDES NO. NY0108260
Lab No. 6/81-74
Field No. 6 DO 6-10

Gentlemen:

On June 10, 1981 samples of industrial waste were taken from your storm drain receiving process water, southside of building. Upon analysis, the following parameters were found in concentrations above the maximum allowed in your SPDES permit or in groundwater effluent standards:

1. Cadmium - 0.03 mg/L
- 6.
- 7.
- 8.
- 9.
- 10.


Please be advised that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please be further advised that the discharge of any water from an industrial process to the groundwater of Suffolk County without having first obtained a State Pollutant Discharge Elimination System (SPDES) permit for that discharge is also a violation of the N.Y.S.E.C.L. and S.C. Sanitary Code, Art. 12.

If you do not already possess a valid SPDES permit for the above discharge, then you should apply immediately, through this office, for said permit.

Since the above noted violations may subject you to legal action, it is expected that these violations cease immediately. A reinspection in the near future will determine your compliance in this matter.

Very truly yours,

(SEE REVERSE SIDE FOR
STANDARDS)


John H. Finkenberg
Sanitarian
Environmental Pollution Control
JHF/cc

Central Islip, N. Y. 11722

FIELD

LABORATORY

FIELD NO. - G DO G-10LAB NO. 6/81-7482042BY DAVID DUBRIG
NAME, NOT INITIALSTYPE SAMPLE INDDATE COL. 10 JUNE 81DATE REC'D. 6/15/81TIME REC'D. ~ 117TIME COL. 1040 amDATE COMPLETED 6/21/81SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTENAME OR FIRM NTUADDRESS OR LOCATION DALE ST. FORMINGDALE (DARTMOUTH)POINT OF COLLECTION SD receiving process water, Southside 3 Bld.

REMARKS/INSTRUCTIONS

TEST	RESULT	TEST	RESULT <small>mg. liter</small>	TEST	RESULT <small>mg. liter</small>
CONDUCT	umho	NITRATE-N		COPPER	8.0
pH		NITRITE		IRON	
TEST	RESULT <small>m.g. liter</small>	AMMONIA-N		MANGANESE	
ph. ALKALINITY		TKN		CHROMIUM	.04
T. ALKALINITY		O-PO ₄ -P		NICKEL	2.1
CHLORIDE				ZINC	2.1
FLUORIDE				MAGNESIUM	
CYANIDE		TOT. SOLIDS		CALCIUM	
		SUS. SOLIDS		LEAD	.4
SULFATE		DISS. SOLIDS		CADMIUM	.03
MBAS				SILVER	2.02
C.O.D.				SODIUM	
T.O.C.				POTASSIUM	
				BARIUM	
		FIELD D.O.			
		FIELD TEMP			
		FIELD pH	7		
		FIELD COND.	umho		

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTICE OF VIOLATION: N.Y.S. ENVIRONMENTAL CONSERVATION LAW

N.T.U. Circuits Inc.
60 Dale Street
West Babylon, NY 11704

Date July 17, 1981
SPDES NO NY0108260
Lab No. 7-81-18
Field No. 1 DO 7-1

Gentlemen:

July 1, 1981 samples of industrial waste were taken from your
sani. pool #1 (pool 60 ft. southwest of N.T.U.)
on analysis, the following parameters were found in concentrations
above the maximum allowed in your SPDES permit or in groundwater effluent
standards:

- | | |
|------------------------|-----|
| 1. Copper - 440.0 mg/L | 6. |
| 2. Iron - 4.4 mg/L | 7. |
| 3. cadmium 0.06 mg/L | 8. |
| 4. Lead - 1.2 mg/L | 9. |
| 5. pH (field) - 11 | 10. |


Please be advised that these unsatisfactory conditions constitute viola-
tions of the N.Y.S. Environmental Conservation Law. Please be further
advised that the discharge of any water from an industrial process to
the groundwater of Suffolk County without having first obtained a State
Pollutant Discharge Elimination System (SPDES) permit for that discharge
is also a violation of the N.Y.S.E.C.L. and S.C. Sanitary Code, Art. 12.

If you do not already possess a valid SPDES permit for the above discharge,
then you should apply immediately, through this office, for said permit.

Since the above noted violations may subject you to legal action, it is
expected that these violations cease immediately. A reinspection in the
near future will determine your compliance in this matter.

Very truly yours,

(SEE REVERSE SIDE FOR
STANDARDS)


John H. Finkenberg
Sr. Sanitarian
Environmental Pollution Control
JHF/cc

Central Islip, N. Y. 11722

(810) 310-1022

FIELD

LABORATORY

FIELD NO. 1 DO9-1LAB NO. 7-81-18BY DAN O'CONNOR - R. OLSEN
NAME, NOT INITIALSTYPE SAMPLE INDUSTRIALDATE REC'D. 7/1/81TIME REC'D. 4:32 PM.DATE COMPLETED 7/13/81TE COL. 1 July 81E COL. 3:40 PMSUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTENAME OR FIRM NTU Circuits Inc.ADDRESS OR LOCATION 60 Dale St. Woburn, MAPOINT OF COLLECTION SEWER POOL #1

REMARKS/INSTRUCTIONS

DELIVERED TO XRAY LAB
4:47 PM 1 JUL 81

TEST	RESULT	TEST	RESULT	TEST	RESULT
CONDUCT	umho	NITRATE-N		✓ COPPER	44 x 10 ²
pH		NITRITE		✓ IRON	4.4
TEST	RESULT $\frac{mg}{liter}$	AMMONIA-N		MANGANESE	
ph. ALKALINITY		TKN		✓ CHROMIUM	1.06
T. ALKALINITY		O-PO ₄ -P		✓ NICKEL	1.2
CHLORIDE				✓ ZINC	1.3
FLUORIDE				MAGNESIUM	
CYANIDE		TOT. SOLIDS		CALCIUM	
		SUS. SOLIDS		✓ LEAD	1.2 oh
SULFATE		DISS. SOLIDS		✓ CADMIUM	0.06
MBAS				✓ SILVER	2.02
C.O.D.				SODIUM	
T.O.C.				POTASSIUM	
				BARIUM	
		FIELD D.O.			
		FIELD TEMP			
		FIELD pH	7.11		
		FIELD COND.	umho		

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTICE OF VIOLATION: N.Y.S. ENVIRONMENTAL CONSERVATION LAW

NTU Circuits, Inc.
60 Dale Street
West Babylon, New York 11704

Date 12-28-81
SPDES NO. NY 0108260
Lab No. 9-81-337
Field No. 3 DO 9-30

Gentlemen:

On 9-30-81 samples of industrial waste were taken from your
SPDES Discharge pool, receiving rinse water

Upon analysis, the following parameters were found in concentrations
above the maximum allowed in your SPDES permit or in groundwater effluent
standards:

- | | |
|---------------------|-----|
| 1. Lead - 2.4, mg/L | 6. |
| 2. | 7. |
| 3. | 8. |
| 4. | 9. |
| 5. | 10. |

Please be advised that these unsatisfactory conditions constitute viola-
tions of the N.Y.S. Environmental Conservation Law. Please be further
advised that the discharge of any water from an industrial process to
the groundwater of Suffolk County without having first obtained a State
Pollutant Discharge Elimination System (SPDES) permit for that discharge
is also a violation of the N.Y.S.E.C.L. and S.C. Sanitary Code, Art. 12.

If you do not already possess a valid SPDES permit for the above discharge,
then you should apply immediately, through this office, for said permit.

Since the above noted violations may subject you to legal action, it is
expected that these violations cease immediately. A reinspection in the
near future will determine your compliance in this matter.

Very truly yours,

(SEE REVERSE SIDE FOR
STANDARDS)

John H. Finkenberg
r. Sanitarian
Environmental Pollution Control
JHF/cc

Central Islip, N. Y. 11722

FIELD

LABORATORY

FIELD NO. 3 DO 930LAB NO. 9-81-337 P. 24BY 30-30-DAVID OBRIG
NAME, NOT INITIALSTYPE SAMPLE INDDATE COL. 30 SEPT 81DATE REC'D. 9/30 - FDUTIME REC'D. 12:20 PMTIME COL. 11⁰⁰ AMDATE COMPLETED 10/1/81SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTENAME OR FIRM NTU CIRCUITSADDRESS OR LOCATION DALE ST, FARMINGDALEPOINT OF COLLECTION SPDES Discharge Pool, Receiving Rinse Water

REMARKS/INSTRUCTIONS

TEST	RESULT	TEST	RESULT $\frac{\text{mg.}}{\text{liter}}$	TEST	RESULT $\frac{\text{mg.}}{\text{liter}}$
CONDUCT	umho	NITRATE-N		✓ COPPER	7.0
pH		NITRITE		IRON	
TEST	RESULT $\frac{\text{m.g.}}{\text{liter}}$	AMMONIA-N		MANGANESE	
ph. ALKALINITY		TKN		✓ CHROMIUM	2.02
ST. ALKALINITY		O-PO ₄ -P		✓ NICKEL	.2
CHLORIDE				ZINC	
FLUORIDE				MAGNESIUM	
CYANIDE		TOT. SOLIDS		CALCIUM	
		SUS. SOLIDS		✓ LEAD	2.4
SULFATE		DISS. SOLIDS		✓ CADMIUM	2.02
MBAS				SILVER	
C.O.D.				SODIUM	
T.O.C.				POTASSIUM	
				BARIUM	
		FIELD D.O.			
		FIELD TEMP			
		FIELD pH	ph 7		
		FIELD COND.	umho		

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTICE OF VIOLATION: N.Y.S. ENVIRONMENTAL CONSERVATION LAW

NTU Circuits Inc.
60 Dale Street
West Babylon, New York 11704

Date 12-28-81
SPDES NO. NY 0108260
Lab No. 11-81-271
Field No. 5 DO 25-11

Gentlemen:

On 11-25-81 samples of industrial waste were taken from your SPDES discharge pool, southside of NTU, actively receiving process waste. Upon analysis, the following parameters were found in concentrations above the maximum allowed in your SPDES permit or in groundwater effluent standards:

- | | |
|----------------------|-----|
| 1. Copper - 9.0 mg/L | 6. |
| 2. Lead - 1.3 mg/L | 7. |
| 3. pH - 3 | 8. |
| 4. | 9. |
| 5. | 10. |

Please be advised that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please be further advised that the discharge of any water from an industrial process to the groundwater of Suffolk County without having first obtained a State Pollutant Discharge Elimination System (SPDES) permit for that discharge is also a violation of the N.Y.S.E.C.L. and S.C. Sanitary Code, Art. 12.

If you do not already possess a valid SPDES permit for the above discharge, then you should apply immediately, through this office, for said permit.

Since the above noted violations may subject you to legal action, it is expected that these violations cease immediately. A reinspection in the near future will determine your compliance in this matter.

Very truly yours,

(SEE REVERSE SIDE FOR
STANDARDS)

John H. Finkenberg
Sr. Sanitarian
Environmental Pollution Control
JHF/cc

Central Islip, N. Y. 11722

FIELD

LABORATORY

FIELD NO.

LAB NO.

COL BY

TYPE SAMPLE

NAME, NOT INITIALS

DATE COL.

DATE REC'D.

TIME COL.

TIME REC'D.

DATE COMPLETED

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

NAME OR FIRM

ADDRESS OR LOCATION

POINT OF COLLECTION

MARKS/INSTRUCTIONS

TEST	RESULT	TEST	RESULT	mg. liter	TEST	RESULT	mg. liter
CONDUCT	umho	NITRATE-N		✓	COPPER	9.0	
pH		NITRITE			IRON		
TEST	RESULT	mg. liter	TEST	RESULT	mg. liter	TEST	RESULT
AMMONIA-N			MANGANESE				
TKN			CHROMIUM	2.02			
0-PO ₄ -P			NICKEL	2.1			
			ZINC	.1			
			MAGNESIUM				
			CALCIUM				
			LEAD	1.3			
			CADMIUM	2.02			
			SILVER	2.02			
			SODIUM				
			POTASSIUM				
			BARIUM				
			FIELD D.O.				
			FIELD TEMP				
			FIELD pH	7.3			
			FIELD COND.	umho			

COUNTY OF SUFFOLK



DEPARTMENT OF HEALTH SERVICES

NOTICE OF VIOLATION: N.Y.S. ENVIRONMENTAL CONSERVATION LAW

NTU Circuits
60 Dale Street
West Babylon, New York 11704

Date 1-19-82
SPDES NO. _____
Lab No. 12-81-116
Field No. 1 EJ 12-14

Gentlemen:

On 12-14-81 samples of industrial waste were taken from your storm drain on the south side of the building. Upon analysis, the following parameters were found in concentrations above the maximum allowed in your SPDES permit or in groundwater effluent standards:

- | | |
|---------------------|-----|
| 1. Copper - 10 mg/L | 6. |
| 2. Iron - 1.3 mg/L | 7. |
| 3. Lead - 3.0 mg/L | 8. |
| 4. | 9. |
| 5. | 10. |


Please be advised that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law. Please be further advised that the discharge of any water from an industrial process to the groundwater of Suffolk County without having first obtained a State Pollutant Discharge Elimination System (SPDES) permit for that discharge is also a violation of the N.Y.S.E.C.L. and S.C. Sanitary Code, Art. 12.

If you do not already possess a valid SPDES permit for the above discharge, then you should apply immediately, through this office, for said permit.

Since the above noted violations may subject you to legal action, it is expected that these violations cease immediately. A reinspection in the near future will determine your compliance in this matter.

Very truly yours,

(SEE REVERSE SIDE FOR
STANDARDS)


John H. Finkenberg
R. Sanitarian
Environmental Pollution Control
JHF/cc

Central Islip, N. Y. 11722

45 JETSON LANE Box G

XXXXXXXXXXXXXXXXXXXX

(816) 234-1822

FILE NO. LET 12-14
 COL. BY JOHNSON
 NAME, NOT INITIALS
 DATE COL. 12-14-81
 TIME COL. 12:10 PM

LABORATORY
 LAB NO. 10-3-1
 TYPE SAMPLE 210
 DATE REC'D. 12-14-81
 TIME REC'D.
 DATE COMPLETED 11/13/81

P. 28 10/28
 10/28

SUFFOLK COUNTY HEALTH SERVICES LABORATORY
 CHEMICAL EXAMINATION OF WATER, SEWAGE, INDUSTRIAL WASTE

NAME OR FIRM NTU CIRCUITS
 ADDRESS OR LOCATION 60 DALE ST. W. BABYLON
 POINT OF COLLECTION STORM DRAIN # 3
 REMARKS/INSTRUCTIONS (NOT FIELD PRESERVED - FIELD PH=7)

TEST	RESULT	TEST	RESULT ^{mg.} liter	TEST	RESULT ^{mg.} liter
CONDUCT	umho	NITRATE-N		✓ COPPER	(10) 1.0
pH		NITRITE		✓ IRON	(1.3) .6
TEST	RESULT ^{m.g.} liter	AMMONIA-N		✓ MANGANESE	
ph. ALKALINITY		TKN		✓ CHROMIUM	2.02
T. ALKALINITY		0-PO ₄ -P		✓ NICKEL	.1
CHLORIDE				✓ ZINC	.1
FLUORIDE				MAGNESIUM	
CYANIDE		TOT. SOLIDS		CALCIUM	
		SUS. SOLIDS		✓ LEAD	(3) .05
SULFATE		DISS. SOLIDS		✓ CADMIUM	2.02
NBAS	1.06			✓ SILVER	2.02
C.O.D.				SODIUM	
T.O.C.				POTASSIUM	
				BARIUM	
		FIELD D.O.			
		FIELD TEMP			
		FIELD pH			
		FIELD COND.	umho		

1.06

REFERENCE NO. 8

P 40618
SUPREME COURT OF THE STATE OF NEW YORK
COUNTY OF SUFFOLK

-----x
STATE OF NEW YORK,

Plaintiff,

- against -

NTU LABORATORIES, INC., d/b/a NTU
CIRCUITS, INC. and TIMOTHY WU,

Defendants.

:
:
:
: STIPULATION OF
: DISCONTINUANCE

: Index No. 81-16855
:
:

WHEREAS, the plaintiff has brought this proceeding against the defendants (hereinafter "NTU") for injunctive and monetary relief due to the alleged discharge of various heavy metals and chemical compounds from a factory used for the production of printed circuit boards for electronic equipment, and

WHEREAS, the parties, by their various authorized representatives, have met and agreed on a plan of settlement of the various disputed and differences between them, the effect of which is to make the continuation of this proceeding unnecessary.

IT IS THEREFORE, hereby stipulated and agreed, by and between the parties hereto and by their attorneys, that this proceeding is discontinued upon the following terms and conditions:

✓ 1. NTU CIRCUITS, INC. will immediately empty the sanitary pool adjacent to its factory at 60 Dale Street in the Town of Babylon, County of Suffolk, State of New York, designated

P.50718

as SP-A in Figure 1 attached hereto. The existing sludge at the bottom of the SP-A pool will be removed, a sulfide or lime slurry will be deposited in the bottom of the pool and mixed with the existing sand. The pool will be filled in with clean sand and the top of the pool will be paved over so as to make an impervious surface, not allowing rain to enter the pool area. The pipes leading to the pool will be grouted or made unusable. A new sanitary pool will be constructed at a location deemed acceptable (in writing) by the Suffolk County Department of Health and will henceforth hold and dispose of all the sludge generated by the facility in a manner acceptable to the said Suffolk County Department of Health.

2. For the sanitary drainage pools No. 2 and No. 3 located in Figure 1 attached, NTU will do the following at the time of completion of its treatment facility (which is being constructed in accordance with current SPDES permit schedule).

a. Pump the liquid waste from the pool through the treatment facility;

b. slurry bottom of the pool with a sulfide or lime slurry to precipitate any residual metal;

c. fill in the pool with clean sand and pave over so as to make the top surface impermeable to rain;

d. the existing pipes will be concreted or grouted so as to make them unusable.

3. The storm draining pools indicated as SD-7,

p 60718

SD-8 and SD-N1 (the latter being the pool closest to plating room) at the time of completion of the NTU treatment facility will be:

- a. emptied of liquid waste and that liquid waste passed through the treatment system;
- b. One foot of bottom sandy material will be removed and disposed of in an environmentally acceptable manner;
- c. bottom material will be replaced with clean sand (one to two feet in depth).

✓ 4. The NTU sanitary pool that receives waste from the water closet located in the northeast corner of the building will be exposed for sampling by the Suffolk County Department of Health. In the event such sampling reveals contamination, such pool will be treated as hereinbefore described for pools SD-7, SD-8, and SD-N1.

5. NTU agrees to obtain all necessary consents from its landlord which may be required in connection with the remedial measures hereinbefore set forth.

6. NTU hereby agrees to notify the Environmental Protection Bureau of the office of the Attorney General, State of New York, in writing, at such time as it either vacates the premises or in any other way alienates its interest, as tenant, therein, either by assignment of lease or otherwise.

7. All pipes leading to and from the pools to be

P-7818

terminated will be filled with grout or concrete by NTU.

8. NTU may install new storm and sanitary pools which are consistent with its needs and with the applicable regulations of the DEC, the Suffolk County Department of Health and any other appropriate agency. NTU agrees to obtain and exhibit to the Attorney General all licenses or permits which may be required in connection with such installation.


9. NTU will pay to the Attorney General the sum of \$2,500.00, the amount agreed to in the consent order entered into on March 28, 1980.


10. This proceeding is terminated without prejudice to either party.

11. Each party is to bear its own costs and disbursements with regard to this proceeding.

Dated: Mineola, New York
April 30, 1982

ROBERT ABRAMS
Attorney General of the State
of New York
Attorney for Plaintiff
By:


CYRIL H. MOORE, JR., Secretary
Assistant Attorney General


HOWARD P. FRITZ
15 Roslyn Road
Mineola, New York 11501
Attorney for Defendants

NTU LABORATORIES, INC.

By: 
TIMOTHY W. [unclear], President

REFERENCE NO. 9

908/8

FANNING, PHILLIPS & MOLNAR

Consulting Engineers

80 SKYLINE DRIVE

PLAINVIEW, NEW YORK 11803

RICHARD FANNING, P.E.
KEVIN J. PHILLIPS, P.E., Ph.D.
GARY A. MOLNAR, P.E.

516 938-2200
212 767-3337

February 21, 1984

Robert Abrams, Esq.
Attorney General
State of New York
Two World Trade Center
New York, New York 10047

Dear Mr. Abrams:

This letter is to notify you that NTU Circuits, Inc. has complied with their Stipulation of Discontinuance (Index No. 81-16855), dated April 30, 1982. All of the items specified in the Stipulation were fully complied with on November 29th, December 1st, 2nd and 3rd of 1983. Enclosed are reports by Fanning, Phillips and Associates (currently Fanning, Phillips & Molnar) and by the Suffolk County Department of Health Services detailing the events that transpired.

If there are any questions, please contact myself or Mr. Timothy Wu of NTU Circuits, Inc.

Thank you again for your time and attention to this matter.

Very truly yours,

Errol S. Kitt

ESK/ks
Enclosures

Errol S. Kitt
Assistant Project Engineer

p.105618

NTU CIRCUITS, INC.
COMPLIANCE TO STIPULATION OF DISCONTINUANCE

This report is in regard to the compliance of NTU Circuits, Inc. to its Stipulation of Discontinuance (Index No. 81-16855) dated April 30, 1982.

On November 29, December 1, 2, and 3 1983 Timothy Wu, President of NTU Circuits, Inc., David O brig and Joann Johnson, Environmental Health Sanitarians from the Suffolk County Department of Health Services, and Errol Kitt, Assistant Project Engineer from Fanning, Phillips and Molnar (consulting engineers for NTU Circuits) were present to supervise all work done by the contractor, Patterson Chemical Company, a certified waste hauler. It was confirmed that the work was conducted in an environmentally safe manner, and that all of the items in the Stipulation were addressed and correctly complied with. The actual proceedings are described as follows:

1. On November 29, storm drainage pool SD-7, shown in Figure 1 (also see Appendix A), was emptied of its liquid waste contents (5,000 gallons) by Patterson Chemical Company. This wastewater was then transported by Patterson to NTU's new building in North Bay Shore, where it was treated in NTU's industrial wastewater treatment system.
2. On December 1, storm drainage pools SD-8 and SD-N1 (see Figure 1 and Appendix A) were emptied of their liquid waste (1000 gallons) and again this wastewater was removed by Patterson, transported to NTU's new building and treated in its wastewater treatment system.
3. Also on December 1, sanitary pools No. 2 and No. 3, located in Figure 1 attached (also see Appendix A) were emptied of their liquid wastes. The wastewater

P-11 018

was transported to NTU's industrial wastewater treatment system and treated.

4. On December 2, over one foot of bottom sandy material was removed from each storm drainage pool (SD-7, SD-8 and SD-N1) and disposed of by Patterson in an environmentally acceptable manner. This bottom material was then replaced with approximately 1-2 feet of clean sand for each pool mentioned.
5. Also on December 2, both sanitary pools (No. 2 and No. 3) were slurried with lime to precipitate any residual metal. They were also filled in with clean sand and paved over so as to make the top surface impermeable. All of the existing piping for both pools was concreted as to render them unusable.
6. On December 3, all drums containing liquid waste that were on the premises were emptied, removed and transported by Patterson to a Treatment Storage and Disposal Facility (TSDF) to be disposed of in an environmentally safe manner.

Date: December 2, 1983
West Babylon, New York

Errol S. Kitt
Assistant Project Engineer
Fanning, Phillips and Molnar

Signed:

Errol S. Kitt

Timothy Wu
President, NTU Circuits, Inc.

Signed:











FIGURE 1- SANITARY POOL & STORM DRAIN LOCATIONS

P-13 of 18


APPENDIX A



914018



915818



81268

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
15 HORSEBLOCK PLACE, FARMINGVILLE, N.Y. 11738
(516) 451-4633

P-17918

NAME OF CITY NTU LABORATORIES		OWNER/OFFICER Timothy L. W.		PAGE 1 OF	
COMPANY NAME DBA NTU CIRCUITS, INC.		CONTACT		TEL.	
ANT ADDRESS 60 LAKE ST.		VILLAGE W. Babylon		TOWN Babylon	
MAILING ADDRESS				ZIP 11735	
DATE 2 Dec 93		TIME 9:15 AM		ORIG PERIODIC <input checked="" type="radio"/> RE <input checked="" type="radio"/> WASTE <input type="radio"/> NO WASTE <input type="radio"/> NON <input type="radio"/>	
INDUSTRY Mfg of Printed Circuit Boards		SEWAGE SYSTEM		PUBLIC PRIVATE	
DES OR DES PERMIT? YES NO PERMIT NO.		360 PERMIT? YES NO PERMIT NO.			
AVENGER PATTERSON Chemical		TEL.			
AVENGER APPROVED <input checked="" type="radio"/> YES <input type="radio"/> NO		PICK UP RECORDS AVAILABLE <input checked="" type="radio"/> YES <input type="radio"/> NO		RECORDS CONSISTENT WITH EXPECTED WASTE GENERATION YES NO	
HEATING SYSTEM-MFG NAME		FUEL TYPE		FIRING RATE	
FURNACE NAME		WASTE BURNED		RATE	
IN STORAGE YES NO		NUMBER STORED INDOORS OUTDOORS		TYPE OF MATERIAL STORED WASTE RAW	
STORAGE TANKS YES NO		NUMBER OF TANKS ABOVEGROUND UNDERGROUND		TYPE OF MATERIAL STORED WASTE RAW	
IN PROCESS TANKS YES NO		NUMBER OF OPEN PROCESS TANKS		ANY ART. XII VIOLATIONS YES NO	
<p>The following information is for the record of NTU Circuits concerning clean up of contaminated storm drains & sanitary pools as per consent order letter No. 81-16855.</p> <p>① Patterson Chemical arrived at approx. 11:45 AM to finish clean up at the NTU site. ② SD-8 was inspected and completed clean out approved. ③ SP-A was cleaned & treated with lime and cleared sand was filled to the top. Piping was concreted & pool filled over. ④ Sanitary drainage pools #2 & #3 were also treated as mentioned in ③. ⑤ SD-7, SD-8 & SD-11 were also treated in the same manner as ③. ⑥ 3 1/2 ft of sand</p>					
<p>PERMISSION IS GRANTED BY THIS FACILITY TO THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES TO CONDUCT ROUTINE SAMPLING OF CESSPOOLS, STORMDRAINS, AND OTHER DISCHARGE POINTS AT THE FACILITY.</p> <p>INSPECTION SCHEDULED ON OR AFTER _____ FAILURE TO CORRECT UNSATISFACTORY CONDITIONS BY REINSPECTION DATE MAY RESULT IN A HEARING AND/OR FINE.</p>					
SIGN. OF PERSON		TITLE		INSPECTOR	
C. REPORT				JoAnne Johnson	

PAGE TWO

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
15 HORSEBLOCK PLACE, FARMINGVILLE, NY 11738
(516) 451-4633

P18518

NAME OF FACILITY NTU		OWNER/OFFICER		PAGE 1 OF
COMPANY NAME		CONTACT		TEL.
STREET ADDRESS 60 DALE ST		VILLAGE WILKES	TOWN BABYLON	ZIP
MAILING ADDRESS				
DATE 3 DEC 83	TIME 10 AM	ORIG	PERIODIC <input checked="" type="checkbox"/>	WASTE <input checked="" type="checkbox"/>
INDUSTRY		NO WASTE	NON	SEWAGE SYSTEM
ES OR ES PERMIT?		YES	NO	PERMIT NO
SCAVENGER		YES	NO	PERMIT NO
SCAVENGER APPROVED		PICK UP RECORDS AVAILABLE	YES	NO
HEATING SYSTEM - MFG NAME		RECORDS CONSISTENT WITH EXPECTED WASTE GENERATION		
		YES NO		
		FUEL TYPE		
		FIRING RATE		
NAME		WASTE BURNED		
		RATE		
STORAGE YES NO		NUMBER STORED		TYPE OF MATERIAL STORED
		INDOORS OUTDOORS		WASTE RAW
STORAGE TANKS YES NO		NUMBER OF TANKS		TYPE OF MATERIAL STORED
		ABOVEGROUND UNDERGROUND		WASTE RAW
TANKS YES NO		NUMBER OF OPEN PROCESS TANKS		ANY ART. XII VIOLATIONS
				YES NO

The 55 gallon drums containing toxic & or hazardous wastes were pumped dry & transported to New Jersey for disposal. (20 x 55 gallon drums)

PERMISSION IS GRANTED BY THIS FACILITY TO THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES TO CONDUCT ROUTINE SAMPLING OF PESTHOLES, STORMDRAINS, AND OTHER DISCHARGE POINTS AT THE FACILITY.

INSPECTION SCHEDULED ON OR AFTER _____ FAILURE TO CORRECT UNSATISFACTORY CONDITIONS BY REINSPECTION DATE MAY RESULT IN A HEARING AND/OR FINE.

NAME OF PERSON REPORT

TITLE

Joanne Johnson
INSPECTOR

REFERENCE NO. 10

NUS CORPORATION
SUPERFUND DIVISION

PROJECT NOTES

TO:

DATE:

3/27/89

FROM:

David Heim

COPIES:

SUBJECT:

NTU Circuits


REFERENCE:

Reference # 10, Three-mile
Map from NTU Circuits
is located in a plastic sleeve
at the rear of the report.

REFERENCE NO. 11

710 720 730 740 750

SIGNIFICANT HABITAT OVERLAY NO. 1 OF 1
 NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
 DIVISION OF FISH AND WILDLIFE
 BUREAU OF WILDLIFE



PREPARED FOR: SIGNIFICANT HABITAT UNIT
 WILDLIFE RESOURCES CENTER
 DELMAR, NEW YORK 12054
 (518) 457-5782
 PREPARED BY: HABITAT INVENTORY UNIT


QUAD: NEW YORK
 SCALE: 1:250,000
 MARCH 1981
 REVISED: 11/6/81

430
 590 600 610 620

KEY

- (SW) SIGNIFICANT FOR WILDLIFE
- (SP) SIGNIFICANT FOR PLANTS
- (SB) SIGNIFICANT FOR WILDLIFE AND PLANTS
- (PW) POTENTIALLY SIGNIFICANT FOR WILDLIFE
- (PP) POTENTIALLY SIGNIFICANT FOR PLANTS
- (PB) POTENTIALLY SIGNIFICANT FOR WILDLIFE AND PLANTS
- (OT) OTHER (e.g. UNIQUE GEOLOGICAL FORMATIONS)

BOSTON
 BUREAU OF HABITAT
 INVENTORY



REFERENCE NO. 12

Hydrology of the Babylon-Islip Area Suffolk County Long Island, New York

Appendix 1.3-1
1 of 5

By E. J. PLUHOWSKI and I. H. KANTROWITZ

GEOLOGICAL SURVEY WATER-SUPPLY PAPER 1768

*Prepared in cooperation with the Suffolk
County Board of Supervisors, Suffolk
County Water Authority, and the New
York State Water Resources Commission*



the development of the all-metal airplane created a need for metal-fabricating shops. The post-World War II boom in electronics and electrical equipment found Suffolk County well prepared for the new industry owing to its established aviation firms, and the presence of the required skilled personnel.

AGRICULTURE AND VEGETATION

Although the value of crops produced and marketed in Suffolk County ranks highest of all the counties in New York State, agricultural production in the Babylon-Islip area is relatively small. The soils in the southern and eastern parts of the area have been classified by Lounsberry and others (1928, p. 13) as Sassafras Sandy Loam and Dukes Loamy Sand. These soils are not as productive as the soils in the northern and eastern parts of the county. The Sassafras Loam soils in the northwestern and north-central parts of the area are fairly productive. Proximity of this area to metropolitan markets spurred the development of numerous truck farms. The major crops produced by these farms are tomatoes, cauliflower, corn, string beans, peas, and cucumbers. Intensive urbanization, however, has reduced farm acreage so sharply that only a few farms remained in 1961.

Extensive tracts of natural vegetation are limited principally to the northern and eastern parts of the area. Much of the hilly area of the Ronkonkoma terminal moraine is forested with well-developed stands of deciduous trees. Low moisture retention characterizes the sandy, well-drained soils of the eastern part of the area and thereby precludes extensive forest development. Stands of scrub oak or pitch pine are common here in conjunction with an undergrowth of huckleberry, sweetfern, and wintergreen.

GEOLOGY

The composition, thickness, and geologic history of the deposits underlying the Babylon-Islip area determine the water-bearing characteristics, and the lateral and vertical extent of aquifers and aquicludes that form the hydrologic environment. The stratigraphy of the geologic formations is known almost exclusively from well records and samples, as outcrops, especially those of Cretaceous age, are rare.

STRATIGRAPHY

The Babylon-Islip area is underlain by unconsolidated sediments of Cretaceous, Tertiary, and Quaternary age, which lie on crystalline bedrock of Precambrian or early Paleozoic(?) age (table 1 and pl. 1). Directly overlying the bedrock is the Raritan Formation of Cretaceous age consisting of the Lloyd Sand Member and an unnamed clay

member. Above the Raritan Formation is a thick sequence of deposits of late Cretaceous age which is in part, correlative with the Magothy Formation of New Jersey, but also includes some formations that are younger than the Magothy (Perlmutter and Crandell, 1959, p. 1066). Pending a more specific identification, these beds are referred to as the Magothy(?) Formation. Deposits of Quaternary, and possibly Tertiary age overlie the Cretaceous deposits. These consist, from oldest to youngest, of the Mannetto Gravel of doubtful Tertiary (Pliocene ?) age, the Gardiners Clay, and the upper Pleistocene and Recent deposits.

TABLE 1.—Summary of stratigraphy of the Babylon-Islip area

Era	Period	Epoch	Geologic unit		Remarks
Cenozoic	Quaternary	Recent	Recent deposits		Miream, beach, and marsh deposits, small areal extent.
		Pleistocene	Upper Pleistocene deposits		Till and outwash deposits of the Wisconsin glaciation.
			Gardiners Clay		Fossiliferous marine clay of probable Sangamon age.
	Tertiary(?)	Pliocene(?)	Mannetto Gravel		Formerly believed to be an outwash deposit but now regarded as a stream-terrace deposit; small areal extent.
Mesozoic	Cretaceous	Late Cretaceous	Magothy(?) Formation		Interbedded sand, silt, and clay.
			Raritan Formation	Clay member	Dominantly clay but may contain some silt and sandy zones locally.
				Lloyd Sand Member	Sand, gravel, and interbedded clay and silt.
Precambrian and early Paleozoic(?)			Bedrock		Schist and gneiss containing some granitic intrusions.

THE BEDROCK

No wells in the Babylon-Islip area have reached bedrock. However, information obtained from wells in nearby parts of Long Island (Suter and others, 1949, p. 30-32, pls. 8 and 9) suggests that the bedrock in the area consists chiefly of schist and gneiss and contains some granitic intrusions. The bedrock is probably correlative in part with igneous and metamorphic rocks of Connecticut.

The bedrock surface dips southeastward at a rate of approximately 50 to 100 feet per mile. The altitude of the surface ranges from about 1,200 feet below sea level in the northwestern part of the area to about 1,800 feet below sea level in the extreme southeastern part. This bedrock surface represents the lower limit of the ground-water reservoir.

(Brice, Whitaker, and Sawyer, 1956, p. 32). Infiltration rates apparently depend chiefly on the interval between successive floodings, depth of water, and permeability of the basin surface. There are now more than 80 storm-water recharge basins in the Babylon-Islip area, and the number may be expected to increase as urbanization continues. The effectiveness of the basins as a means of recharging storm water to the ground-water reservoir from a suburban area is probably comparable to that of natural surface conditions prior to urbanization (Brice, Whitaker, and Sawyer, 1956, p. 2).

Public sanitary-sewer systems on Long Island discharge their effluent directly into tidewater. Because there are no such systems in the Babylon-Islip area (1961), theoretically all water withdrawn from the ground-water reservoir is returned to the ground. Two large sewage-leaching beds serve Pilgrim and Central Islip State Hospitals, and several smaller ones are at other institutions. The balance of domestic sewage is returned to the ground through cess-pools. Water pumped for industrial purposes is usually returned through diffusion wells and cesspools. A small amount of industrial pumpage containing contaminants is discharged into tidewater to avoid pollution of ground-water supplies.

Artificial recharge in the Babylon-Islip area counters the effect of urbanization by restoring the natural rate of infiltration of precipitation through the use of recharge basins and by returning most of the water pumped.

Because it is not practical to measure directly the rate of recharge to the ground-water reservoir, recharge must be determined by indirect methods. An approximate value for recharge is obtained by subtracting evapotranspiration losses and direct runoff from precipitation. The recharge to the ground-water reservoir in the Babylon Islip area as determined by this method is:

	Approximate annual rate (inches)
Precipitation.....	46
Evapotranspiration.....	21
Direct runoff.....	1
	—
Total water loss.....	22
	—
Recharge to ground-water reservoir.....	24

A recharge rate of 24 inches per year is equivalent to 1.1 mgd (million gallons per day) per sq mi or an annual total of about 215 mgd for the Babylon-Islip area. The bulk of this recharge occurs during late fall, winter, and early spring, when evapotranspiration is at a minimum.

THE

Research

24-00000

Fluoxetine

Keywords

Discussion

3

WEST!
ABY:??

DICTIONARY

7711 (b)(7)(C) Excluded from automatic declassification

1

Overview

References

Line of custody

14.255

1991-1992

1

1

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.

1000

100-443646-1

Document Number: 778


▶

FROM THE EDITOR

五、**其他**

MAP OF THE BABYLON-ISLIP AREA, SHOWING GENERALIZED SURFICIAL GEOLOGY, LOCATION OF WELLS, FROM FIRE ISLAND STATE PARK TO BRENTWOOD, SUFFOLK COUNTY, NEW YORK


51 416 1 62 904



EXPLANATION

[illegible]

REFERENCE NO. 13




Prepared in cooperation with the
SUFFOLK COUNTY WATER AUTHORITY
and
SUFFOLK COUNTY DEPARTMENT OF ENVIRONMENTAL CONTROL

MAP SHOWING ALTITUDE OF TOP OF RARITAN CLAY
SCALE 1:250,000
0 5 10 15 20 25 MILES
0 5 10 15 20 25 30 KILOMETERS
CONTOUR INTERVALS 25, 50, AND 100 FEET
DATUM IS MEAN SEA LEVEL

HYDROGEOLOGY OF SUFFOLK, COUNTY, LONG ISLAND, NEW YORK


By
H. M. Jenner and Julian Soren
1974

Appendix 13-2
1 of 4



MAP SHOWING ALTITUDE OF TOP OF LLOYD AQUIFER

SCALE 1:250,000



CONTOUR INTERVALS 25, 50, AND 100 FEET
DATUM IS MEAN SEA LEVEL

Prepared in cooperation with the
SUFFOLK COUNTY WATER AUTHORITY

and

SUFFOLK COUNTY DEPARTMENT OF ENVIRONMENTAL CONTROL


HYDROGEOLOGY OF SUFFOLK, COUNTY, LONG ISLAND, NEW YORK

By

H. M. Jensen and Julian Soren

1976

2 of 4



MAP SHOWING CONFIGURATION OF THE BEDROCK SURFACE

SCALE 1:250,000



COUNTour INTERVALS 25, 50, AND 100 FEET
DATUM IS MEAN SEA LEVEL

Prepared in cooperation with the
SUFFOLK COUNTY WATER AUTHORITY

and

SUFFOLK COUNTY DEPARTMENT OF ENVIRONMENTAL CONTROL

HYDROGEOLOGY OF SUFFOLK, COUNTY, LONG ISLAND, NEW YORK

By

H. M. Jensen and Julian Soren


1974

3 of 4

INTRODUCTION

WATER NEEDS OF SUFFOLK COUNTY

Water pumped from aquifers underlying Suffolk County (index map) is the sole source of water used for public supply, agriculture, and industry. The county's population grew from less than 200,000 in 1940 to 1.1 million in 1970. Most of the growth occurred after 1950. Ground-water pumpage increased from 40 mgd (million gallons per day) in 1950 to 155 mgd in 1970 (New York State Department of Environmental Conservation, written commun., June 1, 1971). The projected ground-water use for an anticipated population of 2 million in the county by 1990 is 300 mgd (New York State Conservation Department, 1970, p. 26-27).



INDEX MAP SHOWING LOCATION (SHADED)
OF SUFFOLK COUNTY

PURPOSE AND SCOPE

The large and growing demand for ground water in Suffolk County has created a need for a detailed knowledge of the geometry and the hydrologic characteristics of the ground-water reservoir. Mapping of subsurface geology and hydraulic heads in the aquifers are important prerequisites to obtaining this information. Maps of the subsurface geologic units of Long Island were first shown in a report by Suter and others (1949, pp. VIII to XXI). But those maps were highly generalized, because there were few data on deep borings and wells in the county when the report was prepared. Since 1949, additional data from many deep borings and wells in the county have been collected.

In 1968, as part of a continuing cooperative program of water-resources studies with the Suffolk County Water Authority and Suffolk County Department of Environmental Control, the U.S. Geological Survey began an updating of the hydrogeologic and hydrologic maps of all the county. The basic data in Jensen and Soren (1971), the first product of the program, are the basis for the hydrologic maps in this report.

ACKNOWLEDGMENTS

The authors appreciate the cooperation of well-drilling companies, their employees, and the many officials of public and private water companies who furnished geologic and hydrologic data for use in this report.

GEOLOGIC AND HYDROGEOLOGIC UNITS

Pleistocene glacial drift generally mantles the county's surface. Pleistocene deposits overlie unconsolidated deposits of Late Cretaceous age. The Cretaceous strata lie on a peneplain that was developed on Precambrian(?) crystalline rocks.

Major landforms include ridges, valleys, and plains. These landforms are roughly oriented in belts parallel to the county's length. The northern and the central parts are traversed by irregular sandy and gravelly ridges of terminal moraine. The crest of the northern ridge ranges in height from 100 to 300 feet above sea level and the crest of the central ridge from 150 to 400 feet. The highest altitudes in the inter-ridge area range from 100 to 200 feet. Irregular plains and rolling hills, formed from sandy and gravelly ground moraine and outwash deposits of sand and gravel lie in the area between the ridges. An outwash plain slopes at a near-uniform gradient from the southern base of the central ridge, which is about 100 feet above sea level, southward to Great South Bay and the ocean. Along the north shore, steep bluffs as high as 100 feet and generally narrow sandy and gravelly beaches face Long Island Sound. The barrier-bar system at the southernmost side of the county is composed of sandy beach and dune deposits. The highest altitudes of the barrier bars generally range from 10 to 45 feet.

The ground-water reservoir system of Suffolk County is composed of hydrogeologic units that include lenses and layers of clay, silt, clayey and silty sand, sand, and gravel. A hydrogeologic unit consists of a geologic unit or a group of contiguous geologic units classified by hydraulic characteristics. These units include aquifers, which are principal water sources, and confining layers, which separate the aquifers. The aquifers are, from the land surface downward, the upper glacial aquifer, the Magothy aquifer, and the Lloyd aquifer. The major areal confining layers are, in descending order, the Gardiners Clay, the Monmouth greensand, and the Raritan clay. The base of the ground-water reservoir is the crystalline bedrock. Characteristics of the geologic and the hydrogeologic units are summarized in the table, and the following data of hydrologic significance are shown on the maps: base of ground-water reservoir, altitudes of aquifers, altitudes and limits of confining layers, and distribution of surficial deposits. The hydrogeologic sections show the vertical relations of the units to each other.

The sharp angular shapes of some of the contours reflect the fact that in places the contours are drawn on stratigraphic tops of the hydrogeologic units and in places the contours are drawn on erosional surfaces. The sharp angles result from the juncture of a stratigraphic top and an eroded surface.

REFERENCE NO. 14

Appendix 1.3-3
198

LONG ISLAND WATER RESOURCES
BULLETIN NUMBER 1

RESULTS OF SUBSURFACE EXPLORATION
IN THE MID-ISLAND AREA OF WESTERN SUFFOLK COUNTY,
LONG ISLAND, NEW YORK

BY
JULIAN SOREN
U. S. GEOLOGICAL SURVEY

WITH A SECTION ON
POTENTIAL DEVELOPMENT OF GROUNDWATER
IN THE MID-ISLAND AREA

BY
PHILIP COHEN
U. S. GEOLOGICAL SURVEY

PREPARED BY
U. S. GEOLOGICAL SURVEY
IN COOPERATION WITH
SUFFOLK COUNTY LEGISLATURE
SUFFOLK COUNTY WATER AUTHORITY

PUBLISHED BY
SUFFOLK COUNTY WATER AUTHORITY

1971

UPPER CRETACEOUS SERIES

Raritan Formation

Lloyd Sand Member

The Lloyd Sand Member of the Raritan Formation comprises the Lloyd aquifer on Long Island. This unit consists mostly of beds and lenses of light- to medium-gray sand and gravelly sand, commonly containing small to large amounts of interstitial clay and silt, that are intercalated with beds and lenses of light- to dark-gray clay, silt, and clayey and silty sand.

Only two drill holes are known to have penetrated the Lloyd in the mid-island area. One hole partly penetrated the unit at the Pilgrim State Hospital, in Brentwood. The second hole, which is in the village of Lake Ronkonkoma, and which was one of the test holes drilled as part of this study, fully penetrated the unit. A log of the test hole describing lithology of the Lloyd is shown in table 1, S33379.

The surface of the Lloyd is roughly parallel to the bedrock surface. The Lloyd surface dips from an altitude of about 550 feet below sea level in the northwestern part of the area, to an altitude of about 1,250 feet below sea level in the southeastern part (pl. 2), and the unit's thickness ranges from about 260 feet to 360 feet from northwest to southeast, respectively. Plate 2 shows contours on the Lloyd surface. Plate 2 also shows contours on the bedrock surface; therefore, the Lloyd's thickness, in any part of the area, can be estimated by computing the local difference between the altitudes of the bedrock and Lloyd surfaces.

The Lloyd aquifer is moderately permeable. Its average horizontal permeability has been estimated by Lusczynski and Swarzenski (1966, p. 19), Isbister (1966, p. 20), and Soren (in press) to range between 400 and 500 gpd per sq ft (gallons per day per square foot) in Queens and Nassau Counties, west of the mid-island area. Warren and others (1968, p. 102) estimated the Lloyd's horizontal permeability to be 165 gpd per sq ft at the Brookhaven National Laboratory, about 12 miles east of the mid-island area. The section of Lloyd penetrated by the test well near Lake Ronkonkoma was fairly sandy and gravelly (table 1, S33379), and at this site the average horizontal permeability of the Lloyd probably is considerably more than 500 gpd per sq ft. Wells tapping the Lloyd in other parts of Long Island have been pumped at rates of as much as 1,600 gpm (gallons per minute), and the specific capacities of these wells (pumpage, in gallons per minute, divided by drawdown, in feet) have been reported to range from 3 to 40 gpm per foot of drawdown.

At present, there is no pumpage from the Lloyd aquifer in the mid-island area, mainly because of the great depth of the aquifer, and because more permeable aquifers are found at shallower depths. In addition to being at a greater depth, the water from the Lloyd commonly has undesirably high concentrations of iron.

Clay Member

The clay member of the Raritan Formation (commonly referred to as the Raritan clay) completely covers the underlying Lloyd aquifer in the mid-island area, and confines water in that aquifer. The Raritan clay consists mostly of beds and lenses of light- to dark-gray clay, silt, and clayey and silty fine sand (table 1). Thin to thick sandy beds commonly occur in the unit from place to place, but these beds do not have great lateral extent. Laminae and thin beds of lignite and pyrite and disseminated particles of these substances are common in the clay beds of the unit. The thickness of the Raritan clay increases to the southeast, and ranges from about 150 feet in the northwestern part of the mid-island area to about 200 feet in the southeastern part.

The surface of the Raritan clay is roughly parallel to that of the underlying Lloyd Sand Member. The altitude of the surface of the Raritan clay ranges from about 300 feet below sea level in the northwestern part of the mid-island area, to about 1,050 feet below sea level in the southeastern part (pl. 3).

Matawan Group-Magothy Formation, Undifferentiated

The Matawan Group-Magothy Formation, undifferentiated, comprises the Magothy aquifer of Long Island. Deposits in this unit consist of beds and lenses of light-gray fine to coarse sand, containing traces to large amounts of interstitial clay and silt, intercalated with thin to thick beds and lenses of light- to dark-gray clay, silt, and clayey and silty sand (table 1). The clay and silt beds commonly contain laminae and thin beds of lignite. Disseminated lignite and pyrite also are common in the sand beds of the aquifer. Gravelly coarse sand is commonly found in the basal part of the aquifer. This coarse zone ranges in thickness from 100 to 150 feet west of the mid-island area to 150 to 200 feet in the mid-island area. The basal zone also commonly contains abundant interstitial clay and silt and many thin to thick beds and lenses of clay, silt, and clayey and silty sand.

The surface of the Magothy aquifer (pl. 4) is not planar as are the surfaces of the underlying units. The Magothy surface was deeply eroded during Tertiary time, and probably was considerably eroded in Pleistocene time. Consequently, the depth to the Magothy aquifer and the aquifer's thickness cannot be predicted as accurately as the depths and thicknesses of the underlying units. Many control points in addition to those already known are needed to accurately map the upper surface of the Magothy aquifer.

The highly irregular character of the surface of the Magothy aquifer is shown in plate 4. The upper surface of the aquifer ranges in altitude from as high as about 200 feet above sea level to as low as about 500 feet below sea level. The Magothy was completely removed by erosion in a buried valley near the South Huntington area, and in that area upper Pleistocene deposits lie directly on the Raritan clay. This buried valley was called the "Huntington buried valley" by Lubke (1964, pl. 3), and as mapped by Lubke, the valley extended about 2-1/2 miles south of the Northern State Parkway.

458

source of the rock materials in the outwash deposits is manifold. As the glaciers moved southward to Long Island, they plucked the bedrock and soils of the surfaces they slid over. Rock materials were incorporated into the ice in contact zones and were also pushed along the glacial front. As the ice melted in late Pleistocene time, the various rock materials were carried away by broad coalescing streams and sheets of water. Consequently, the outwash deposits are stratified, and because of the varied materials carried by the glacier, these deposits consist of a heterogeneous suite of rock types. The great diversity of rock and mineral suites in the Pleistocene deposits, along with the chemically unstable (easily decomposed) rocks and minerals, commonly facilitates differentiation of glacial from the Cretaceous deposits on Long Island.

Outwash deposits underlie the plain in the mid-island area south of the Ronkonkoma terminal moraine, where the major source of glacial deposition was material from the Ronkonkoma ice advance. A readvance of the glacial front followed recession of the Ronkonkoma ice front and resulted in the formation of the Harbor Hill terminal moraine. Lakes were formed in depressions and valleys between the Ronkonkoma and Harbor Hill terminal moraines, and clayey materials were deposited in these lakes. The inter-morainal areas also contain recessional deposits of outwash and ground moraine (see the following section, "Ground-Moraine Deposits") from the Ronkonkoma and Harbor Hill deglaciations, and these materials buried the clayey lake deposits.

The outwash deposits are thickest in the buried valleys and thinnest where the Cretaceous surface is closest to land surface (pl. 5). These deposits generally extend below the water table, and are a major source of ground water. Outwash deposits comprise most of the so-called upper glacial aquifer of Long Island, and because these deposits of sand and gravel contain virtually no interstitial clay and silt, the upper glacial aquifer is the most permeable aquifer on Long Island. The estimated average horizontal permeability of the outwash deposits is about 1,000 to 1,500 gpd per sq ft (Luszczynski and Swarzenski, 1966, p. 17; and Soren, in press). Warren and others (1968, p. 75) computed the horizontal permeability of outwash to be about 1,300 gpd per sq ft at the Brookhaven National Laboratory, east of the mid-island area. A horizontal permeability for outwash as high as about 2,500 gpd per sq ft has been reported in Nassau County, west of the project area (Isbister, 1966, p. 29).

Public-supply and other high-capacity wells screened in glacial outwash on Long Island have yielded as much as 1,700 gpm, and reported specific capacities of such wells range from less than 10 gpm per foot of drawdown to as much as about 200 gpm per foot of drawdown; however, the specific capacities range mostly from 50 to 100 gpm per foot of drawdown. (See section "Yields of Individual Wells.")

- 48

the shorelines, the direction of flow is reversed, and ground-water movement is upward from the deeper aquifers toward the surface. Thus, because of the character of the flow system, under natural conditions virtually all the recharge to the Magothy and Lloyd aquifers in western Suffolk County originated in the mid-island area, and all of that recharge ultimately discharged from the ground-water system near the shorelines.

The movement of ground water through Long Island's aquifers in the horizontal direction is generally more rapid than movement in the vertical direction because of the occurrence of interbedded fine- and coarse-grained layers, and because the largest dimensions of unevenly shaped particles in the individual layers tend to be oriented horizontally. Approximate rates of ground-water movement can be computed from hydraulic gradients and estimated coefficients of permeability and porosities of the aquifers. In 1968, water in the upper glacial aquifers in the project area was moving horizontally at rates from less than 0.5 foot per day at points distant from centers of pumping, to hundreds of feet per day near the screens of pumping wells. At the same time, water in the Magothy aquifer was moving horizontally at rates from less than 0.2 foot per day at points distant from pumping, to hundreds of feet per day near the screens of pumping wells.

HYDRAULIC INTERCONNECTION OF AQUIFERS

The aquifers of Long Island are hydraulically interconnected. Layers of clay and silt within an aquifer or between aquifers serve to confine water below them, but they do not completely prevent the vertical movement of water through them. Ground water moves downward readily through coarse outwash deposits in the upper glacial aquifer. Vertical movement of water through the Magothy aquifer is impeded by beds and lenses of clay and silt. Because the clay and silt strata in the Magothy are not continuous, some water may move around lenses of this material in addition to moving slowly through the fine-grained strata.

The contact between the upper glacial and Magothy aquifers is not regular either in attitude or in composition of the contact surfaces. Glacial deposits in buried valleys are in lateral contact with truncated sandy beds in the Magothy. In the buried valleys water can laterally enter the Magothy at great depth directly from the glacial deposits, rather than the water having to move vertically to the same depth through less permeable Magothy beds. In the Huntington buried valley, glacial deposits extend completely through the Magothy aquifer to the underlying Raritan clay. (See plate 4.) In addition to the good hydraulic continuity between the upper glacial and Magothy aquifers in the buried valleys, good hydraulic continuity occurs between the aquifers outside the buried valleys where glacial sand and gravel deposits lie directly on Magothy sand beds. Thus, a fairly good hydraulic connection exists between the upper glacial and Magothy aquifers over large parts of the mid-island area, and the configuration of the piezometric surface of the Magothy aquifer is generally similar to that of the water table. However, in the mid-island area hydraulic heads in the Magothy are lower than those in the upper glacial aquifer because of the downward component of ground-water movement in the area.

The thick areally persistent Raritan clay that lies between the Magothy and Lloyd aquifers impedes but does not prevent downward movement of ground water into the Lloyd aquifer, and water in the Lloyd is tightly confined between the Raritan clay and bedrock. Downward leakage into the bedrock is negligible.

Figures 2 and 3 show hydrographs of wells screened in the upper glacial aquifer and the Magothy aquifer at the test-drilling sites in Brentwood and Nauppauge. At both sites, the heads in the deepest wells in the Magothy aquifer are about 2.5 to 3 feet lower than the heads in the shallowest wells in the upper glacial aquifer. The loss of head downward reflects the downward movement of ground water in the mid-island area. The hydrographs in figures 2 and 3 show that the heads in these two aquifers in the project area decrease at a fairly uniform rate with increasing depth. In addition, water-level fluctuations in the two groups of wells were very similar. Both of these facts, the uniform decrease in head and the similar water-level fluctuations, reflect the high degree of hydraulic interconnection between the upper glacial and Magothy aquifers.

The average vertical permeability of the Magothy aquifer is only poorly known. Estimates range from less than 1 to about 30 gpd per sq ft. Assuming that it averages about 5 gpd per sq ft in the mid-island area, the computed amount of downward ground-water movement through the Magothy aquifer in the vicinity of the ground-water divide in 1968 was about 0.4 mgd (million gallons per day) per square mile, and the estimated velocity of the downward movement was about 0.006 foot per day.

Because of the low permeability of the Raritan clay, the hydraulic head loss across this unit is very much larger than the head loss across a comparable thickness of the Magothy and upper glacial aquifers. At the easternmost test site in the village of Lake Ronkonkoma, wells were screened near the base of the Magothy and near the top of the Lloyd aquifers (pl. 5, section A-A', S33379-80). In 1968, the head near the base of the Magothy aquifer (about 45.5 feet above sea level) was about 11.5 feet higher than the head in the Lloyd aquifer (about 34 feet above sea level). Head losses across the Raritan clay at localities east and west of the Lake Ronkonkoma area differ considerably. At Upton, about 12 miles east of the mid-island area, the head loss across the clay was about 6 feet in 1968; and at Plainview (in Nassau County), about 3 miles southwest of Melville, the head loss across the clay was about 42 feet. The differences in head loss from place to place are largely a result of differences in the vertical permeability and thickness of the Raritan clay.

The head in the Lloyd aquifer at Lake Ronkonkoma in 1968 (about 34 feet above sea level) was higher than either of the heads in the Lloyd at Upton (about 30.5 feet above sea level) and at the Suffolk-Nassau boundary (about 27.5 feet above sea level). The head in the Lloyd at Terryville, about 7 miles northeast of the Ronkonkoma area was about 21 feet above sea level in 1968, and it was 19 feet above sea level at Fire Island State Park in 1968, about 13 miles to the southwest. These data suggest that water in the Lloyd aquifer is moving radially from the Lake Ronkonkoma area. The estimated rate of horizontal movement of water in the Lloyd aquifer in the project area in 1968, was on the order of 0.1 foot per day.




Figure 2.--Fluctuations of water levels in wells screened in the upper glacial aquifer and the Magothy aquifer at Brentwood, N. Y.

FLUCTUATIONS OF GROUND-WATER LEVELS

Fluctuations of water levels in the wells of the mid-island area reflect local variations in recharge to and discharge from the aquifers tapped by the wells. Therefore, changes in ground-water levels afford an insight into many aspects of the ground-water system. Furthermore, the information on water-level fluctuations can be used to help assess the impact of urbanization on the natural hydrologic system.




Figure 3.--Fluctuations of water levels in wells screened in the upper glacial aquifer and the Magothy aquifer at Hauppauge, N. Y.

Under natural conditions and in relatively undeveloped areas of Long Island, the water table fluctuates over a range of several feet during the year. Under such conditions, the water table has a rhythmic seasonal pattern; the lowest levels are in late autumn and highest levels are in early spring. This pattern of decline and recovery of the water table reflects the greatest losses of water through evapotranspiration during the growing season and the least such losses between growing seasons. The hydrologic systems in such undeveloped areas are in equilibrium, with inflow balancing outflow. However, if large amounts of water are continually pumped out of a ground-water system, the water table declines until equilibrium is reestablished at a lower level, reflecting a loss of ground water from storage and decreased subsurface and stream outflow from the system.

REFERENCE NO. 15



**New York State Atlas of
Community Water System Sources
1982**

NEW YORK STATE DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF PUBLIC WATER SUPPLY PROTECTION

New York State Atlas of Community Water System Sources

1982

NEW YORK STATE
DEPARTMENT OF HEALTH




TABLE OF CONTENTS

FORWARD		PAGE 1					
COUNTY	PAGE	COUNTY	PAGE	COUNTY	PAGE	COUNTY	PAGE
ALBANY	66	FRANKLIN	42	ONEIDA	32	SCHUYLER	18
ALLEGANY	14	FULTON	68	ONTARIO	28	SCHUYLER	18
BROOK	76	GENESEE	8	OSWEGO	12	SENECA	24
BROOME	20	GREENE	64	ORANGE	72	STELLEN	18
CATTARAUGUS	4	HAMILTON	48	ORLEANS	8	SUFFOLK	78
CAYUGA	24	HERKIMER	34	OSWEGO	20	SULLIVAN	70
CHAUTAUQUA	2	JEFFERSON	38	PUTNAM	68	TOMPKINS	18
CHEMUNG	16	KINGS	78	QUEENS	76	ULSTER	68
CHEMUNGO	22	LEWIS	30	RENSSELAER	68	WARREN	60
CLINTON	44	LIVINGSTON	10	RICHMOND	76	WASHINGTON	62
COLUMBIA	64	MADISON	28	ROCKLAND	74	WAYNE	28
CORTLAND	22	MONROE	8	ST. LAWRENCE	40	WESTCHESTER	74
DELAWARE	62	MONTGOMERY	68	SARATOGA	64	WYOMING	10
DUTCHESS	68	NASSAU	78	SCHENECTADY	68	YATES	12
ESSEX	48	NEW YORK	6				
		NIAARA	8				

LEGEND

BOUNDARIES AND PLACES

International
State
County
Town
Indian Reservation
City
Unincorporated Place
Village
Federal Reservation
Built-up Area (Over 25 000 population including any contiguous city or village)

CLASSIFICATION OF POPULATED PLACES

100,000 or more
50,000 to 100,000
12,500 to 50,000
2,500 to 12,500
250 to 2,500
250 or less

YONKERS
Levittown
Poughkeepsie
Hampton Bays
Bocsville
Canton

TRANSPORTATION

Highways
Divided Highways
Full Control of Access
Partial or No Control of Access
Undivided Highway
Interchange
Touring Route (State, U.S., Interstate)
or State Parkway
Touring Route Markers
State, U.S., Interstate

Railroads
Operating Line
Operator
Owner (If Other than Operator)
Company Having Trackage Rights
Service Discontinued
Reliance and Transfer
From Central
(Station)

Airports (Open to the Public, Military)
Runway under 4000'
Runway over 4000'

Rest Areas
Food, Gas, Rest Rooms
Gas, Rest Rooms
Rest Rooms
Parking Only

RECREATION FACILITIES

State or National Recreation Area
State Campground
State Boat Launching Site
State Canal Park
State Fish Hatchery
Other State Recreation Site

SUFFOLK COUNTY

ID NO	COMMUNITY WATER SYSTEM	POPULATION	SOURCE
-------	------------------------	------------	--------

Municipal Community

1	Bevon Water Corporation.	1150.	Wells
2	Brentwood Water District.	25812.	Wells
3	Bridgehampton Water Company.	1916.	Wells
4	Captain Kidd Water Company.	580.	Wells
5	Crab Meadow Beach.	50.	Wells
6	Culross Corporation (Culross Beach).	104.	Wells
7	Dering Harbor Village.	130.	Wells
8	Dix Hills Water District.	30000.	Wells
9	East Farmingdale Water District.	7850.	Wells
10	Fishers Island Water Works Corporation.	250.	Barlow, Middle Farms and Treasure Ponds, Wells
11	Greenlawn Water District.	40000.	Wells
12	Greenport Village.	6851.	Wells
13	Hampton Bays Water District.	9500.	Wells
14	Hawthorne - Maple Civic Association.	50.	Wells
15	Herod Point Association.	80.	Wells
16	North Shores Water Company.	5000.	Wells
17	Ocean Beach Village.	155.	Wells
18	Reeves Beach Water Company.	650.	Wells
19	Riverhead Water District.	9300.	Wells
20	Roanoke Water Corporation.	201.	Wells
21	Saltaire Village.	35.	Wells
22	Scott's Beach Water Company.	342.	Wells
23	Shelter Island Heights Association.	498.	Wells
24	Shirley Water Works.	3400.	Wells
25	Shorewood Water Corporation.	10000.	Wells
26	Soundview Association.	236.	Wells
27	South Huntington Water District.	51260.	Wells
28	Suffolk County Water Authority.	900000.	Wells
29	Sunhill Water Corporation.	3959.	Wells
30	Swan Lake Water Corporation.	1485.	Wells
31	Terrace-on-the-Sound.	400.	Wells
32	Woodbury Triangle Corporation.	800.	Wells

Non-Municipal Community

33	Aquebogue Mobile Home Court.	120.	Wells
34	Brookhaven National Labs.	3373.	Wells
35	Calverton Hills Owners Association.	897.	Wells
36	Cedar Lodge Nursing Home.	100.	Wells
37	Central Islip Psychiatric Center.	4525.	Wells
38	Crest Hall Health Related Facility.	120.	Wells
39	East Quogue Mobile Estates.	160.	Wells
40	Good Samaritan Hospital.	NA.	Wells
41	Greis Mobile Park.	70.	Wells
42	Hampton Gateway Apartments.	304.	Wells
43	Kings Park Psychiatric Center.	3100.	Wells
44	Knox School.	NA.	Wells
45	Lake Hurst Lodge Adult Home.	57.	Wells
46	Leier's Mobile Park.	350.	Wells
47	Little Flower Children's Services.	150.	Wells
48	Montauk Air Force Station.	10.	Wells
49	Napeague Trailer Park.	78.	Wells
50	Northport VA Hospital.	3000.	Wells
51	Oak Park Trailer Park.	50.	Wells
52	Oakland Ridge Mobile Park.	74.	Wells
53	Park Lake Rest Home.	46.	Wells
54	Peacock Alley.	35.	Wells
55	Peconic River Trailer Park.	90.	Wells
56	Peconic View Adult Mobile Home Park.	70.	Wells
57	Pinecrest Garden Apartments.	392.	Wells
58	Ramblewood Mobile Homes.	210.	Wells
59	Ridge Rest Home.	58.	Wells
60	Rocky Point Family Housing.	55.	Wells
61	Rollin Mobile Homes.	220.	Wells
62	St Joseph Convent - Long Island University.	1177.	Wells
63	Sam A Lewison Start Center.	40.	Wells
64	South Bay Adult Home.	40.	Wells
65	Southampton College.	1000.	Wells
66	Speonk Mobile Home Park.	50.	Wells
67	Suffolk Developmental Center.	3500.	Wells
68	Three Mile Harbor Trailer Park.	40.	Wells
69	Thurm's Mobile Estates.	450.	Wells
70	USCG Station - Moriches.	23.	Wells
71	Wes Dubicki Apartments.	NA.	Wells

NASSAU COUNTY

ID NO	COMMUNITY WATER SYSTEM	POPULATION	SOURCE
-------	------------------------	------------	--------

Municipal Community


1	Albertson Water District.	13500.	Wells
2	Bayville Village.	7500.	Wells
3	Bethpage Water District.	32000.	Wells
4	Bowling Green Water District.	12000.	Wells
5	Carle Place Water District.	11000.	Wells
6	Citizens Water Supply Company.	30000.	Wells
7	Deforest Drive Association.	25.	Wells
8	East Meadow Water District.	52000.	Wells
9	Farmingdale Village.	7946.	Wells
10	Franklin Square Water District.	20000.	Wells
11	Freeport Village.	38272.	Wells
12	Garden City Park Water District.	22596.	Wells
13	Garden City Village.	22927.	Wells
14	Glen Cove City.	24618.	Wells
15	Hempstead Village.	40404.	Wells
16	Hicksville Water District.	58000.	Wells
17	Jamaica Water Supply Company.	128448.	Wells
18	Jericho Water District.	64000.	Wells
19	Levittown Water District.	50000.	Wells
20	Lido-Point Lookout Water District.	10000.	Wells
21	Locust Valley Water District.	8500.	Wells
22	Long Beach City.	34073.	Wells
23	Long Island Water Corporation.	258936.	Wells
24	Manhasset-Lakeville Water District.	44730.	Wells
25	Massapequa Water District.	52000.	Wells
26	Mill Neck Estates Water Supply.	240.	Wells
27	Mineola Village.	20600.	Wells
28	New York Water Service.	172180.	Wells
29	Old Westbury Village.	3100.	Wells
30	Oyster Bay Water District.	10225.	Wells
31	Plainview Water District.	40000.	Wells
32	Plandome Village.	2616.	Wells
33	Port Washington Water District.	35000.	Wells
34	Rockville Centre Village.	25405.	Wells
35	Roosevelt Field Water District.	1640.	Wells
36	Roslyn Water District.	27500.	Wells
37	Sands Point Village.	3002.	Wells
38	Sea Cliff Water Company.	17850.	Wells
39	Sei-Bra Acres Water Supply.	80.	Wells
40	South Farmingdale Water District.	49900.	Wells
41	Split Rock Water Supply.	25.	Wells
42	Uniondale Water District.	25000.	Wells
43	West Hempstead-Hempstead Garden Water District.	32000.	Wells
44	Westbury Water District.	20050.	Wells
45	Williston Park Village.	8216.	Wells

Non-Municipal Community

46	Community Hospital at Glen Cove.	1350.	Wells
47	Planting Fields Arboretum.	90.	Wells
48	Stuart, Walker, Zimmer Water Supply.	41.	Wells

LOCATION OF COMMUNITY WATER SYSTEM SOURCES-1982


NEW YORK STATE DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF PUBLIC WATER SUPPLY PROTECTION




LOCATION OF COMMUNITY WATER SYSTEM SOURCES-1982

NEW YORK
DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF PUBLIC WATER SUPPLY PROTECTION

BRONX, KINGS, NASSAU, NEW YORK, QUEENS and RICHMOND COUNTIES



A T L A



SCALE 1:250,000


NORTH

REFERENCE NO. 16

1 YEAR 24-HOUR RAINFALL (inches)

The map displays the Great Lakes region with a grid of latitude and longitude lines. Contour lines indicate rainfall amounts in inches. Key features include:

- Great Lakes:** Superior, Michigan, Huron, Erie, and Ontario.
- Contour Lines:** Labeled with values such as 2.5, 3, 3.5, and 4.
- Geographic Labels:** "LAKES SUPERIOR", "LAKES MICHIGAN", "LAKES HURON", "LAKES ERIE", and "LAKE ONTARIO".
- Grid:** A grid of latitude and longitude lines is overlaid on the map.




**MEAN ANNUAL LAKE EVAPORATION
(In Inches)**


Based on period 1946-55


Based on period 1946-55

NORMAL ANNUAL TOTAL PRECIPITATION (Inches)



REFERENCE NO. 17



	TITLE: THREE MILE VICINITY MAP	
	SITE:	
DATE: 03/16/89	NTU CIRCUITS, INC., BABYLON, N.Y.	
TDD: 02-8811-13		
QUAD: AMITYVILLE, N.Y.	FIGURE NUMBER:	SCALE: 1" = 2000'

CONTROL NO:

DATE:

3/29/89

TIME:

1420

DISTRIBUTION:

N T L Circuits

BETWEEN:

Bob Parker

OF: Suffolk County

Dept. of Health Services

PHONE:

(516) 345-2517

AND:

David Lein (NUS)

DISCUSSION:

I asked Mr. Parker about any surface water uses for the Reguntatogue and Santapogue creeks. He said that there was no potable intake on either of these creeks, and to the best of ^{his} ~~their~~ knowledge, they were not used for recreational use either.

3-29

ACTION ITEMS:

Ground Water Route Work Sheet							
Rating Factor	Assigned Value (Circle One)		Multi-plier	HRS	Max. Score	PRO	
1 Observed Release	0	45	1	0	45	45	
If observed release is given a score of 45, proceed to line 4 . If observed release is given a score of 0, proceed to line 2 .							
2 Route Characteristics							
Depth to Aquifer of Concern	0	1 2 3	2	6	6		
Net Precipitation	0	1 2 3	1	2	3		
Permeability of the Unsaturated Zone	0	1 2 3	1	3	3		
Physical State	0	1 2 3	1	3	3		
Total Route Characteristics Score				14	15	—	
3 Containment	0	1 2 3	1	3	3	—	
4 Waste Characteristics							
Toxicity/Persistence	0	3 6 9 12 15 18	1	18	18	18	
Hazardous Waste Quantity	0	1 2 3 4 5 6 7 8	1	1	8	1	
Total Waste Characteristics Score				19	26	19	
5 Targets							
Ground Water Use	0	1 2 3	3	9	9	9	
Distance to Nearest Well/Population Served	0	4 6 8 10	1	30	40	30	
	12	16 18 20					
	24	30 32 35 40					
Total Targets Score				39	49	39	
6 If line 1 is 45, multiply 1 x 4 x 5				31,122	57,330	33,345	
If line 1 is 0, multiply 2 x 3 x 4 x 5							
7 Divide line 6 by 57,330 and multiply by 100	S _{gw} = 54.29				58.16		

Surface Water Route Work Sheet									
Rating Factor	Assigned Value (Circle One)				Multi- plier	HRS	Max. Score	PRO	
1 Observed Release	0	45			1		45		
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .									
2 Route Characteristics									
Facility Slope and Intervening Terrain	0	1	2	3		1	3		
1-yr. 24-hr. Rainfall	0	1	2	3		1	3		
Distance to Nearest Surface Water	0	1	2	3		2	6		
Physical State	0	1	2	3		1	3		
Total Route Characteristics Score								15	
3 Containment	0	1	2	3		1	3		
4 Waste Characteristics									
Toxicity/Persistence	0	3	6	9	12	15	18	1	18
Hazardous Waste Quantity	0	1	2	3	4	5	6	7	8
Total Waste Characteristics Score								28	
5 Targets									
Surface Water Use	0	1	2	3		3	9		
Distance to a Sensitive Environment	0	1	2	3		2	6		
Population Served/Distance to Water Intake Downstream	0	4	6	8	10		40		
	12	16	18	20					
	24	30	32	35	40				
Total Targets Score								55	
6 If line 1 is 45, multiply 1 x 4 x 5									
If line 1 is 0, multiply 2 x 3 x 4 x 5								64.350	
7 Divide line 6 by 64.350 and multiply by 100							$S_{SW} = 0.00$	0.00	

The surface water migration route was scored zero, as there is no overland migration pathway from the site to surface waters.

HRS

	S	S ²
Groundwater Route Score (S _{gw})	54.29	2946.94
Surface Water Route Score (S _{sw})	0.00	0.00
Air Route Score (S _a)	0.00	0.00
$S_{gw}^2 + S_{sw}^2 + S_a^2$		2946.94
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		54.29
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		31.38

WORKSHEET FOR COMPUTING S_M

PRO

	S	S ²
Groundwater Route Score (S _{gw})	58.16	3382.59
Surface Water Route Score (S _{sw})	0.00	0.00
Air Route Score (S _a)	0.00	0.00
$S_{gw}^2 + S_{sw}^2 + S_a^2$		3382.59
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		58.16
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		33.62

WORKSHEET FOR COMPUTING S_M